

AD-A096 440

ARMY ENGINEER WATERWAYS EXPERIMENT STATION VICKSBURG--ETC F/0 13/2
15 MILE ROAD/EDISON CORRIDOR SEWER TUNNEL FAILURE STUDY, DETROIT--ETC(U)

JAN 81 D ALBERT, G C HOFF, B LORENCE

NCE-IA-80-055

UNCLASSIFIED


WES/TR/6L-81-2


NL

1 of 5

05A


086410





LEVEL #

12



TECHNICAL REPORT GL-81-2

15 MILE ROAD/EDISON CORRIDOR SEWER TUNNEL FAILURE STUDY DETROIT AREA, MICHIGAN

Geotechnical Laboratory
U. S. Army Engineer Waterways Experiment Station
P. O. Box 631, Vicksburg, Miss. 39180

and

U. S. Army Engineer District, Detroit
Detroit, Mich. 48231

January 1981

Final Report

Approved For Public Release; Distribution Unlimited

DTIC
ELECTE

MAR 17 1981

A



Prepared for Environmental Protection Agency, Region 5
Chicago, Ill. 60604

THIS DOCUMENT IS BEST QUALITY AVAILABLE
THE COPY FURNISHED TO DDC CONTAINED A
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.

81 3 17 002

DDC FILE 60604

Destroy this report when no longer needed. Do not return
it to the originator.

The findings in this report are not to be construed as an official
Department of the Army position unless so designated
by other authorized documents.

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER Technical Report GL-81-2 ✓	2. GOVT ACCESSION NO. AD-A096 440	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) 15 MILE ROAD/EDISON CORRIDOR SEWER TUNNEL FAILURE STUDY, DETROIT AREA, MICHIGAN		5. TYPE OF REPORT & PERIOD COVERED Final report
7. AUTHOR(s) Dick Albert, George C. Hoff, Brian Lorence, Gerald B. Mitchell, Paul F. Mlakar, William L. Murphy, William E. Strohm, Jr.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U. S. Army Engineer Waterways Experiment Station P. O. Box 631, Vicksburg, Miss. 39180 and U. S. Army Engineer District, Detroit, P. O. Box 1027, Detroit, Mich. 48231		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS U. S. Environmental Protection Agency, Region V, 230 S. Dearborn St., Chicago, Ill. 60604		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE January 1981
		13. NUMBER OF PAGES 381
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Case history Structural behavior Field control tests (soils) Tunnel failures Laboratory tests Sewers.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The study consisted of field and laboratory investigations, construction evaluation, and geotechnical and structural analyses to determine the cause(s) of distress and failure of a 2600-ft section of 12-ft 9-in. diameter concrete-lined sanitary sewer tunnel in the Detroit, Mich., area. The work was performed at the request of the Environmental Protection Agency, Region V, Chicago, Ill. The report includes summaries of all pertinent construction records, results of all pertinent past and current field and laboratory tests (Continued)		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

20. ABSTRACT (Continued).

on construction and geotechnical materials, and detailed geotechnical and structural analyses based on observed conditions and measured parameters. Factors that could have potentially influenced or contributed to the distress were investigated; the findings eliminated certain possible factors and identified the essential causes and mechanisms. The conclusions are limited to those which could be made based on results of the analyses and facts and evidence documented in the report.

The section of tunnel that experienced distress is at a depth of approximately 65 ft and was mined through lake-bed deposits that contain strata of silt and fine sand. The water table is normally approximately 20 ft above the invert but was drawn down for construction. The silts and fine sands are highly susceptible to piping under even small heads. Some of the construction joints in the concrete liner were made without waterstops and concrete placement procedures were such that cold joints occurred in the liner.

The tunnel was completed and placed in service in 1972; however, the distress actually began immediately following construction as soon as the groundwater level was sufficiently high to initiate piping of soil through the open construction and cold joints. This piping took place over a significant period of time. As greater loss of support occurred, the concrete liner deformed, the joints opened wider, and more soil was allowed to pipe into the tunnel. These events progressed until the distress was manifested by the crack pattern found and by total collapse at Distressed Area 1 and partial collapse at Distressed Area 3. Varying degrees of distress were experienced along the 2600-ft section depending upon the location of the strata of piping soil with respect to open construction joints and/or cold joints.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

PREFACE

This study was conducted during the period March through August 1980 by the Geotechnical Laboratory (GL) and the Structures Laboratory (SL) of the U. S. Army Engineer Waterways Experiment Station (WES), and the Construction-Operations Division of the U. S. Army Engineer District, Detroit. The U. S. Army Corps of Engineers (CE) was authorized to perform the study by a letter dated 11 March 1980 from Region V, U. S. Environmental Protection Agency (EPA). The WES portion of the study was authorized by Detroit District's Intra-Army Order for Reimbursable Services No. NCE-IA-80-055 dated 27 March 1980.

The construction portion of this report was prepared by Messrs. D. Albert and B. Lence of the Construction-Operations Division, Detroit District. The geotechnical portion of this report was prepared by Messrs. W. L. Murphy and W. E. Strohm, Jr., of the Engineering Geology and Rock Mechanics Division (EGRMD), GL, and Mr. G. B. Mitchell, Chief, Engineering Group, Soil Mechanics Division (SMD), GL. Messrs. G. C. Hoff, Chief, Materials and Concrete Analysis Group, Concrete Technology Division (CTD), SL, and P. F. Mlakar of the Structural Mechanics Division (SMD), SL, prepared the structural portion.

COL Nelson P. Conover, CE, was Commander and Director of the WES during the preparation of this report. Mr. F. R. Brown was Technical Director. COL Robert V. Vermillion was District Engineer, Detroit District.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	
Unannounced	
Justification	
Distribution/	
Availability	
Dist	
A 23 MNI	

CONTENTS

	<u>Page</u>
PREFACE	1
PART I: INTRODUCTION	5
Study Authority	5
Purpose	5
Scope	6
Participants and Coordination	6
PART II: PROBLEM IDENTIFICATION	8
Background	8
Study Chronology	11
PART III: STUDY METHODOLOGY	14
Construction	14
Chronology	14
Plans and Specifications/Change Orders	15
Comments	19
Geotechnical	21
Investigations performed	21
Regional geology	29
Groundwater	32
Preconstruction conditions	37
Construction conditions	43
Postconstruction conditions	48
Postfailure conditions	49
Soil properties	87
Analytical studies	103
Structural	110
Concrete investigations	110
Summary of concrete investigations	142
Mechanics of the structural failure	142
Description of structural failure	143
Design loading	149
Resistance specified	152
Resistance constructed	155
Loadings imposed	160
PART IV: SUMMARY	181
Findings	181
Conclusions	182
REFERENCES	184
Figures 1-81	

Tables 1-21

APPENDIX A: BORING LOGS

APPENDIX B: GRADATION CURVES

APPENDIX C: CONSOLIDATION TEST DATA

APPENDIX D: DIRECT SHEAR TEST DATA

APPENDIX E: K_o \bar{R} TEST DATA

APPENDIX F: OVALING MEASUREMENTS

APPENDIX G: COMPUTER PROGRAM FOR RESISTANCE COMPUTATION

15 MILE ROAD/EDISON CORRIDOR
SEWER TUNNEL FAILURE STUDY
DETROIT AREA, MICHIGAN

PART I: INTRODUCTION

Study Authority

1. On 10 March 1980 Region V, U. S. Environmental Protection Agency (USEPA), requested that the U. S. Army Engineer Division, North Central (NCD), initiate a technical evaluation (hereinafter designated a study) to determine the cause of a sewer tunnel failure at 15 Mile Road/Edison Corridor, Sterling Heights, Michigan.

2. On 11 March 1980 Region V, USEPA, sent a letter to the U. S. Army Engineer District, Detroit, indicating that under the terms of Appendix A of Interagency Agreement No. EPA-78-D-X0267 the Corps was being assigned a special on-site inspection/study of the sewer tunnel failure.

3. On 12 March 1980 the NCD officially directed the Detroit District to implement the necessary steps required to perform a study of the factors that resulted in the tunnel failure.

4. In a hearing held on 12 March 1980 the Detroit District Engineer, Colonel Robert V. Vermillion, received an official request from the Honorable John Feikens, Chief Judge, U. S. District Court for the Eastern District of Michigan, to investigate the cause(s) of the tunnel failure. However, the Detroit District advised the Court that it had already been asked to perform a study of the failure for USEPA. Judge Feikens agreed that the Detroit District would conduct this study under the aforementioned interagency agreement.

Purpose

5. The purpose of this study was to determine the factor or

combination of factors that caused the sewer tunnel to experience distress.

Scope

6. By direction of the Court, this report is limited to findings of fact and the application of scientific and engineering principles to those facts to draw technical conclusions. This study was limited to a segment of sewer tunnel located in Sterling Heights, Michigan, between 15 Mile Road and the Red Run Drain (approximately 2600 ft), where three failed sections occurred. This segment was a part of the City of Detroit's Contract No. PCI-7, constructed between 10 February 1970 and 15 July 1972. This study reviewed and analyzed the following:

- a. Tunnel construction procedures and materials.
- b. Geotechnical and groundwater conditions.
- c. Structural soundness and design of primary and secondary tunnel linings.

Participants and Coordination

7. In response to the requests from EPA (Region V), Judge Feikens, and NCD, the Detroit District determined the resources, both in-house and Corps-wide, that would be needed to accomplish the tunnel failure study.

8. The failure study was designated as one of the District's top priorities. The District EPA Coordinator was assigned the task of initiating, directing, and coordinating the tunnel failure study. Some of the District's technical resources were made available to assist in the formulation of the entire study. Construction-Operations Division provided a project manager, an assistant project manager, and an on-site resident monitor. The project manager was responsible for coordinating all personnel and activities involved in the study, and acted as the central contact for the District. The assistant project manager assisted the project manager and performed major activities, such as

data collection, safety programming, and procurement processing. The on-site resident monitor observed the bypass (Contract No. CS-858) and temporary repair construction and assisted in the management and coordination of the Corps' field investigation. Construction Branch reviewed the contract and construction records to identify factors or construction difficulties that may have been related to the tunnel failure. The Engineering Division provided geotechnical and design engineers to assist in the review of the tunnel design assumptions and the actual tunnel construction utilized in Contract No. PCI-7.

9. Personnel of the U. S. Army Engineer Waterways Experiment Station (WES) in Vicksburg, Mississippi, were contacted to supplement the resources required to perform the study.

10. On 20 March 1980 the WES agreed to provide a team of professional experts, as required, to evaluate the geotechnical, structural, and construction factors that may have caused the tunnel failure. The scope of work performed by the WES personnel included:

- a. Visits to site, as necessary.
- b. Assistance in the identification, collection, and review of existing data essential to this study.
- c. Determination of additional data requirements (soil borings, concrete cores, etc.).
- d. Assistance in preparation of plan of study.
- e. Responsibility for testing and analyzing all data collected in the field investigation.
- f. Providing written evaluation on sewer tunnel design and construction.
- g. Providing written findings of facts on the causes of the tunnel failure.


PART II: PROBLEM IDENTIFICATION

Background

11. As mentioned previously, the segment of sewer tunnel where the failures occurred was part of Contract No. PCI-7. This contract consisted of the construction of approximately 13,633 ft of sewer tunnel. Contract No. PCI-7 was a part of a tunnel network constructed by the City of Detroit to serve Macomb and Oakland Counties. The network, which is several miles in length, had similar designs throughout and was built with the assistance of USEPA grant funds. The site location is shown in Figure 1, General Area Map.

12. The design for this sewer tunnel was prepared by the City of Detroit and is discussed in more detail later in this report. The design assumed that the tunnel would be uniformly loaded externally and be in perfect ring compression. The surrounding soil was assumed to have no shear strength. The concrete wall thickness was a function of the soil cover to the springline and the inside diameter of the tunnel. The compressive strength of the concrete, using these design assumptions, had a safety factor of about 7. For this tunnel, the inside diameter was specified to be 12 ft 9 in. and the wall thickness 16 in. The required concrete compressive strength, f_c , was computed to be 482 psi.

13. The contractor constructed this sewer by boring a circular tunnel with a mining machine and holding the soil in place with steel ribs and wood lagging (see Figure 2, Tunnel Cross Section). Steel forms were centered in the ribs and lagging of the primary lining, and concrete was dropped from the ground surface through baffled pipes to place the concrete lining. Generally, the concrete placements for the lining were 105 ft long. Keyways were formed at the construction joint for each concrete placement. The tunnel design did not provide for any steel reinforcing; however, when the concrete wall thickness was between 15 in. and 12 in., reinforcing was required. Thicknesses less than 12 in. were not allowed and re-mining was required to provide minimum wall thickness. The contractor sank deep wells to dewater the project



15 Mile Road-Edison Corridor Sewer Tunnel Failure

Sketch of Tunnel Crosssection

PRIMARY LINING = 4" Wood Lagging & 5 WF 16 Steel Ribs.




Figure 2. Tunnel cross section

area during construction. The initial specifications did not require the use of waterstops at construction joints, but during construction, the contractor received change orders to add waterstops. Waterstops are either metal (copper or stainless steel) or polymeric (rubber or vinyl chloride) appurtenances which are cast in the concrete of two different adjoining placements in such a manner that they span the joint between the two, preventing the passage of water or other liquids through that joint. The waterstop locations were determined in the field, based on soil conditions encountered during mining, and are given later in this report.

14. On 12 July 1972 the City inspected the substantially complete sewer tunnel and it appeared to be in an acceptable condition.

15. On 27 January 1980 the Detroit Water and Sewerage Department (DWSD) sewer safety crew performed an inspection of Contract PCI-7. The crew entered the tunnel through a manhole just south of 15 Mile Road, walked one mile southward, and exited from a manhole south of the center line of 14 Mile Road. It was during this inspection that the three distressed areas in the sewer tunnel were discovered (see Figure 3, Tunnel Plan and Elevation Sketch). No record of an inspection between 1972 and 1980 was found.

Study Chronology

16. On 8 February 1980 the Detroit District initiated an on-site monitoring assignment at the bypass construction site (Contract No. CS-858) located in the Edison Corridor between 15 Mile Road and the Red Run Drain, Sterling Heights, Michigan.

17. On 18 March 1980 Detroit District personnel were in the DWSD offices collecting contract documentation and history concerning Contracts No. PCI-7 and No. CS-858. On 30 May 1980 a letter was transmitted to the DWSD requesting clarification on some aspects of the contract documentation and history reviewed. On 20 June 1980 the DWSD provided a written response to our inquiries. The following contract documentation and historical items were reviewed and are on file




Figure 3. Tunnel plan and elevation sketch

at the Detroit District and the WES:

- a. A set of Contract No. PCI-7 as-built plans and specifications.
- b. The plans for Contract No. CS-858 (no specifications issued for this construction; work under emergency status).
- c. Inspector's reports and daily reports for PCI-7.
- d. Soil data and boring logs for PCI-7 and CS-858.
- e. Design calculations for Contract No. PCI-7.
- f. Shop drawings for PCI-7.
- g. Groundwater data collected during Contract No. CS-858.
- h. Tunnel profiles proposed under CS-858.

18. The City made a videotape of the distressed areas and the Detroit District made complete pictorial surveys of the tunnel (Contract No. PCI-7, Sta 136+00 to Sta 110+00) which are on file at the Detroit District and the WES.

19. On 21 April 1980 a WES drilling crew and equipment arrived at the bypass construction site. All but two of the soil borings were completed and the samples delivered to the WES for analysis and testing on 21 May 1980. Samples from the two remaining soil borings and all the concrete cores were delivered to the WES on 25 June and 9 July 1980. A large piece of concrete was taken out of Distressed Area No. 1 and delivered to the WES on 7 August 1980.

20. During the period May-August 1980, the WES performed laboratory tests on the soil and concrete samples obtained from the site.

21. On 15 June 1980 a plan of study was presented to the USEPA (Region V) and NCD. This plan of study presented the analysis approach by which the factors contributing to the tunnel failure would be determined.

PART III: STUDY METHODOLOGY

Construction

Chronology

22. On 16 December 1969 the Common Council for the City of Detroit approved the award of Contract No. PCI-7 to the low bidder, Michigan Sewer Construction Company, in the amount of \$8,977,765. This contract consisted of the construction of approximately 13,633 ft of sewer tunnel. The north and south limits of this contract were designated as Sta 136+33 and Sta 0+00, respectively. (This study was restricted to that segment of tunnel between Sta 136+02 and Sta 103+00 in which three distressed areas occurred.)

23. On 10 February 1970 the City issued a start work order to the contractor. The contractor started this construction project by constructing a work shaft at Sta 51+66. The contractor intended to mine north and south from this shaft. However, mining in the north heading was halted on 1 September 1971 when water and mud from the Red Run Drain flooded the tunnel at approximately Sta 103+23.

24. On 13 October 1971 the contractor placed a "Caldwell" mining machine in the work shaft at Sta 136+02. The contractor started mining this new south heading on 27 October 1971.

25. Between 27 October 1971 and 24 May 1972, the contractor mined the new south heading between Sta 135+86 and Sta 103+63. See Table 1, Excavation Summary, for a detailed breakdown of starts and stops of mining, feet mined per day, number of steel ribs between stations, soil conditions encountered, problems encountered, and significant events such as remining and resetting of ribs. These data were obtained by a thorough search of all available records.

26. Between 13 March 1972 and 21 June 1972, the contractor placed the concrete lining between Sta 135+82 and Sta 103+47. See Table 2, Concrete Summary, for a detailed breakdown of the concrete placement dates, stationings, durations, operations, problems, and notes such as waterstop locations and resteel installation. These data

were also obtained during the records search.

Plans and Specifications/Change Orders

27. The plans and specifications for Contract No. PCI-7 were collected and reviewed for this study; however, they were not included in the body of this report. These plans and specifications will be kept on file in both the Detroit District Office and the WES for review by interested parties.

28. Some changes were made to the contract plans and specifications. The documented contract change orders are as follows:

- a. Change Order No. 1 extended the contract substantial completion date of 1 July 1971 to 21 July 1971, and the final completion date of 30 September 1971 to 20 October 1971. This time extension was precipitated by the occurrence of an operating engineers strike (Local 324) from 1 September 1970 to 20 September 1970. The contractor requested a 26-day time extension but the City only allowed him a 20-day extension. The total contract price was not affected by this change order. The issuance of the change order was approved by the Board of Water Commissioners on 26 July 1971.
- b. Change Order No. 2 provided for the installation of waterstops in certain portions of the tunnel where unacceptable soil conditions were encountered. The waterstops were intended to prevent imminent infiltration of water and soil into the tunnel and thereby eliminate potential damage due to loss of ground support (see Table 2, Concrete Summary, for waterstop locations). The contractor was to install waterstops, where required, on a cost plus-limited amount basis. The cost increase for this change was not to exceed \$3400 (\$2000 for split bulkhead and \$1400 for the waterstops; approximately 7 waterstops were anticipated). No time extension was allowed for this change. The issuance of this change order was approved by the Board of Water Commissioners on 10 January 1972 and by the City's Common Council on 18 January 1972.
- c. Change Order No. 3 provided for the construction of one interceptor bulkhead south of the Red Run Drain. This change deleted a bulkhead from Contract No. PCI-6 and allowed the construction of an exit shaft between these two adjoining contracts. Accordingly, a deduction of \$1000 was approved for Contract No. PCI-6. The bulkhead was relocated into Contract No. PCI-7. No time extension was allowed for this change order. The issuance of this change order was approved by the Board of Water

Commissioners on 20 March 1972 and by the City's Common Council on 28 March 1972.

- d. Change Order No. 4 provided for the installation of waterstops in all remaining concrete construction joints and the alteration of three steel bulkheads to accommodate the waterstops. This change order increased the contract price by an amount not to exceed \$9600, with the final price to be fixed by a confirming change order when the cost was determined (\$6000 for the three bulkheads and \$3600 for the waterstops; approximately 18 waterstops were anticipated). No time extension was allowed under this change order. The issuance of this change order was approved by the Board of Water Commissioners on 30 May 1972 and by the City's Common Council on 13 June 1972.
- e. Change Order No. 5 established the final price for Change Orders Nos. 2 and 4. The work under the initial two change orders (Nos. 2 and 4) had been completed and the total amount owed the contractor was determined to be \$11,078.18. The work under this change order included alteration of 4 split bulkheads and installation of 19 waterstops. No time extension was allowed under this change order. The issuance of this change order was approved by the Board of Water Commissioners on 29 January 1973.
- f. Change Order No. 6 deleted the required bulkhead on Contract PCI-7 at the junction between Contract Nos. PCI-7 and PCI-12A. The contractor requested deletion of the bulkhead because of coordination problems with adjoining work performed by others. The City agreed that it would be more advantageous to have the bulkhead constructed under Contract No. PCI-12A. This change order reduced the contract price by \$1500. This change order had no effect on the contract completion dates.

29, Certain deviations to the contract plans and specifications occurred during the construction of this sewer tunnel. These deviations are as follows:

- a. Detailed Specifications, Section 1.III.3, Tunnel Excavation, Paragraph C, Full Circle Steel Ribs, page 1.7, required that no part of ribs will, when in place, protrude into the specified tunnel wall thickness and that rib sections shall fit closely for bolted connections at segmental and transverse joints. Also, the bolt connections were to be capable of developing the full strength of the ribs. At least some of the ribs which were installed, as documented by the during-construction photographs, and ribs removed at the access shaft during the

bypass construction had bearing plates that extended past the interior flange of the ribs and into the tunnel wall thickness. The full circle ribs were oriented so that bearing plates were located at the invert, at the 10 o'clock and the 2 o'clock positions. As the mining machine advanced, the steel ribs were hydraulically jacked out against the surrounding soil. This jacking left a space between the bearing plates at the 10 and 2 o'clock positions. Steel spacers were placed between the bearing plates. The approved shop drawing shows the rib bearing plates with bolt holes located on both sides of the rib web. However, construction photographs show that the bolt holes were actually located on that portion of the bearing plate which extended past the interior flange of the ribs. During-construction photographs confirm the above-mentioned condition.

- b. Under this same section of specifications, a requirement was added by Bulletin No. 5 where in no case shall the soil be supported only by ribs and wood lagging for a period longer than seven consecutive days. The Inspector's Reports indicate that there was approximately a 5-month delay before the concrete lining was placed inside the full circle rib and wood lagging. Mr. Beckham's 20 June 1980 response to our 30 May letter of inquiry confirmed that this time lag was approved by the City.
- c. Detailed Specifications, Section 2.II.3, Fine Aggregate (Sand), Paragraph A, Physical Requirements, page 2.2, required testing for organic impurities, tensile strength, and soundness. The test reports for these physical requirements were not found during our review of the contract documentation and files.
- d. Detailed Specifications, Section 2.II.4, Coarse Aggregate, Paragraph A, Physical Requirements, page 2.4, required testing for soundness, loss by washing, other deleterious substances, and thin and elongated pieces. The test reports for these physical requirements were not found during our review of the contract documentation and files.
- e. Detailed Specifications, Section 2.II.4, Coarse Aggregates, Paragraph B, Gradation, page 2.5, required that only 60 to 90 percent of the 6A coarse aggregate pass the 1-in.-sq sieve openings. All the Metro Water Department-Detroit Division of Engineering Mechanical Analysis Reports showed that 100 percent of the 6A coarse aggregate passed the 1-in.-sq sieve openings.
- f. Detailed Specifications, Section 2.III.2, Forms, Paragraph E, Removal of Forms, page 2.10, specified that the

time of removal of forms shall be at least 36 hours after concrete placement was terminated. Discussions with the City of Detroit's inspector on this construction contract disclosed that the majority of the south heading utilized 140 ft of tunnel forms. A review of the City's records indicates that concrete was generally placed in 105-ft segments. The practice was to strip the remaining 35 ft of the second to the last placement and the upstream 70 ft of the last placement to form the next 105 ft. This left 35 ft of forming in place on the downstream end of the last placement. When concrete was placed every day, the day shift would strip forms, reset forms, and place concrete. The second shift cleaned up ahead of forms, removed form bolts, and began stripping forms (no third shift). In the area of this study, the duration between concrete placements was approximately 16 hours. This means that the last placement had 70 ft of forms stripped within 16 hours after placement, less than one-half the specified minimum.

- g. Detailed Specifications, Section 2.III.6, Mixing Concrete, Paragraph F, Samples for Concrete Strength, page 2.16, specified that three standard test cylinder specimens be made for each run of 50 cu yd or less, and for each 100 cu yd poured. The available contract records on concrete sampling show that the average concrete pour in the study area was approximately 260 cu yd for which only two cylinders were normally made.
- h. Detailed Specifications, Section 2.III.7, Placing Concrete, Paragraph B, Concrete Drop Holes, page 2.17, required that the drop pipe have a pocket or remixing box at the lower end to permit remixing of the concrete before it flowed into the forms. Also, this paragraph specified that a flexible pipe or boot be connected to the side of the remixing box on the drop pipe (extending around the arch of the forms and down to the springline) to reduce the free fall of the concrete. Mr. Beckham's 20 June 1980 response letter states that the drop pipe end consisted of a 90-deg elbow and no mention was made of the pocket for remixing nor the use of a flexible pipe or boot. A discussion with the City's inspector confirmed that the concrete was placed through a drop pipe without using the specified pocket and flexible pipe or boot.
- i. Detailed Specifications, Section 2.III.8, Construction Joints, Paragraph A, General, page 2.18, specified that the contact surface of any joint would, after being cleaned, be coated with a waterproof material before adjoining concrete was placed. In particular, the vertical construction joints would be coated with a cold

bituminous, fibrous compound Flinkote #200 or equal. Inspections made during our field investigation and cores taken at joints revealed no mastic coating.

- j. Detailed Specifications, Section 2.IV.1, Core Tests - Tunnel Sewers, page 2.22, required that three 6-in.-diam cores be taken for each 1000 ft of tunnel sewer or fraction thereof. Also, these cores were to be measured for length and tested for compressive strength. Mr. Beckham's 20 June 1980 response letter verified that the required number of cores were not taken and, of the cores taken, no test results or records of visual observation were found.

Comments

30. The Construction Branch of the Detroit District has made a comprehensive evaluation of the construction techniques and procedures used on this project. Several pertinent comments were generated during the evaluation. These comments are as follows:

- a. A 4- to 5-month time lag between setting ribs and lagging and placement of the concrete lining occurred on this project. Current sewer tunnel construction contracts in the DWSD do not allow such long lag periods.
- b. The Portland Cement Association in their "Suggested Specifications for Plain and Reinforced Concrete, 1969" states that "concrete shall be deposited as nearly as practicable in its final position to avoid segregation due to flowing." On this project concrete was lowered to the tunnel from the ground surface through drop holes. In the average placement length of 105 ft, two drop holes were installed. One drop hole was located about 7 ft downstream from the previous pour. The second drop hole was located about 50 ft downstream of the first drop hole. Discussions with the City's inspector revealed that the first drop hole was used for the entire pour unless it became plugged. Therefore, concrete in this project was normally transported to distances up to 100 ft in the forms.
- c. The Portland Cement Association in the same reference as above suggests a minimum of two concrete cylinder specimens for each test at each age, and not less than one test for each 150 cu yd of concrete. The Report of ACI Committee 301, "Specifications for Structural Concrete," recommends three specimens for each test and one test be made for each 100 cu yd of concrete. On this project it was common practice to take only two specimens for concrete placements in excess of 250 cu yd.

- d. According to the Inspector's Reports, the machine mining was higher than the specified grade and off line to the west by as much as 1.75 ft in Distressed Area No. 1. The high areas were generally remined. During the remining, the ribs and lagging were removed and modified ribs were reinstalled.
- e. The hydraulic system of the "Caldwell" mining machine was continually failing.
- f. Between 2 February 1972 and 21 June 1972, water seepage was experienced through the primary liner throughout the mined tunnel. On 30 May 1972, mud and water entered the tunnel during mining through a drop hole drilled through a field tile (Sta 118+57). On 21 June 1972 flooding occurred in the tunnel in the area of Sta 103+67.
- g. On 15 December 1971 the rear shield of the "Caldwell" mining machine developed a radial crack, and on 8 January 1972 the tail section broke.
- h. The Inspector's Reports note that a void occurred over the mining machine from Sta 109+36 to Sta 103+63. Grouting was done over the mining machine at Stas 104+30, 104+25, and 104+10.
- i. Overmining with mining machine occurred between Sta 109+36 and Sta 103+83.5.
- j. Ribs from Sta 107+40 to Sta 107+65 were deflected by excessive loading and were braced.
- k. The Inspector's Reports show that voids occurred between steel forms and rib and lagging during concrete placement at Stas 134+92 and 126+12. Voids were filled at a later date.
- l. Cold joints were noted in the Inspector's Reports at Sta 130+17 (unspecified locations), Sta 130+35 (east and west sides), Sta 130+10 (lower east quarter), Sta 123+50 (invert), Sta 123+30 (west side), Sta 118+62 (east and west lower quarters), Sta 114+42 (east and west sides), and Sta 112+32 (east and west sides).
- m. The Inspector's Reports state that pour progress was slow for concrete placements from Stas 133+32 to 132+27, 129+12 to 128+07, 127+02 to 125+97, and 119+67 to 118+62. This slow progress was caused by late arrival of mix trucks and plugged drop pipes. The Inspector's Reports regarding the placement starts and terminations indicate that an average rate of 65 cu yd/hr constituted normal progress. Slow progress would appear to be something less than this rate.
- n. The Inspector's Reports stated that the concrete between Sta 129+12 and Sta 128+07 was placed "wet" and that

groundwater was entering the forms. No slump test was performed on the concrete. It is assumed that "wet" concrete was a visual evaluation of high slump.

Geotechnical

31. Geotechnical studies included review and analyses of pertinent information from the City and other sources, site visits, surface borings, tunnel wall holes, laboratory tests of soil samples, and analytical studies. The studies were made to develop the geology of the site, groundwater conditions, soil stratification, soil properties and in situ soil conditions, and ground pressures. The main objective was to assess the in situ soil conditions before, during, and after construction, and after failure, and their possible bearing on the cause of tunnel distress. The studies made and pertinent results are summarized in this section.

Investigations performed

32. The initial step was a geotechnical plan of study which was based on a review of a preliminary copy of CS-858 contract drawings for the temporary bypass and pumping shaft containing boring logs for the study site. A viewing of the City of Detroit video tape of tunnel Distressed Areas 1 and 2 provided insight to the problem being studied. This information was used to select the type and location of surface borings and needed laboratory tests. Other information used, field work performed, laboratory tests conducted, and analytical studies performed are outlined below.

33. Available information. Information from the City of Detroit, Detroit District, and other sources used in the geotechnical study is summarized in Table 3. Pertinent literature used in the study is cited where appropriate. The preconstruction boring logs provided general information on soil stratification and physical properties (standard penetration test, blow counts, water contents, wet unit weights, and unconfined shear strengths) and were used in developing

area geology and possible sources of groundwater. The construction records for PCI-7 contained information on the following:

- a. Construction sequence.
- b. Dewatering well locations and depths.
- c. Excavated soils and groundwater seepage during tunneling.
- d. Distances between concrete forms and lagging, recorded by stations at 4 to 9 locations for each pour.
- e. Locations of construction joints, water stops, cold joints, leaks, joints requiring concrete finishing work.
- f. Locations of crown drill holes to check tightness of concrete against lagging.


Contract CS-858 site investigation data provided information on detailed soil stratification, soil conditions, grout quantities, dewatering operations, piezometer levels along the tunnel and approximately 1300 ft east and west of the tunnel, and profiles of the tunnel invert, crown, and springlines.

34. Fieldwork performed. The surface borings, site visits, and disturbed sampling through holes in the tunnel are described below:

- a. Surface borings. WES surface borings, under the supervision of a field geologist, were started on 22 April 1980 to confirm soil stratification and in situ soil conditions along distressed and nondistressed segments of the tunnel. The borings were needed to obtain undisturbed samples for laboratory tests to develop soil properties for analyses and analytical studies. A total of seven sample borings and three wash borings (to define a land fill found in the second boring) were made. The boring locations and purposes are summarized in Table 4. A boring location within Distressed Area 1 was not possible because of ground freezing and shaft excavation operations. A 24-in. gas line and overhead power lines west of the tunnel restricted boring locations to the east side (except for boring WES-10). Overhead power lines and towers further restricted locations for borings on the east side. Boring logs are contained in Appendix A. All borings were made using a Failing 1500 truck-mounted drill rig, as shown in Figure 4a, drilling mud, and casing where necessary. Borings WES-1 through WES-4 were drilled deep enough to penetrate a thick sand stratum encountered near the tunnel invert. The borings bottomed in hard sandy clay to clayey sand,



Figure 1. Field investigation activities,
1.9 Mile Road/Fish Creek
Channel Failure Study



identified as glacial till, underlying and marking the bottom of the sand stratum. Boring WES-5 bottomed about midway through the sand stratum. Borings WES-6, WES-7, and WES-8 were drilled only deep enough to define the landfill (maximum depth 29 ft). Logs were not made of these borings. All boreholes were grouted when completed.

- (1) Sampling. Undisturbed samples were taken using a Hvorslev fixed piston sampler with thin-wall steel tubes where possible. Three-inch or five-inch diameter tubes, with spring steel catchers riveted in the bottom, were pushed when possible in sandy soils to prevent the sample from sliding out of the tube during withdrawal from the borehole. Soils too hard to push the Hvorslev sampler into were sampled by rotating a Denison barrel equipped with a 5-in. diam Hvorslev inner tube and a 6-in. carbide rock bit. Cohesive samples were pushed out of those 5-in. steel tubes not fitted with catchers and waxed in 6-in. diam cardboard tubes. Samples containing sand were left in the sample tube. Jar samples were taken for each undisturbed sample. Disturbed samples were taken using a standard (2-in. O. D.) split spoon with catcher. Disturbed samples were sealed in glass jars. All samples were delivered to the WES soils laboratory by a Detroit District van on 7 June 1980.
- (2) Penetration tests. Penetration resistance tests were made in borings WES-1, WES-2, WES-9 and WES-10 using the standard 2-in. O. D. split spoon and a 140-lb weight free falling 30 in. Blow counts were recorded for each 6-in. penetration up to 18 in. In dense sands, a penetration of 18-in. was not feasible and the blow count for the first 6 in. plus the blow count in excess of about 50 to 80 for an additional penetration less than 6 in. were added together and divided by the total penetration in tenths of a foot to obtain an equivalent blow count for a 1-ft penetration.
- b. Site visits. Visits were made to the site by WES geotechnical engineers on 7-8 May 1980 and 22-26 June 1980. The first visit was made to check boring work and sampling problems (recovering sand samples), to observe accessible tunnel conditions north of Distressed Area 1 at the work shaft, and to obtain additional available records and information from site personnel. The second visit was made to observe completion of concrete coring as shown in Figure 4b, check soil conditions being found behind the lagging from 2-in.-diam holes drilled through the tunnel wall, supervise soundings using a small cone penetrometer in holes south of Sta 130+25, and then

inspect conditions at seeps, joints, and cracks along the tunnel south of Distressed Area 1.

- c. Tunnel wall holes. A total of sixty-four, 2-in.-diam holes were drilled through the tunnel wall at the invert, lower quarter, and springline to check soil conditions behind the lagging in both distressed and nondistressed areas. Voids or soft loose soil conditions and types of soils encountered were of primary interest. The holes were drilled through the concrete using an air hammer as shown in Figure 4c and through the lagging using a wood auger or circular saw bit. The holes were not always perpendicular to the surface and concrete thickness and measurements taken were not true indications of wall thickness. The soil behind the lagging was sampled using a common piece of 1-in. pipe, 4 ft long, and small sledge hammer. Soil recovered was classified and placed in plastic or glass jars. A small hand-held 60 deg cone penetrometer (0.5 in² area) was used before sampling in most of the holes south of Sta 130+25 to obtain a qualitative comparison of in situ soil consistency (loose or dense for sands and soft or stiff for clays).

35. Laboratory test program. Laboratory tests performed on selected undisturbed samples included classification and physical property tests (natural density and water content, specific gravity, and gradation). Consolidation tests were performed on two clay samples, one from a depth of 21.5 ft and one from a depth of 55.3 ft, to determine the degree of overconsolidation of upper and lower clay stratum. Five drained direct shear tests were performed on clay samples from depths of 10, 25, 41, 50, and 52 ft to determine drained shear strength. Special consolidated undrained triaxial compression tests with pore pressure measurements ($K_o \bar{R}$) were performed on four undisturbed samples from depths of 55 ft to 65 ft and included clays and silty sands to determine modulus values and estimates of in situ K_o values (K_o = coefficient of earth pressure at rest = ratio of effective horizontal earth pressure to effective vertical earth pressure) for analytical studies. Special tests were also performed on undisturbed samples to assess the piping characteristics (susceptibility to erosion through small holes or cracks under various groundwater levels) of fine-grained sands, silts, and sandy clays. The

special K_o \bar{R} tests and piping test procedures are outlined briefly below. Other tests were conducted using standard procedures described in Engineer Manual EM 1110-2-1906.

- a. K_o \bar{R} tests. Specimens 2.8 in. in diameter and 6 in. high were trimmed in the humid room from selected samples. The specimens were enclosed in a rubber membrane, placed in a triaxial chamber, and saturated under isotropic back pressure and then consolidated to the estimated in situ vertical pressure. A girth clamp placed around the specimen to monitor lateral deformations was used to adjust lateral pressures during consolidation such that no change occurred in the diameter of the sample, (i.e., no lateral strain to simulate in situ K_o conditions). The ratio of lateral pressure to vertical pressure at the end of consolidation provided an estimate of the in situ K_o value. The slope of the stress-strain curve during axial loading provided an estimate of in situ modulus which for a linear elastic material would be Young's Modulus. The test also provided an estimate of in situ shear strength.
- b. Special piping tests. A special apparatus shown in Figure 5 was constructed to determine piping characteristics of the undisturbed samples of sands and silts. The following procedure was used on performing the special soil piping test:
 - (1) Measured desired length of sample for testing and cut off excess part of sample tube at each end.
 - (2) Cut narrow slot in sample tube, longitudinally, along center one-third of sample length or short circumferential slots around middle of sample.
 - (3) Measured total weight of cut sample and tube.
 - (4) Attached end caps to sample tube with a 200-mesh screen placed inside each end cap.
 - (5) Placed rubber sleeves over end caps and the sample tube.
 - (6) Placed band clamps over rubber sleeves, making end caps watertight.
 - (7) Hooked each end cap to pressurized water source.
 - (8) Placed sample on a cradle inside plexiglas reservoir and filled reservoir with water to submerge sample to increase percent saturation. Sealed slots with tape and applied water at 1/2-psi pressure to ends of sample to further increase percent of saturation.




Figure 5. Special test apparatus for measuring piping characteristics of sands and silts
15 Mile Road/Edison Corridor Tunnel Failure Study

- (9) After increasing percent saturation, opened slots, applied water under increasing pressure to initiate piping, and recorded water pressure and time.
- (10) Applied increasing water pressure until all piping ceased as indicated by no further flow of material out of slots.
- (11) Dismantled sample and noted erosion conditions at ends of sample.
- (12) Measured weight and gradation of material piped out of sample and material left in the sample.
- (13) Measured weight of empty sample tube.

The test apparatus in Figure 5 shows a 5-in.-diam sample in its steel sample tube being saturated under 0.5-psi water pressure (circumferential slots cut around the center of the steel tube are sealed with gray tape).

- c. Pinhole tests. Pinhole erosion tests described in EM 1110-2-1906, Change 1, dated 1 May 1980, were performed on three samples of a sandy clay to determine the susceptibility of this material to seepage erosion through small openings. The test consists of measuring the rate of water flow through a 1/6-in. diam hole in a 4.6-in. long sample under a range of water pressures. The color of water (cloudy, clear, etc.) flowing out of the hole is recorded. The flow rate versus water head is used to assess erosion and to determine a dispersion index for the soil.

36. Analytical studies. In addition to area and site geology and groundwater studies, analyses were made to determine earth pressure coefficients, in situ stresses, and elastic constants (Young's Modulus and Poisson's ratio) of the soils. Changes in the in situ stresses after construction and potential water and soil infiltration into the tunnel also were analyzed. The results were provided to WES structures engineers for use in soil-structure interaction analyses (paras 94 and 95). Other possible causes of distress such as seismic ground vibrations (para 55) were considered.

Regional geology

37. A brief description of the Quaternary stratigraphy of southeastern Michigan is included in this report to enable a better understanding of geologic strata and soils encountered locally at the study site. The vertical geologic column in southeastern Michigan consists typically of 0-400 ft of relatively flat-lying glacial soils, deposited within the last one million years, overlying dipping bedrock strata of early Paleozoic age (300 to 500 million years old). Bedrock is below the depth of interest for this geotechnical investigation and will not be discussed further, except to say that occurrences of methane (natural gas) in the glacial overburden probably originates from the underlying bedrock from which the gas is believed to migrate upward (Mozola, 1973).

38. Glacial geology. During the latter part of the Wisconsin Glaciation, the western half of southeastern Michigan was covered by a large glacial lake. The level of the lake was controlled by the glacier as it retreated to the east and north (Twenter, 1975). Beaches were formed when the lake level remained stationary for some time. Clays and silt were deposited toward the center and deeper parts of the lake. As the glacier advanced or retreated, the beach deposits would be reworked and deposited higher or lower than previous beaches forming offlap and onlap cycles of deposition with facies changing from sand to clay. Morainal deposits were moved about and redeposited by the lake water. Figure 6 is a map showing the location and type of glacial deposits.

39. Glacial deposits. In southeastern Michigan, glacial deposits are variable, ranging from soft and hard clays to silts to sands and gravels. The strata can persist for miles laterally or play out within tens of feet by lensing or by gradational facies changes. The glacial section is highly variable and complex both laterally and vertically. All glacially deposited materials are known as drift and were transported and deposited or reworked by ice, water in streams, water in lakes, or by wind. Unstratified and unsorted drift was deposited by ice and is a mixture of clay, boulders, sand,

and silt known as till. Till is commonly hard when drilled and often is described locally as "hardpan" in drillers' logs. Stratified drift is deposited by and within water of streams and lakes or by wind and includes outwash deposits and lake deposits. Outwash deposits are generally sands and gravels carried beyond the ice by meltwater streams and are recognized in subsurface investigations as channel shaped strata that form lenses of limited lateral extent in cross sections. Lake deposits consist of water-laid till, bottom sediments, ice-rafted (berg) sediments, and near shore sediments deposited as beach ridges and deltas (Flint, 1971). Bottom sediments are commonly the finer grained constituents, clay and silt; beach ridges and deltas are usually sand and gravel. Fine-grained lake sediments are often laminated in cycles representing yearly seasonal deposition of clays and silts and are often varved. Environments of deposition sometimes overlap both laterally and vertically (time wise), producing complex and intermingled depositional sequences.

40. Loading from glacial ice. The last glacial ice which covered the St. Clair basin retreated north approximately 14,000 years ago (during the Early Post-Lake Border interval of the Cary substage of the Wisconsin stage of glaciation) (Hough, 1958). Lacustrine clays were deposited in the Lake St. Clair basin during the period of glacial Lakes Whittlesey and Warren, approximately 13,000 to 11,000 years ago (Soderman and Kim, 1970). Paleontological studies indicate that a dry climate existed in the Great Lakes region from 11,000 to 9,000 years ago (Stanley-Chippewa interval of Hough) (Dreimanis, 1970). The effects of the dry climate and associated isostatic changes in the Great Lakes Region caused a lowering of the groundwater table due to a lowering of the Lake St. Clair level. Based on the elevation of overconsolidated brown oxidized zones in the clay, the groundwater table at the time of this dessication and oxidation was at least 12 to 13 ft lower than it is now in the Detroit and Windsor, Ontario area (Dreimanis, 1970). The lowering of the groundwater table caused the development of the oxidized overconsolidated crust. Based on the

above geologic history, it does not appear that the lake bed clays and beach sands have been subjected to ice loading.


41. Land surface. The modern topography in the Detroit area is characterized as a relatively flat, featureless plain sloping gently southeastward toward Lakes St. Clair and Erie. The flat plain is the remnant of the glacial lake plain constructed at ancient higher lake levels. Northwest of the plain the topography is more rugged, dotted with irregularly shaped lakes and ridges and hills of till deposits of glacial moraines.


42. Local geology. The study site lies wholly within the glacial lake plain and is underlain by a complex series of lake clays and silts, gravelly clays (gravelly to rocky silty clays were encountered during tunnel excavation, para 52), sand and gravel deposits, and older till plains that predate the glacial lake deposits. The thickness of glacial deposits is approximately 150 ft (Twenter, 1975). A general geologic profile of the study area (based on contract PCI-3 boring logs) is shown in Figure 7. The clays are interpreted in this study as glacial lake deposits and reworked till (para 60). The glacial lakes formed in front of the ice lobes and changed in size, shape, and depth with each of several advances and retreats of the last glacier. Deposits within the lake area are therefore intermixed and complex. The bedrock formation beneath the glacial deposits at the site is the Antrim Shale.

Groundwater

43. The source of the groundwater in southeastern Michigan is precipitation (Twenter, 1975). The amount of precipitation that infiltrates the ground and recharges the groundwater reservoir is determined by the upper few feet of soil. If the soil contains a large amount of sand and silt, the infiltration rate will be high (8-12 in./hr). When soils are mostly clay, water does not penetrate rapidly and the infiltration rate will be less than 2 in./hr. Figure 8 shows a map of southeastern Michigan soils and their infiltration rates.

44. Occurrence of groundwater. The sediments in the areas shown as lakebeds (Figure 6) are a poor source of water (Twenter, 1975).





NOTE: SEE APPENDIX A FOR LEGEND SHEET
 GENERAL GEOLOGIC PROFILES BASED
 ON CITY OF DETROIT CONTRACT
 PCI-3 BORING LOGS




Figure 7. Site geologic profile
15 Mile Road/Edison Corridor
Failure Study

15 MILE ROAD

10,000

12,000




Figure 7. Site geologic profiles,
15 Mile Road/Edison Corridor Tunnel
Failure Study




Figure 8. Soils and their infiltration rates, southeast Michigan (Twenter, 1975)

They are composed primarily of clay-rich materials and are not very permeable. A series of hills and ridges composed of sand and gravel 25 to 30 ft thick rest on top of the clay-rich materials in some areas. These hills and ridges were formed as beaches, terraces, and river deltas by wind, waves, and stream action during the late Wisconsin Glaciation (Wisler, 1952). They are very porous and absorb a large amount of the precipitation. The water seeps downward to the water table where it contacts the thick layers of lake clays and interbedded deposits of sand and gravel which are buried beaches, bars, and deltas associated with former lake levels (Mozola, 1969).

45. Recharge. The interbedded deposits of sand and gravel are probably gradational with the matrix and are probably interconnected to each other (Mozola, 1973). These deposits are partially confined and develop artesian systems. The system is recharged by either an outcrop of an aquifer at the surface (no matter how tortuous the route to the confined aquifer) or by crossbed leakage. "Permeability in glacial till is relative; a large cross section of clay till could pass as much water as a small cross section of sand. A large sand and gravel body, even if enclosed by till of low permeability can still function as a good aquifer because of the extensive contact with the surrounding till" (Mozola, 1969).

46. Local groundwater. At the site, the glacial sediments consist of about 60 ft of gravelly clays overlying some 30 ft of sorted sands and silts (Figure 7). The sand unit lies on top of glacial till and outwash of an earlier glacial age. This last unit is inferred to extend to a depth of 150 ft where it contacts the Antrim Shale. The sand unit is interpreted as a beach deposit due to its characteristic sorting and large areal extent. This unit is probably interconnected in the subsurface with the large glacial lake sand deposits which are located less than 2000 ft to the southwest (Figure 6). A minor amount of recharge water comes from crossbed leakage from the clay deposits due to the large areal extent of the beach deposit. Some recharge could also be contributed by seepage from the Red Run River at the site. In addition, as indicated by Figure 7, the sand thickens and is coarser

to the east of the site along 15 Mile Road. Preconstruction borings just east of the Red Run (east of C-182 on Figure 7) indicate that the sands extend up to the ground surface. Farther east to Lake St. Clair, deep glacial clays separate infrequent narrow beach sand deposits and it is considered unlikely that the St. Clair lake is connected to the sands at the tunnel site.


Preconstruction conditions

47. Preconstruction boring logs C-176, C-224, C-223, and C-222 cover the tunnel study area from Stas 137 to 112. A profile of these boring logs, shown in Figure 9, indicates variable strata of gray hard silty clays and silts along the tunnel and the top of a strata of very dense, fine to medium sand, along the base of the tunnel. Blow counts increase significantly in sands below elevation 550 to 545 and generally range from 150 to 180 in the sand. Minimum blow counts below elevation 560 are significantly higher in the silty clays and silts in borings C-223 and C-222 than in C-176 and C-224. Although all boring logs indicated only a trace of gravel in the clays and silts above the tunnel, the high blow counts in borings C-224 and C-222 could be the result of higher gravel content.

48. Soil properties. Soil properties were determined by DWSD for small samples (1.4-in. diam) taken with a drive sampler in borings C-176 and C-222. A summary of water contents, wet densities, unconfined shear strength, and transverse shear strength shown in Figure 10 (boring log legend is in Appendix A) indicate the following:

- a. Samples from both borings had similar water contents, ranging from about 30 percent in upper clays to about 12 percent below elevation 585. Wet densities ranged from about 130 to 150 pcf below elevation 590. Densities of samples from C-222 were generally higher than for samples from C-176.
- b. Unconfined shear strengths ranged from about 200 psf (0.1 tsf) to about 10,000 psf (5 tsf) with generally higher values for samples from C-222. Samples below elevation 563, logged as silty sand and fine to medium sand in boring C-176 (Figure 10), were classified as silt and fine sand, very clayey silt and fine sand, and silt and fine sand when tested in the DWSD laboratory. Transverse shear resistance (Housel, 1970)

Black








Figure 9. Preconstruction geologic profile, 15 Mile Road/Edison Corridor Tunnel Failure Study






Figure 10. Preconstruction soil properties, 15 Mile Road/Edison Corridor Tunnel Failure Study

values were generally less than 1,400 psf (0.7 tsf) and about equal to one-fourth of the unconfined shear strength. The values for samples from C-176 were about one-half of those for samples from C-222.

- c. The blow counts and soil property values indicate that strata at and just above the tunnel depths north of about Sta 128 are relatively softer than south of this station. No gradation or soil characteristics other than blow counts for the fine to medium sands along the tunnel base were measured. Also, the extent of these sands to the south of about Sta 111+50 to the Red Run were not defined. Consequently, their influence on tunnel stability does not appear to have been considered.

49. Groundwater conditions. Boring C-176, in connection with contract PCI-8 was made using a hollow stem auger and no drilling water. Consequently, the groundwater elevation of about 581 observed in November 1968 is considered a reliable indication of artesian pressures in the fine to medium sand below elevation 552 (Figure 9). The preconstruction borings C-222 to C-224 along the PCI-7 study area were made using casing to shallow depths and drilling water. The shallow water levels observed in these borings before casing removal probably reflects the influence of drilling water and are not true groundwater levels. Consequently, artesian water pressures in the sands near the tunnel base were not defined south of Sta 137 to the Red Run.

Construction conditions

50. Tunnel construction conditions important to geotechnical considerations were dewatering; soils and seepage conditions encountered during mining; times between initial lining and concreting; location of construction joints, cold joints, and water stops; and leakage after concreting. These aspects are discussed below.

51. Dewatering. Deep construction dewatering wells were installed between Stas 136+33 and 105+80 from 20 October to 14 December 1970 as summarized in Table 5 from DMWD daily reports. Daily inspector reports also indicated initial installation of these wells as shown in Table 6 (first two items). The wells were located 25 ft east of the

tunnel centerline at a spacing of 100 ft from Sta 134 to Sta 114, and extended some 30 ft into the sand underlying the tunnel invert. From Stas 112+20 to 105+80, the spacing ranged from 10 ft to 100 ft (average spacing of 46 ft). The depth of water shown in Table 5 was the depth that free water was first encountered during drilling and does not reflect the artesian pressures that would be indicated if water level readings in the borings had been taken several days after drilling. The wells apparently were operated until completion of construction in August 1972 as indicated from inspector's reports summarized in Table 6 (last three items). No records were found of the dewatering level maintained during construction. Consequently, it is assumed that the ground around the tunnel was dewatered to the depth of the mined invert (since no seepage was noted during mining until Sta 125+81, Table 7), and that ground pressures during construction corresponded to wet unit weights for the soils (no buoyant effect) which ranged from 130 to 150 pcf. After construction and removal of dewatering, the artesian groundwater pressure in the sand along the base of the tunnel was free to increase to preconstruction levels of 5 ft to 15 ft above the tunnel crown, depending on recharge from rains and surface infiltration (discussed in para 45 on groundwater) and watertightness of the completed tunnel.


52. Soils encountered during mining. Soils encountered during mining from Sta 135+83 to 103+93, as described in daily inspector's shift reports, are listed in Table 7. Although the predominant soil type was gray, sandy clay and clay, hard to very hard with varying amounts of rock, frequent changes occurred in the amount of sand, gravel, and rocks. Gravel and sand with clay was noted for Stas 134+35 to 133+83. Hard gray sandy clay from Stas 132+95 to 132+85 changed to gray sand with clay from 132+50 to 132+25 and gray sand with very hard gray sandy seams from 132+70 to 127+76 changed to clay, very rocky from 127+76 to 127+21. Gravel, sand, and sand strata were indicated at a number of locations as indicated by underlined words in Table 7. Except for the rocky condition, the soils excavated at the location of preconstruction borings generally agreed with the boring logs. Running sand

strata as mining neared the Red Run were encountered south of Sta 109+16 (see Excavation Summary, Table 1).

53. Seepage during mining. No indication of seepage into the tunnel was noted in inspector's shift reports until Sta 125+81 where some water started to appear. Other indications of seepage are highlighted by dashed underlining in Table 7. Seepage increased south of Sta 109 as mining approached the Red Run. Water seepage and caving ground south of Sta 109 are noted in the Excavation Summary, Table 1. The caving and increased seepage near the Red Run correlate with the sand layer and sand strata shown in the log for boring C-222 (Figure 9).

54. Tunnel lining. The conditions during tunnel lining construction important to geotechnical considerations are discussed below.

- a. Ribs and lagging. Steel ribs (5WF16) on 5-ft centers and 4-in thick wood lagging (between flanges of the ribs) were erected within a shield behind the mining machine and jacked against the tunnel soil surface as the machine pushed ahead. Because of the numerous rocks (as large as 4 ft) encountered during mining (many required blasting for removal through the mining wheel, as noted in the Excavation Summary, Table 1), the tunnel surface was probably irregular with depressions and hard rock spots. Thus, it is possible that numerous small voids existed between the wood lagging and the tunnel soil wall. Voids, if present, would increase the available seepage paths for water to flow from the soil through spaces in the lagging and through any open joints in the concrete lining after construction and removal of the dewatering system. The construction sequence from Tables 1 and 2 indicates that the concrete lining was placed some four months after the ribs and lagging were installed. This time allowed redistribution of ground pressures around the tunnel, probably to an all around pressure less than the overburden pressure.
- b. Concrete lining. The location of construction joints, waterstops, and dates of pours are summarized for Stas 136 to 107 in Figure 11. The 16-in. thick (nominal) concrete lining was poured in 105 ft lengths. South of Sta 119, construction joints with waterstops existed at 105 ft intervals. No waterstops were installed north of Sta 119 (Table 1). Distance from concrete form to rib and lagging (liner) condition



after pour, and other pertinent notes from City inspectors daily shift reports are also shown in Figure 11. Locations of distressed areas are shown for subsequent reference. The construction joints, cold joints, concrete finishing (in both distressed and nondistressed areas) that could effect the watertightness and potential for soil infiltration after construction and removal of dewatering could influence the stability of the tunnel. The measured distances to the lining from the concrete forms are an indication of the variation in tunnel dimensions after four months and just prior to concrete placement. This variation could have an influence on ground pressure distribution along the tunnel. The tabulation of grout holes drilled in the crown to check tightness of concrete against lagging is included in Figure 11. The results indicated only two locations where either the concrete was not tight against the lagging or a void existed (Stas 136+68 and 126+12). The void at Sta 126+12 was filled on 7 July 1972 as was a power drop hole at Sta 123+42.

- c. Entry of water. During concrete placement, the drop hole at Sta 118+57 pierced a tile field. Water and mud entered the tunnel at this location (shift inspector's daily reports for 30 May to 4 June 1972). Any water that leaked around the outside of the lagging could have eroded soil from around the upper section of the tunnel and through the lagging near the springline, causing a potential weak spot in the tunnel.
- d. Tunnel leakage. Notes in City inspector's daily reports indicated concrete finishers were "finishing joints and leaks down to Sta 103+95" on 28 June 1972, "continued to finish tunnel north of cofferdam shaft and stop leaks" on 29 June 1972, "finishers continued to stop leaks and finish joints at various places north of cofferdam shaft" on 5 July 1972. How far north this work extended was not recorded. It appears that leakage at joints occurred after concrete liner placement, but specific locations and type of leakage (i.e., clear water or water and fine sand or silt) is unknown for the study section of the tunnel.
- e. Effect of Red Run cofferdam. During construction, a cave-in at the Red Run (Table 1, Excavation Summary) required a cofferdam which had significant leakage and resulted in a shaft which was later backfilled. No information was found on compaction of backfill. It is not known how impervious the backfill was. It is possible that increased leakage from the Red Run through the backfill could have contributed to the

groundwater recharge and increased the groundwater levels at the site.

Postconstruction conditions

55. Once the dewatering system was removed after construction, the groundwater could return to normal levels. Preconstruction boring C-176 for PCI-8 indicated a groundwater level at elevation 581, some 35 ft above the tunnel invert. The 35-ft head would cause a water pressure of 15 psi at the invert and 8 psi at the crown. Any open joints in the tunnel would be subject to leakage and possible infiltration of fine sand and silty sand where such strata existed at a leaking joint. No observation or producing wells exist in the local area and thus a direct measurement of groundwater levels since construction does not exist. Since surface infiltration in the region is the primary source of recharge for the beach sand along the tunnel base, variations in rainfall and Red Run stages could effect the maximum groundwater level especially during unusually wet seasons. Local rainfall and river discharge records were reviewed from 1972 to the present and the results are summarized below. Possible seismic activity in the area was also considered. The only activity during 1972-1980 was a small tremor of magnitude 3.4 centered at Point Pelee, Ontario, some 48 miles from the tunnel site.

56. Rainfall records. Rainfall records through 1978 for the Detroit City airport, about 9 miles south of the site, indicated higher rainfall in 1973, 1975, and 1976 than in 1974 and 1977, based on yearly totals. The wettest year was 1976.

57. Red Run and Clinton River stages and discharges. Gage stations on the Red Run were not established until October 1979. However, discharge records for a gage on the Clinton River near the Garfield Road bridge provided data from 1972 through October 1979. This gage is one mile from the exit of the Red Run into the Clinton and some two miles from the tunnel site. The number of consecutive days for discharges over 1000 cfs was used as a measure of significant runoff from long-term rainfall periods. The comparison showed 16, 18, 8, and 15 continuous days of 1000 cfs or greater discharge for 1973-1976

and only 3 to 4 continuous days for 1977-1979. Thus much higher runoff, suggesting much more rainfall, was apparent for 1973-1976 than for 1977-1979. The 1973-1976 long-term rainfall periods would allow greater infiltration and recharge of the groundwater and produce relatively higher groundwater levels than in 1977-1979. The nearest observation wells to the site are in Oakland County. Water levels for a well west of Pontiac (Huffman, 1979) in glacial deposits showed maximum extreme levels in 1974 and 1976. The variation between the monthly high and low for 1976 was 2 ft and slightly less than 2 ft for monthly lows for 1973-1977. Thus, even in wet years, the groundwater rise may be relatively small.

58. Red Run borings. Borings for the Corps of Engineers made in September 1978 indicated a groundwater level at a depth of 40 ft in a cased boring (RR-43-78) some 270 ft east of tunnel Sta 111+10. This groundwater depth corresponds to an elevation of 565 near the crown of the tunnel. Several other borings along this reach also indicated a groundwater level at the 40 ft depth. This level was during the drier season and the level during the spring may have been higher.

Postfailure conditions

59. The subsurface soil stratification and soil conditions after tunnel distress indicated by test borings made for the DWSD in Feb-Mar 1980 were confirmed by the WES borings. The locations of all test borings and WES borings are shown by four plan plots along the centerline in Figure 12, in relation to the distressed areas. The post failure geotechnical conditions based on these borings, tunnel drill holes, testing and sampling, laboratory soil testing, and visual observations during site visits are described in this section.

60. Soil stratification and in situ conditions. Figure 13 is a detailed stratigraphic profile along and near the tunnel centerline from approximately 15 Mile Road south to near the Red Run. The "as-built" tunnel profile is shown to indicate the elevations of different soil strata relative to the tunnel before distress. The profile was constructed with data selected from three sets of borings:





Figure 12. Location of all borings used in developing subsurface stratification and soil conditions, 15 Mile Road/Edison Corridor Tunnel Failure Study



STATIONING, FT

127+00

125+00

123+00


121+00

119+00

117+00

115+00

DISTRE



LEGEND

- PROBABLE STRATIGRAPHIC CONTACT.
- FACIES (GRADUAL) CHANGE OR INTERFINGERING CONTACT.
- NUMBERS ON SIDE OF LOGS ARE BLOWS FT

SON), GENERALLY ON C.
LIT-SPOON • 5-10 FT INTERVALS (NX).
DRILLED ALONG SIDE TUNNEL.
STANDARD SPLIT SPOON, FEB-MAR 1980
STANDARD UNIFIED SOIL CLASSIFICATION SYSTEM.
D NEAR TUNNEL, 6" ROCK BIT, 5" & 3" SAMPLE
SPOON, APR-MAY 1980




Figure 13. Detailed stratigraphic profile, 15 Mile Road/Edison Corridor Tunnel Failure Study

(1) "C" borings, emplaced along the centerline in 1969, prior to tunnel excavation and construction; (2) "TB" borings, emplaced alongside the tunnel in February-March 1980, subsequent to distress of the tunnel; and (3) "WES" borings, emplaced by the Corps of Engineers in April-May 1980. A landfill-trash dump was discovered just east of the tunnel centerline in the WES borings. The natural soils at the site to a depth of approximately 110 ft (elevation 500 ft msl) can be divided into three units. The upper 60 ft is predominantly clay (CL) with varying gravel content, ranging from soft and plastic to very hard and stiff. Occasional sand and silt lenses also occur within the upper 60 ft, but gravelly clay predominates. A distinct well-sorted (poorly-graded), cohesionless sand and silt unit (SP, SM, and ML) persists throughout the length of the section between approximately 60 ft and 90 ft depth (elevation 550-520 msl). The sand and silt unit is difficult to penetrate (high blow counts), but its cohesionless nature gives it a very low apparent strength when removed from the borehole. At the base of the silt-sand unit, a very hard, cohesive, sandy, gravelly clay (CL) to clayey, gravelly sand (SC) is encountered. This unit lies at about the same elevation (approximately 520 ft msl) for the length of the profile. It often is referred to in other boring logs as "hardpan."

- a. Landfill dump. The presence of a "sanitary" landfill extending to a maximum depth of about 40 ft was verified in borings WES-2, -3, -5, and -6 (Figure 13). The landfill, believed to have been started in the 1950's and filled in by early 1960, was also noted by the bypass contract foreman at the site, who stated that they encountered loose rubbish with little or no soil when excavating for the temporary bypass east of the tunnel. Boring C-224 (Figure 9), 12 ft west of the centerline, did not encounter the landfill. Several "TB" borings recorded "no sampling" in the upper 40 ft or so of the log and some of them may have indicated the presence of the landfill. However, the WES borings represent the only certain verification of the landfill. The refuse encountered was typical landfill debris with little or no soil content, and included paper products, tin cans, automobile tires, and other rubbish that caved so badly the entire vertical section had to be cased to allow sampling


of the underlying soils. The north-south limits of the landfill are shown on Figure 13 as well as could be determined from borings. Borings WES-7 and -8 did not encounter the fill. The east-west extent of the landfill is not known, but the fill definitely exists just east of the tunnel. The probable significance of the landfill to this investigation is that the excavation replaced 25 to 40 ft of tight clays (low permeability) with loose permeable rubbish that readily fills with water. Such an excavation might also have relieved residual lateral pressures in the soil in the vicinity of Distressed Area 2.

- b. Clay strata. The upper 60 ft of gravelly clays is a complex series of glacial lake sediments. WES borings 1 and 4 logged varved soft clays associated with quiet water glacial lake deposition. Much of the gravelly clay and other lean clay (CL) encountered in the upper 60 ft was resistant to penetration by the sampler (standard split spoon and 140-lb hammer) and a few units were considered very hard, indicating a high degree of consolidation. Some samples from the gravelly clay between 20- and 40-ft depth in boring WES-4 were almost shale-like in consistency and hardness. The silts and sands encountered within the upper 60 ft generally all exhibit some cohesion and maintain their shape when cored. An exception is the 5-ft thick sand lens near elevation 555, Sta 124+00 to 129+00, logged as SP, SW, and SM in several borings, that shows only a little cohesion. Blow counts in borings presented in Figure 13 increased abruptly at similar depths (around 50 ft at elevation 560 msl) south of Sta 125+00. The soils at that depth would appear to have been overconsolidated by loading, but because the sediments down to a depth of about 90 ft have been determined to be late Wisconsin glacial lake deposits (para 38), there should have been no thick glacial ice loading of the upper 90 ft. It is also improbable that any great thickness of soil overburden has been subsequently removed in the short geologic time since deposition of the sediments occurred. The glacial till complex below the beach sand unit (Figure 13) is interpreted as older glacial drift and probably has been ice loaded and overconsolidated.
- c. Beach sand. The cohesionless well-sorted sand below the gravelly clays is interpreted as a beach ridge developed on the margin of one of the glacial lakes (Mozola, 1969). The importance of the sand is its persistence along the tunnel route near the invert of the tunnel. The unit grades from fine, occasionally


medium-grained sand to very fine (grit just perceptible) to silt size. The silt sizes generally occur toward the base of the unit, as can be seen in borings TB-29, WES-4, TB-27, WES-3, TB-4, and TB-1, Figure 13. The sand is predominantly quartz with varying percentages of light and dark colored accessory minerals of igneous origin. The top of the beach unit, as determined from boring logs, is relatively flat (less than 5-ft relief) along the tunnel line and is exposed along the tunnel above the invert.

- d. Distressed Area 1. Detailed 1 to 1 profiles and sections constructed from logs of the closely spaced TB borings made in early February 1980 on either side of the tunnel, in the central portion of Distressed Area 1 are shown in Figure 14. The tunnel profile and sections are for the as-built location before distress. Silty sand, silt, and fine sand exist along the base of the tunnel; clay and silt strata exist above the sand. The material excavated during mining in this segment noted considerable sand along with clay, sandy clay, stones and rocks (Table 7). Borings TB-4 and 8A show loose sand and soft clay strata. Voids were also found adjacent to the invert in TB-5 and TB-12. The sections show the variable stratification on either side of the tunnel. Lines connecting similar strata indicate orientation of silt, clay, and sand around the tunnel periphery, before distress. The density values from split spoon samples are shown on the profiles in Figure 14. Although split spoon samples are considered disturbed samples, the dry densities (excluding the effects of water content) provide a relative measure or index of in situ conditions. Low density values are indicated for the soft to stiff clay above the crown at Sta 132+40 (TB-8 and TB-8A) and in the silt layer at Sta 131+40 (TB-12). Dry densities for other strata range from 113 to 129 pcf. These values are within the range for samples from other locations as shown in Figure 15. It should be noted from Figure 15 that there is a wide range in dry densities at the tunnel site. Thus, low density values may be a result of the natural variation in the complex stratification. Gradation data shown in Figure 14a indicates that the beach sand unit along the base of the tunnel is primarily a silty sand. The sand content increases with depth. Very low blow counts of 2 to 15 (compared to blow counts of 33 to 83 in preconstruction borings C-224 and C-176, Figure 9) can be noted close to the tunnel in Figure 14b. Final collapse of the tunnel crown at Sta 131+80 occurred during the time the TB borings were being drilled

Black



a. PROFILES






NOTE:





B/F = BLOWS PER FOOT

γ = DRY UNIT WEIGHT, PCF

40/55/5 = % SILT OR CLAY/ % SAND/ % GRAVEL



b. S



b. SECTIONS

Figure 14. Profiles and sections in Distressed Area 1, 15 Mile Road/Edison Corridor Tunnel Failure Study




Figure 15. Range of dry density values, elevation 535 to 570 ft msl

(site settlement observations, para 61 c). Occurrence of the loose and soft soil conditions and low blow counts prior to collapse or as a result of collapse cannot be determined. Additional sections of soil stratification just north and south of Distressed Area 1 are shown in Figure 16. Although considerable variation in stratification persists in the east-west direction, TB-1 north of TB-26 (Figure 14a) shows the same silt-sand sequence with silt deepening to the north. Strata changes between TB-24 and WES-3 are shown directly in Figure 13. At Sta 134+50 (Figure 16), low dry densities and low blow counts were measured 17 ft from the tunnel sides in the silt to the west (TB-1) and silt and clayey sand to the east (TB-21), indicating loosening of these materials north of the distress zone. Figure 15 shows a lower range of dry densities in comparison to other locations. At Sta 130+15, south of Distressed Area 1 (Figure 16), dry densities and blow counts were generally higher than those at Sta 134+50 and in Distressed Area 1. The beach sand unit at Sta 130+15 has considerable sandy silt (TB-34). The section of Sta 119+90 in Figure 16 is referred to later.

- e. Nondistressed section between Distressed Areas 1 and 2. Between Distressed Areas 1 and 2, the beach sand unit grades from interbedded silt and fine sand to fine sand along the tunnel invert and then dips to elevation 531 (Figure 13, borings WES-3 to TB-17) some 5 ft below the tunnel invert, at the north end of Distressed Area 2. Clay and silt strata occur above the beach sand. The 1 to 1 profiles and sections for closely spaced TB borings (extending 72 ft north of Distressed Area 2) in Figure 17 show gradational but relatively continuous clays, silt, and sand strata, respectively, above the beach sand. The gradation data for strata shown as sand and silty sand in Figure 17 indicates considerable sandy silt lenses. The permeability of three sandy silt samples from TB borings (Figure 17) was 10^{-6} cm/sec and 10^{-5} cm/sec for one sample of silty sand. During excavation (as the tunneling progressed south), soils were noted as hard sandy clay to hard clay with sandy spots, stones and rock. The material changed at Sta 128+76 to sand with traces of clay and pebbles to large stones (Table 7). As shown in Figure 17, some samples of clay above the crown and of sand at the base of the tunnel had low dry densities of 105 to 109 pcf (TB-3, TB-22, and TB-17). Other dry densities in the clay, silt, and sand strata ranged from 111 to 118 pcf and from 122 to 140 pcf in the stiff to








Figure 16. Sections north and south of Distressed Area 1 and south of Distressed Area 2

Blank



a. PROFILES





NOTE:

B/F = BLOWS PER FOOT



γ = DRY UNIT WEIGHT, PCF

40/55/5 = % SILT OR CLAY / % SAND / % GRAVEL

5×10^{-5} PERMEABILITY CM/SEC



b. SECTION



b. SECTIONS

Figure 17. Profiles and sections along nondistressed tunnel segment between Distressed Areas 1 and 2, 15 Mile Road/Edison Corridor Tunnel Failure Study

hard sandy clay to clayey silt stratum dipping from the springline at Sta 129 to the tunnel base at Sta 128+50. These dry density values are compared with those at other locations in Figure 15. Only borings TB-22 and TB-17 encountered a loose sand interval with low blow counts of 9 and 10. Low blow counts of 8 to 20 in clays, just above the tunnel are similar to those in preconstruction borings C-224 and C-176 (Figure 9). High blow counts adjacent to the tunnel are also comparable to those for the preconstruction borings. The soil conditions along this undistressed segment are similar to conditions before construction.

- f. Distressed Area 2. In Distressed Area 2 the fine-grained beach sand rises back above the tunnel invert and a stratum of fine to very fine sand persists along the tunnel between the springline and crown (Figure 13). A compact to soft silt layer exists along the tunnel crown. Tunnel excavation was noted as (1) sand mixed with traces of clay, pebbles, and large stones from 128+76 to 127+76, (2) clay, very rocky to 127+56, (3) clay to sandy clay with boulders, rocks, and scattered stones to 125+81, and (4) hard clay, sand, traces of soft clay in crown, some water appearing, also scattered stones (Table 7). Test boring TB-14 at the south end of Distressed Area 2 showed low dry densities of 106 pcf and low blow counts of 11 and 12 in the silty clay near the tunnel crown.
- g. Nondistressed section between Distressed Areas 2 and 3. Between Distressed Areas 2 and 3, the beach sand continues at a slightly decreasing level along the tunnel base as shown in Figure 13. A relatively thick strata of hard to very hard silty to sandy clay with variable gravel content occur along the tunnel above the sand with intermittent silt strata above the clay. High blow counts in boring WES-2 and the TB borings are similar to those before construction. Soil conditions indicated by these borings are considered representative of those adjacent to the tunnel. The section at Sta 119+50 (Figure 16) shows correlation of strata in the east-west direction between borings TB-35 and the preconstruction boring C-223 and blow counts that are similar. During tunneling along this segment, sand was noted only from 123+46 south to 122+61 (Table 7); sandy clay with rocks and stones was the general soil condition noted.
- h. Distressed Area 3. Along Distressed Area 3, the fine-grained beach sand dips below the tunnel invert (Figure 13), but strata of sand, sand seams, and clayey

sand with much gravel (boring WES-4) are prevalent. A detailed section along this segment shown in Figure 18 indicates the sand and silt layers and prevalent sand seams. Both the as-built and after distress tunnel profiles are shown. Boring WES-9 and WES-10 adjacent to the tunnel sides lost considerable drilling fluid down to elevations 570 and 563. Drilling fluid from WES-9 was found entering the tunnel the day following completion of the boring. Very low blow counts were indicative of the soft to very soft soil conditions found in boring WES-9. Boring WES-10 indicated relatively low blow counts to a depth of 8 ft below the tunnel. The higher blow counts in boring TB-30 can be explained by the fact that this boring was 24 ft further west of the tunnel than boring WES-10, and soils at TB-30 were probably less affected by the tunnel distress. Both borings TB-30 and WES-4 indicated relatively high dry densities (Figure 15) which compare with those for samples from the preconstruction boring C-222. As discussed subsequently (para 61 g), the sand layers and seams are water bearing. Notes on tunnel excavation materials along this segment included "sand on bottom" (115+41 to 115+11), "sand seams in bottom" (114+66 to 114+36), "sand layer in face at springline" (113+71 to 113+31), "sandy bottom and top" (113+31 to 111) and traces of sand indicative of sand lenses from Stas 114+86 to 114+66 and 113+11 to 112+76. Seepage water was also noted from 113+11 to 112+76.

1. South of Distressed Area 3. South of Distressed Area 3, the beach sand dips below elevation 540. A thick stratum of well-graded sand and gravel with boulders overlain by sandy silts and silty sands occurs along the tunnel at boring TB-29 and Sta 108+70 where caving ground problems started during mining. Samples from boring TB-29 indicated a wide range of dry densities (Figure 15).

61. Conditions during site stabilization measures. Tunnel conditions during grouting, freezing, and dewatering were modified as well as the soil conditions around the tunnel. While these measures were necessary, they undoubtedly modified in situ stresses and soil properties. The sequence of stabilization measures, conditions occurring during their implementation and effects on in situ stresses and soil properties are presented in the following section.




Figure 18. Stratification and soil conditions, Distressed Area 3

- a. Sequence of operations. Closely spaced TB borings in Distressed Area 1 and just north of Distressed Area 2 were started 1 February 1980 and continued through 28 February 1980. Piezometers were installed in selected TB borings and grouting was done in other TB borings. Grouting operations, summarized in Table 8, were accomplished from 2 February 1980 to 7 February 1980. Borings ("SP") made to install settlement pins were started 2 February 1980 and completed on 13 February 1980. The tunnel was still in operation. Dewatering at well No. 1 started on 18 February 1980 and all wells were in operation by about 10 March 1980.
- b. Tunnel crown collapse, Distressed Area 1. In Distressed Area 1, some TB borings and grouting were completed before and others after the first settlement pin readings as summarized in Table 9. A summary of settlement pin data is shown for Distressed Areas 1 and 2 in Figure 19. The as-built and deformed tunnel profiles are shown in the figure for correlation with settlement pin data. When installed, pins 5 through 9 showed that the crown had sagged about 5 ft. Pins 5 and 9 indicated further movement totaling 1 to 3 ft from 5 February 1980 to 20 February 1980 (plot of elevation versus date in Figure 19). Table 9 shows that significant grout was injected in TB-4, TB-12, TB-5, and TB-10 on 2 February 1980 through 5 February 1980 before settlement readings. After initial pin readings, grout was injected in TB-11, TB-8A, and TB-6 on 6 February 1980 with 50 cu ft taken in TB-11 and 150 cu ft in TB-6. After completion of the TB borings on 8 February 1980 and grouting on 6 February 1980, pins 5 and 9 showed an additional downward movement of the crown. Based on this sequence of events, it is possible that further fall-in of the crown and worsening of distress could have been due, in part, to the boring and grouting operations.
- c. Surface settlement, Distressed Area 1. Because of site operations, the ground surface was being modified and apparently no record was made of any surface depressions over break areas. Using ground surface elevations recorded on TB and SP boring logs, estimated contours of the ground surface over break area 1 as of 8 February 1980 was developed and is shown in Figure 19. An apparent surface depression of about 1.2 ft was indicated. This depression could have resulted from collapse at break 1 and settlement or deforming of clay strata and dump material above the break.




Figure 19. Settlement pin observations, Distressed Areas 1 and 2, 15 Mile Road/Edison Corridor Tunnel Failure Study

- d. Ground freezing, Distressed Area 1. Ground freezing of the collapsed section in Distressed Area 1 apparently started on 14 February 1980 with row 9. All freeze pipes were apparently in operation by 29 February 1980. The ground freezing prevented further movement and deformation around this section and thus helped preserve in situ and tunnel collapse conditions and any caving above the tunnel crown.
- e. Distressed Area 2 to 3. Just north of Distressed Area 2, closely spaced borings and grouting were accomplished after initial settlement pin readings. In the five TB borings where grout was injected, grout take was recorded only at TB-17 (27 cu ft) at the north end of Distressed Area 2 where 5 ft of fine sand existed at the east springline with a low blow count of 9 (Figure 17). Settlement pin readings in this area indicated only a small settlement of 0.02 ft at SP-4. SP-14 in the middle of area 2, but apparently not seated on the wood lagging, showed only 0.02 ft settlement through 24 March 1980 while visual measurement in the tunnel showed a crown sag of 1.33 ft and 0.83 ft settlement of the invert on 1 March 1980. Thus, the tips apparently were founded in silt above a void created when the tunnel crown moved downward. Settlements of other deep pins south of Distressed Area 1 and through Distressed Area 2 showed either no settlement or settlements of 0.02 to 0.05 ft (0.6-in. or less) and their tip elevation except for SP-14 correlate with the existing top of tunnel. Shallow pins indicated random settlements as high as 0.26 ft (3.5 in.), which could have resulted from surface operations (operating equipment destroyed several pins) or by freezing weather and ice recorded on data sheets of pin readings.
- f. Settlement of Distressed Area 3. The settlement pin data for area 3 is summarized in Figure 20. The tip elevations of the pins indicated significant crown displacement had taken place before pins were installed on 6 February 1980. The deep pins recorded as being in contact with the lagging (SP-19 and 20) showed no further crown settlement as of 24 March 1980. SP-18 founded at the same depth as SP-20 also showed no settlement, while SP-17A indicated 0.02 ft on 4 March 1980. The tip elevations of the pins agree closely with the estimated existing top of tunnel lagging. Shallow settlement pins, along the tunnel centerline, indicated settlement of 0.11 ft to 0.60 ft which tend to correlate with the variation in tunnel crown movement. Pins SP-25 and SP-24, offset 38 ft west of centerline indicated no






Figure 20. Settlement observations, Distressed Area 3, 15 Mile Road/Edison Corridor Tunnel Failure Study

settlement. It is possible that a narrow surface depression formed as a result of tunnel settlement.

- g. Site dewatering and groundwater conditions. Dewatering at the site reduced water pressures around the tunnel and increased vertical ground pressures to the wet weight of the overburden. Dewatering could, thus, have caused additional settlement. Operation of dewatering wells generally started at Distressed Area 1 on 18 February 1980 and progressed southward with all wells pumping by 10 March 1980. Since the surface settlement over break 1 was deduced from ground surface elevations at TB and SP borings completed on 8 March 1980 prior to dewatering, the surface settlement was not affected by dewatering. However, shallow settlement measurements after 18 February 1980 probably were affected by dewatering especially north of Distressed Area 2 and over Distressed Area 3. On the other hand, piezometer data, recorded to monitor dewatering success, provided valuable information in groundwater at the site.

- (1) Locations. A plan map of piezometer and dewatering well locations and a profile of recorded water levels in piezometers is shown in Figure 21. Piezometer locations were mainly along the tunnel. However, two piezometers (Nos. 39 and 42) were installed 1300 to 1400 ft west of the tunnel and three piezometers were located 268 ft (No. 40) and some 1300 ft (Nos. 43 and 44) east. One additional piezometer (No. 37) was located 192 ft west at Sta 136+88. All piezometer tips were set into the beach sand unit to a depth of ± 85 ft with tips at elevations of about 530 to 515 depending on ground surface elevations.
- (2) Installation and reading. Most of the 8-in.-diam piezometer borings (MCC-1, TB-1, TB-24 to TB-29, TB-33, TB-37 to TB-39, TB-41 to TB-43) were drilled by rotary drilling methods using water. Borings TB-37, TB-39 and TB-41 were drilled using hollow stem augers (no drilling water) and recorded groundwater depths were not affected by drilling. Water was encountered in TB-37 at elevations 576 and 550. The elevation of 576 is 5 ft lower than that found in 1969 in Boring C-176 and elevation 550 is 5 ft higher than that found in drilling the 1970 preconstruction well near the same location. Frequent water level readings were taken and usually stabilized in a few days. Selected piezometers were bailed and recovery readings were taken to verify functioning of the piezometer. Initial water levels and selected levels by date are shown in Figure 21. Bailed






Figure 21. Summary of groundwater conditions, 15 Mile Road/Edison Corridor Tunnel Failure Study

piezometers recovered within one to two days indicated relatively high mass permeability of the sand unit.

- (3) Groundwater levels. Three water profiles are shown on Figure 21. The upper profile is for conditions 192 to 1400 ft away from the tunnel after stabilization of piezometer levels in the sand which were not significantly influenced by dewatering. The second profile is for piezometers near the tunnel before the effects of dewatering. The third and lowest profile is along the tunnel after dewatering had its maximum effect. The two lower profiles slope upward to the south where they tie into the profile unaffected by dewatering. This trend indicates increased stratification of clays and water bearing sands to the south, as indicated by borings in Distressed Area 3 (Figure 18). The trend is supported by the fact that the five wells from Sta 115 south could not pull the water level as far down as wells north of Sta 122 (Figure 21). The water profiles before dewatering along the tunnel and at a distance of 1300 ft to 1400 ft from the tunnel dip down in the vicinity of Distressed Area 2. The reason is unclear but could be caused by a southwesterly seepage trend since the beach sand appears to slope to the southeast (based on the top of beach sand at elevations 560 in boring A-34 on Schoenherr Rd east of the site and elevation 530 in boring C-26 on Maple Rd to the west). Also the dip in the top of the beach sand at Sta 128 could indicate a buried channel with more permeable strata below elevation 540.
- (4) Groundwater conditions. Groundwater levels at elevations 581 in 1969 and 576 in 1971 near Sta 133 (see (2) above) indicates a perched water table in the clay at a depth of 29 and 34 ft, respectively. Groundwater encountered at elevations 545 in 1971 and 550 in 1980 in the beach sand near Sta 133 was seepage water under pressure. An artesian condition exists in this sand because piezometers at this location (No. 37) and west of the site (No. 39) in the beach sand, showed a significant rise in water levels for several days after initial readings. This is confirmed by the local groundwater conditions (para 46) and by bailing tests in piezometers MCG-1, Nos. 40, 29, and 38 (Figure 21). The estimated groundwater profile before dewatering is a measure of the reduced artesian pressure in the beach sand caused by the distressed tunnel segments acting as a drain. This condition is evident in Figure 21 from the difference in profiles before dewatering, and 1300 to 1400 ft from the tunnel, the level in piezometers No. 37 near 15 Mile Road (Sta 137) and No. 43, 1284 ft east of Sta 101+40. The latter groundwater elevations correspond to the natural artesian pressures in the sand

away from distressed segments of the tunnel. This higher water profile represents conditions that could have existed prior to start of distress and tunnel cracking. The profile before distress could have been higher or lower at times from 1972 to 1980 depending on rainfall and recharge conditions as described in para 57. From the above conditions, it appears that the sand along the tunnel base and tunnel construction joints was subject to water pressure heads of at least 13 ft to 22 ft above the invert during the interim period from 1972 to 1980.

62. Tunnel and surrounding soil condition. Seepage and sand infiltration (piping), soil conditions behind lagging, joint conditions, and visual observations relating to geotechnical considerations are described in this section.

a. Sand piping and tunnel leakage. During the field visit of WES structures and concrete engineers (just after cleaning out of the tunnel south of break 1) on 15 May 1980, seepage water and fine sand were observed flowing in at the invert of a construction joint at Sta 120+71. The water pressure at this location was equal to a head of about 2.5 ft above the base of the tunnel (see Figure 21). A photograph of this condition is shown in Figure 22. This location is in the nondistressed segment where waterstops were not placed in construction joints and where sand exists along the invert as shown in Figure 23. A sample of the sand was obtained and the gradation is shown in Figure 24. This gradation is very similar to that for the natural sands along the base of the tunnel (see soil test results, para 64). When a concrete core at Sta 117+70 (23 May 1980), 2 ft above the invert on the east side, was taken (with the last 0.05 ft of concrete drilled using a 2-in. air hammer), water seepage began piping sand into the hole. The water pressure at this location was equal to a head of about 2.5 ft above the wood lagging at the base of the core. Again at Sta 117+25, water seepage piped sand into the tunnel after a concrete core at the invert was removed from the hole. On several occasions, a packer in one of the core holes near the invert was knocked out during bracing operations and water seepage piped 1 to 2 cu ft of sand into the tunnel. Seepage also occurred from 2-in.-diam holes drilled through the tunnel wall to check soil conditions. After completion, a wooden plug was inserted. Several days later seepage, as shown in Figure 25, was evident around the plugs south of Sta 122+82. When some of the



Figure 1. Deep-seated water and fine sand flowing into
tunnel at location of construction joint, Sta 120+71,
tunneling through a highly permeable failure zone.





Figure 23. Summary of distressed tunnel profile and soil stratification, 15 Mile Road/Edison Corridor Tunnel Failure Study



ENG FORM 2087
1 MAY 83

Figure 24. Gradation of sand piped into tunnel at Sta 120+71,
15 Mile Road/Edison Corridor Tunnel Failure Study



Figure 25. Seeping water from plugged holes south of
Sta 122+22, 15 Mile Road/Edison Corridor
Tunnel Failure Study

plugs were removed, it was found that sand had been carried up into the hole by seepage water. The above incidents illustrate the piping characteristics of the beach sand under relatively low water pressure. Staining of the tunnel wall from water seeping out around the plugs and leaving an iron mineral deposit started several days after the holes were first plugged. Numerous construction joints and cold joints showed evidence of water leakage from staining and mineral deposits built up on the inside of the tunnel wall. An example of staining at a cold joint is shown in Figure 26. This area had waterstops in construction joints starting at Sta 118+62. Data summarized in Table 10 for the nondistressed area is indicative of conditions prior to distress in other areas. Water seepage was noted on 24 June 1980 at Sta 114+40 and 115+30 where the water pressure head was near the springline outside the tunnel. The water was clear with no apparent sand piping. The seepage at 114+40 was 1/2-in. high and coming through a narrow crack in the construction joint at the invert. At 115+30 water was seeping through a 1/8-in. crack in the west lower quarter.

- b. Soil conditions behind lagging. The 2-in.-diam air hammer holes in the tunnel wall were made at selected locations in distressed and nondistressed areas initially to check for voids beneath the tunnel just below the location of clay-sand strata contacts derived from boring logs. However, no voids were found behind the lagging. Use of the small core penetrometer was then decided on after a number of the holes were completed. The cone penetration tests were made to obtain a qualitative indication of the consistency of clays (stiff to soft), and sands (loose to dense). The results shown in Table 11 verified soil types determined from surface borings. However, the results of these borings and tests are not entirely representative of natural conditions because of dewatering which increased the soil resistance, especially for sands. In the accessible area north of break 1, the sand, silty sand, and silty clay was frozen to semi-frozen from Sta 132+36 to 132+12 and the relative consistency was not considered. South of break area 1 no soft or loose conditions were found until Sta 128+39 near area 2. At several locations adjacent to construction joints in Distressed Area 2, 1.5 in. to 6 in. of penetration was recorded, indicating relatively loose sands and soft clays. Similar penetrations indicated loose silty sand and sandy clay at or near construction joints in the nondistressed segment at Stas 124+92,



Figure 26. Example of straining indicating water leakage through cold joint,
nondistressed tunnel section

123+87, and 122+82. Behind the lower quarter on the east side at Sta 123+07, very soft sandy silt was penetrated 18 in. At 122+82 very soft sandy clay was found just behind the lagging. In Distressed Area 3, two holes in the east and west lower quarter indicated silty sand to sandy silt. These soil types correlated with those found in boring WES-10. However, no apparent loose condition was noted. Additional holes in this area were not made because of the higher groundwater pressures and the possibility of excess piping of sand into the tunnel.

c. Joint conditions. Construction joints in the tunnel showed the following conditions:

- (1) Pieces of construction joint from fractured areas in Distressed Area 2, Sta 128+07, east lower quarter and springline contained a firm deposit of silty sand on the joint face.
- (2) A concrete core was taken at Sta 115+45 in the east side of the Sta 115+47 construction joint. The tunnel at this joint is shown in Figure 27. The core was taken to check the competence of an undistressed waterstop joint just north of Distressed Area 3. As shown in Figure 28, a waterstop was found in the joint keyway. Also found was a piece of wood at the lagging side of the joint. The wood did not appear to be part of the lagging and could be a piece of wood used to block off the bulkhead from the lagging during concreting. The joint was iron stained on the tunnel side portion, indicating water leakage. The joint was clean with no signs of silt and no signs of waterproofing mastic.
- (3) At Sta 114+42, a small section of construction joint on the east lower quarter was filled with sandy silt behind a loose concrete cover piece about 4 in. thick. The area is shown in Figure 29. Subsequent digging into the silt indicated that it extended all the way through the joint. A waterstop and a piece of soft wet (partially decayed) wood was found in the digging process. Whether this wood was used to hold the waterstop out during concreting or was used to block off the lagging side of the concrete-form bulkhead is unknown. The waterstop and a piece of wood were also found high up in this joint.
- (4) Construction joints at Stas 113+37, 112+32, and 111+27 in Distressed Area 3 were checked using a geologist's hammer and drill to open the joints. Waterstops and wood were also found as noted in Table 12.



Figure 27. Location of concrete core at construction joint
with waterstop, west side, nondistressed area, Sta. 15+41.15
15 Mile Road/Edison Corridor Tunnel Failure Site

DRILLING LOG			DIVISION	INSTALLATION	Hole No.	SHEET
1. PROJECT <i>Detroit Sewer</i>			<i>Detroit</i>	<i>15 mile + Edison Corrid</i>		OF 1 SHEETS
2. LOCATION (Coordinate or Station) <i>Station 115+45 - West Well Water Stop</i>				10. SIZE AND TYPE OF BIT <i>6 x 6 1/2</i>		
3. DRILLING AGENCY <i>CSWSS</i>				11. DATUM FOR ELEVATION SHOWN (FBM or MSL) <i>Bit No. 80PK 167-1</i>		
4. HOLE NO. (As shown on drawing title and file number) <i>115+45 - West W. II</i>				12. MANUFACTURER'S DESIGNATION OF DRILL <i>Longyear</i>		
5. NAME OF DRILLER <i>B. Harrell</i>				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN	<input checked="" type="checkbox"/> DISTURBED	<input checked="" type="checkbox"/> UNDISTURBED
6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT.				14. TOTAL NUMBER CORE BOXES		
7. THICKNESS OF OVERBURDEN				15. ELEVATION GROUND WATER		
8. DEPTH DRILLED INTO ROCK				16. DATE HOLE	<i>6/30/60</i>	<i>6/30/60</i>
9. TOTAL DEPTH OF HOLE				17. ELEVATION TOP OF HOLE		
18. TOTAL CORE RECOVERY FOR BORING				19. SIGNATURE OF INSPECTOR <i>Gray B. Smith</i>		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
	0.0		Break			ML Run 15'
			Fert Staining			Began 3'00
			Waterstop (Plastic/Walk)			End 4'50
	1.0		Break			Time 1.54.5
			Waterstop			Drill time 1.54.5
			Run (0.0 to 1.5')			Hyd press
	2.0		Wood			Water press
						End 5.01
						Drill Action Smooth
						Water ret
						14.5000
						Remarks

Figure 28. Log of concrete core of waterstop joint in nondistressed area




Figure 29. Construction joint, east side of the structure.

AD-A096 440

ARMY ENGINEER WATERWAYS EXPERIMENT STATION VICKSBURG--ETC F/6 13/2
15 MILE ROAD/EDISON CORRIDOR SEWER TUNNEL FAILURE STUDY, DETROIT--ETC(1
JAN 81 D ALBERT, G C HOFF, B LORENCE NCE-IA-80-055
UNCLASSIFIED WES/TR/6L-81-2 NL

2 OF 5
40 - 40.0




- (5) A concrete core of a cold joint in the nondistressed area between Distressed Areas 2 and 3 was checked when received at WES. The core separated easily at the cold joint and contained a thin veneer of fine sand.
- (6) The above information indicates that construction joints in Distressed Areas 2 and 3 contained silty sand, that very fine sand existed in cold joints in the nondistressed area, that the waterstop in a non-distressed area contained wood and experienced leakage. In addition, when the tunnel section south of Distressed Area 1 was cleaned out in early May 1980, a considerable amount of fine sand was removed. The competence of waterstops in construction joints in Distressed Area 3 could have been detrimentally affected by wood found in the keyways.

Soil properties


63. Soil properties from WES laboratory tests are summarized in this section. A test data summary sheet is shown in Table 13 and detailed test results are contained in Appendices B through E.

64. Soil classification and sand gradation. Laboratory classifications were performed on sections of undisturbed samples trimmed into specimens for different tests, and whole samples selected for physical property tests and special piping tests. The results indicated that soils at the site were more variable than indicated on graphical logs of borings. Gradation curves (Appendix B) summarized in Figures 30 through 32 and Atterberg limits (Table 13) show that some samples recovered from the beach sand unit classified in the field (from material in the ends of undisturbed sample tubes) as fine sand often contained more silty and clayey strata. This condition was previously noted in paragraph 60 from gradation data shown in Figures 14 through 18. However, jar samples from split spoon borings indicated strata of very fine sand similar to the gradation of sample 38, boring WES-1 (Figure 30). The sample of silty sand piped into the tunnel at Sta 120+71 (Figure 24) indicates that very fine cohesionless sand exists along the tunnel. The gradation of the fine sands is further illustrated in Figure 33 by the grain size distribution curves shown from the CS-858 contract drawings for the



ENG FORM 2087 REPLACES WES FORM NO 1241, SEP 1962, WHICH IS OBSOLETE
(MAY 83)

Figure 30. Gradation of samples from boring WES-1, 15 Mile Road/Edison Corridor Tunnel Failure Study



NEVER, TISEQ & HINDO, LTD

GRAIN SIZE DISTRIBUTION CURVE

PROJECT NO. 77803
 PROJECT LOCATION 15 Mile and Edison Corridor
 BORING NO. 1, 5 and 21
 SAMPLE DESCRIPTION GRAV FINE SAND TO SILTY FINE SAND
 DATE SAMPLED FEB 1980
 BY NTL Ltd. DATE TESTED Feb 1980
 U.S. STANDARD Sieve Size
 SOURCE Test Boring Nos. 1, 5 and 21
 FOR Tunnel Repair
 See Below
 SAMPLE DEPTH See Below
 SAMPLE ELEV. (TIP) -
 CHECKED BY -





Figure 33. Gradation of samples from borings TB-1, TB-5, and TB-21, 15 Mile Road/Edison Corridor Tunnel Failure Study

temporary bypass and pumping shaft. The curves of interest are those labeled "native soils" for depths of 70 to 79.5 ft from TB-1, TB-5, and TB-21. These borings were located just north of and in break area 1. During clean out of break area 1, a large amount of sand was found under other soil and concrete in the tunnel. The lower segment of the tunnel at break 1 had settled about 5 ft into sand along the base of the tunnel. The gradations for two jar samples from the sand deposit in the tunnel are shown in Figure 34 and are similar to gradations for the silty sand from Sta 120+71, sample S-4 (TB-5) and sample 38 from boring WES-1.

65. Physical properties. Water contents, Atterberg limits, and wet unit weights for selected undisturbed samples from borings WES-3 (Sta 130+20) and WES-4 (Sta 112+81) are shown according to elevation in Figure 35. Specific gravities for the clay materials were uniform with values of 2.74 to 2.76.

- a. Water content. The water contents of samples for Sta 132+20 were higher at depth than at Sta 112+80, perhaps due to the greater water seepage source from the dump material and the existence of more plastic clays at Sta 130+20. Water contents of samples from boring WES-4 (Sta 112+81) between elevations 590 and 555 were higher than those before construction at Sta 111+80 (boring C-222, Figure 10). These are the only two borings close enough to compare water contents after distress with those before construction. Thus, water contents after tunnel distress in area 3 appear to be higher than before construction. The water contents before tunnel distress could have been slightly higher since about two months of dewatering and drainage of soils around the tunnel occurred before boring WES-4 was made. In the upper 15 ft at Sta 112+81, water contents were near the liquid limits, indicating normally consolidated soils; at depths below elevation 590 water contents were close to the plastic limit, indicating an overconsolidated condition.
- b. Wet unit weights. The total unit weights (as indicated by wet density) are shown in Figure 35 since they relate to the existing total overburden pressure. Wet densities of about 129 to 143 pcf for samples from Sta 130+20 (under the dump) are generally lower than






Figure 35. Water content, plasticity, and wet unit weight versus depth

those at Sta 112+81 (dry densities also are lower). The wet densities at Sta 112+81 increase with depth to 152 pcf (at the tunnel crown in Distressed Area 2), then show a marked decrease for the sandy clay above the springline. However, this decrease may be a result of natural variation since unit weights for samples from boring WES-4, between elevation 553 to 558 (Figure 35), are almost the same as those for samples from boring C-222 (Figure 10). The density of the silty sand samples (below elev 539, Figure 35) are not as dense as would be expected from the blow count data. Since sampling causes stress release, the samples tend to expand and may be further disturbed during handling and transit to the laboratory. This is especially true for silty sand and sand samples. Consequently, unit weights can be lower than they are in situ. When clay samples were opened in the laboratory, some were noted to have cracks indicative of stress release. Consequently, all test results should be considered with the above in mind.

66. Special piping tests. To assess the piping susceptibility of sands and silts around the tunnel, six undisturbed samples were tested. Five samples were selected from those recovered from the sand unit along the base of the tunnel and one from the sandy clay strata at the tunnel crown. The selection of samples was limited since the fine-grained sands along the tunnel and in the beach sand unit were easily eroded out of the tubes during field sampling. Recovery was low, in spite of attempts to obtain complete samples (using core catcher strips in 5-in.-diam tubes, heavier drilling mud, and pushing 3-in.-diam sample tubes). Although most samples tested had homogeneous pockets of sand, they also had varying amounts of silt and clay. The samples tested and a summary of test results are listed in Table 14.

- a. Initial tests. The first two samples were tested with a 1/16-in. wide longitudinal slot cut along the central one-third of the sample. These samples piped material next to the sample tube interface where the least resistance to flow occurred. To provide better distribution of seepage piping, the longitudinal slots were sealed and five short circumferential slots, 1/32 in. wide, were cut around the middle of these samples and the samples retested. When a sample preserved in wax and cardboard tube (WES-4-20) was tested, the slots

tended to swell shut and further tests were restricted to samples in steel tubes.

- b. Piping sequence. When the water pressure was raised to 2 or 3 psi at the start of a test, soil particles began streaming out of the lower slot as shown in Figure 36. More material usually flowed out of slots in the sides than out of the slot in the top. Very little material flowed out of slots in the bottom, probably due to the weight of the sample against the bottom of the tube. Under a given pressure, piping ceased after several minutes. If the water pressure was then shut off, allowing "soil readjustment" for several hours (at zero pressure), a small amount of piping could be reinitiated when the same pressure was again applied. Piping occurred readily from samples containing less dense sands and silts having little or no cohesion.
- c. Sample erosion. Examination of samples after testing revealed erosion primarily along the top half of samples and also along the sample and tube interface. An example is shown in Figure 37. Samples tested were not tight against the tube. Erosion along an interface (such as between the tunnel lagging and adjacent soil) would be expected because of the likely existence of small voids. This condition would allow water under pressure to seek the path of least resistance, picking up soil particles along its route. An anomalous erosion path occurred in sample WES-4-32, as shown in Figure 38. This sample developed a circular piping hole that continued to the slots at the middle of the sample. During testing, a sudden rise in water pressure was made inadvertently. It is suspected that this pressure jump started the hole in the center of the sample. However, the other end of the sample eroded in the usual manner.
- d. Piping susceptibility. Because of the heterogeneous quantities of sand, clay, and silt in the samples and variation in erosion, a quantitative scale of piping susceptibility for the sands and silts cannot be established. However, it was evident that the sands and silts readily piped under water pressures as low as 3/4 to 2 psi. This pressure is equal to a head of water of only 1.7 to 4.6 ft. The first sample tested was predominantly fine- to medium-grained sand and began piping rapidly under the low water pressure of 3/4 psi. The gradation of the piped material versus material left in the sample is shown for tests on sample WES-1-34 and WES-1-38 in Figure 39. The piped material gradation is similar to silty sand piped into the tunnel (Figure 24).




Figure 6b. Special piping test in progress, 19 Mile Revolution Carrier Tunnel Failure Study




Figure 36. Erosion of sample after special piping test, 15 Mile head, Edison, Corvair, and Edison.



Figure 32. High hole in sample after test, 15 Mile Road/Edison Corridor Tunnel Failure Study





Figure 39. Comparison of parent and piped material gradation

Slot openings of 1/16-in. and 1/32-in. were selected as a practical minimum corresponding to possible construction joint openings. While these slot widths would not apply to the much smaller openings in cold joints, the minimum size of joint openings for the susceptible sands and silts with little or no cohesion can be estimated from criteria used for slotted drain pipes. To prevent soil infiltration, the slot width for drain pipes used to collect subsurface seepage is required to be equal to or less than the D_{50} size (mean particle size) of the soil next to the slot (Department of the Army TM 5-818-1). For the gradations shown in Figures 33 and 38, the D_{50} size varies from 0.15 to 0.6 mm and corresponds to a slot width of 0.006 to 0.02 in. Based on this criteria, fine sands and silts could be piped through joint openings as small as 0.01 in. which could correspond to cold joint openings.

- e. Pinhole erosion tests. Results of pinhole tests on silty clay and clayey silt in a sample from the tunnel depth (WES-1-32, 53 to 54.7 ft) indicated no susceptibility to piping erosion. This result would be expected for cohesive soils.

67. Consolidation characteristics. Specimens trimmed from the two samples of clay (WES-4-12, 21 to 22 ft, and WES-3-18, 55.5 to 55.6 ft) used for consolidation tests (Appendix C) showed the clay to be overconsolidated. The estimated overconsolidation ratios (OCR) were about 3.8 for the clay at a depth of 21-22 ft and 1.4 for the clay at a depth of 55 ft. Based on a relationship of K_o versus plasticity index ($PI = LL - PL$) and OCR by Brooker and Ireland (1965), the estimated K_o values were 0.8 for the 21-22 ft depth and 0.43 for the 55-ft depth. The higher value at the 21-22 ft depth may be related to overconsolidation from dissipation (para 40). Constrained modulus values were determined for the estimated in situ vertical effective stress by plotting the consolidation load and deformation as a stress strain curve. The estimated values were 2570 and 2890 psi, respectively for the depths of 22 and 55 ft. These values correspond to a drained condition with no lateral yield.

68. Drained direct shear strength. Standard direct shear tests (Appendix D) were performed on specimens from samples of lean clays and sandy clays from depths of 41 ft in boring WES-3 and 10, 25, 50, and 52 ft in WES-4. Each test included three specimens consolidated under a range of loads spanning the estimated in situ vertical pressure at the sample depth. The shear stress peaked and then decreased with increasing horizontal deformation, indicating a brittle type material in which the shear strength decreases after a small displacement. As listed in Table 13, the lowest strength ($c = 0.1$ tsf, $\phi = 24$ deg) is for clay at a depth of 10 ft. The strength parameters below the dump at a depth of 41 ft were $c = 0.15$ tsf and $\phi = 26.5$ deg. For the sandy clay at the 50 to 52 ft depth near the tunnel crown in Distressed Area 3, strength values were $c \approx 0$, $\phi = 28.5$ deg and 33.5 deg. The strength of clay below the dump just south of Distressed Area 1 for the one test is slightly lower than that in Distressed Area 2.

69. Results from $K_o \bar{R}$ tests. The results of special $K_o \bar{R}$ triaxial compression tests (Appendix E) on four 2.8-in.-diam specimens are summarized in Table 15. After K_o consolidation to the estimated in situ vertical stress using stress controlled loading, the axial loading was increased with no drainage until a straight line on a Mohr stress plot was well established. Induced pore water pressures during undrained loading changed from positive to negative and the line of constant slope indicated a negative cohesion for three of the tests (WES-3-24, WES-4-24, and WES-4-30). For the three tests, the failure condition was taken at zero induced pore water pressure and zero cohesion to establish a ϕ value.

- a. K_o values. The values of K_o appear reasonable since they tend to agree with the value of 0.43 based on the consolidation test on a specimen from sample WES-4-24 which was also used for one of the $K_o \bar{R}$ tests. Thus, it appears that the in situ K_o values after tunnel distress and dewatering are in the range of 0.4 to 0.45. A range of 0.4 to 0.5 is considered reasonable for conditions prior to distress.

- b. Modulus values. The deviator-stress-strain curves for undrained loading (in which the effective and total deviator stress values are equal) showed an increase in slope at strains where induced pore water pressure became negative. The modulus values were determined from the initial segment of the stress-strain curve and show a lower value for the silty clay (CL) specimens than for the silt and interbedded sand-silt specimens. This appears reasonable since values for less cohesive soils such as dense silts and fine sands are usually higher. Data in Table 16 for similar glacial lake materials, show a range of modulus values estimated for this report from the results of two standard \bar{R} triaxial tests reported in the Midland FSAR. Only materials below a depth of about 180 ft (elevation 420) at the Midland site were reported to have been heavily overconsolidated by ice loading in past geologic history. Ground surface at Midland is at about elevation 600 and corresponds with the tunnel site ground surface elevations and confirms that overconsolidation of materials above elevation 520 at the tunnel site is not due to ice loading. It can be noted from Table 16 that while cohesion values were obtained in these tests, the ϕ values are similar to those for the $K_o \bar{R}$ tests in Table 15.

Analytical studies

70. Analyses were made to estimate in situ vertical and lateral pressures for use in the structural finite element analyses in the subsequent structural section of this report. The range of values of effective and total stress earth pressure coefficients, Poisson's ratio, and modulus of elasticity applicable for soils at the site were also determined. Changes in the in situ stresses after restoration of the groundwater and potential water and soil infiltration into the tunnel were also analyzed. These analyses are summarized below.

71. In situ stresses. Vertical and horizontal pressures were estimated for two conditions on the basis of wet unit weights from undisturbed samples and K_o values from $K_o \bar{R}$ tests. The first condition, as shown in Figure 40 at boring WES-3, Sta 130+20 (just south of Distressed Area 1), is during mining with dewatering. The second is before and after construction when the water table returned to a




Figure 40. Estimated in situ soil stresses, Sta 130+20

natural condition at about elevation 566 (based on measured piezometric levels 1300 to 1400 ft from the tunnel (para 61 g)).

- a. Vertical pressures. Total vertical stresses are based on total unit weights. A perched water condition exists in the dump area and the water and material in the dump rest on the underlying soils as if contained in a bathtub. Drainage of the dump is prevented by the underlying plastic and impermeable clays. The perched water level is based on the log of boring TB-24 that showed fill with some debris to a 6-ft depth and that groundwater was encountered at the same depth (considered reliable because the hole was advanced with a solid stem auger to 10 ft and cased to 12.5 ft). The saturated unit weight of 110 pcf for dump material was based on the loose, caving conditions in boring WES-2 (para 60). Effective vertical pressures are based on submerged unit weights of soils below the water levels shown for conditions A and B. The artesian pressure acting in the beach sand unit is assumed for condition B to rise through the lean clay and sandy clay which is stratified with silt and sand seams. A similar plot of vertical pressure versus depth is shown in Figure 41 for Sta 112+81 (adjacent to Distressed Area 3). Vertical stresses are only about 0.3 tsf higher than at Sta 130+20 and the stresses shown for Sta 112+81 are representative of stresses at locations other than the dump area.
- b. Horizontal stresses. Effective horizontal stresses are equal to K_0 (the effective stress coefficient of earth pressure at rest) times the effective vertical stress. The effective stress is equal to the total stress less the pore water pressure. For the drained condition with no pore water pressure during dewatering, the effective stress was taken as equal to the total stress. The values of K_0 shown in Figures 40 and 41 are based on the K_0 test results (Table 15) and K_0 values estimated from consolidation test data. The K_0 values are affected by stress release of ground pressure during sampling and may be low. Consequently, effective horizontal stress lines for an upper limit for K_0 of 0.6 are shown on Figures 40 and 41 to bracket possible values. A value of 0.65 was determined for very dense highly overconsolidated glacial till north of Toronto (Radhakrishna and Klym, 1974) and a value of 0.6 is considered an upper limit for the dense materials at the tunnel site. When total stresses are considered beneath the water table for saturated




Figure 41. Estimated in situ soil stresses, Sta 112+80

soils, a total stress at rest coefficient (K) is used and determined (Dunlop, Duncan, and Seed, 1968) from:

$$K = K_o + (1 - K_o) (\gamma_w / \gamma_{sat})$$

where γ_w and γ_{sat} are the unit weight of water and of saturated soil, respectively. Listed below are values of K and corresponding ν values used in calculating estimated horizontal pressures on soil boundaries for the structural analyses. Corresponding values of ν' and ν (effective and total Poisson's ratio, respectively) are also shown ($\nu = K/(1+K)$). These values change very little as shown in Figure 42 for the range of saturated unit weights (136 to 152 pcf) used to determine in situ stresses.

K_o	ν'	K	ν
0.40	0.29	0.67	0.40
0.60	0.38	0.78	0.44

Values of K and ν for total pressures are higher and have less variation than K_o and ν' values. Thus, K values of 0.7 and 0.8 were selected to cover the possible range for in situ conditions.

- c. Modulus values. Modulus of elasticity (E) values needed in the structural analyses were based on those in Table 15 from K_o undrained loading. Sample stress release affects laboratory measured values. Studies of E values from in situ field tests and laboratory tests show that field measured values for highly overconsolidated till are as much as twice the laboratory values (Radhakrishna and Klym, 1974). Consequently E values in Table 15 were increased by a factor of 1.5 to account for stress release and possible disturbance. The value recommended for the 60 ft clay and silt unit was 3000 psi. A value of 6000 psi was recommended for fine sands to sandy silts in the beach sand unit. These values also tend to agree with those in Table 16 for the Midland Nuclear Plant Site.
- d. Effect of restored groundwater. As shown in Figures 40 and 41, restoration of the groundwater results in lower vertical and lateral effective stresses from the buoyancy effect of the water. However, the total




Figure 42. Range of at rest earth pressure coefficient K_0 and K versus unit weight, 15 Mile Road/Edison Corridor Tunnel Failure Study

stresses in the soil below the restored water level are essentially the same as during dewatering since the total vertical and horizontal pressures include the water pressure. The total stress horizontal pressure is K times the total vertical pressure. Water pressures in the sands, silts, and clays increase linearly with depth below the restored groundwater level as shown in Figure 40 and 41. The sands and silts with little or no cohesion were found to be susceptible to piping (para 66) with the cohesionless sands being highly susceptible, under water pressures as low as 0.75 psi. The water pressures in the soils around the base of the tunnel would be equal to the effective water level above the tunnel at elevation 560 to 568 (as a minimum, Figure 21) less the water level in the tunnel at approximately elevation 550 (for a water depth equal to about one-fourth the inside diameter). This difference in elevation would correspond to an effective head of water of 10 to 18 ft or 4 to 8 psi. For soils around the tunnel but above the water level inside the tunnel, the water head would be equal to the difference between the soil elevations and effective water level elevations (minimum of about 8 ft or 3 psi at the springline). These water pressures are more than those required to cause piping. Consequently, material from fine sand and silty sand and silt strata supporting the sides and/or base of the tunnel would be piped into the tunnel through leaking joints. The supporting strata would loosen from loss of volume and a gradual loss of ground support would increase with time at the base and sides of the tunnel. Based on this series of events, the estimated in situ total stresses and soil properties for the following cases were provided for use in the structural analyses:

- (1) Full overburden pressure (total vertical stress, σ_v) acting in the soil above the tunnel and horizontal pressures increasing with depth in the soil outside the tunnel of 0.7 to 0.8 times the vertical pressure (K times σ_v). These pressures would simulate conditions several years after construction when full overburden stresses would be developed over the tunnel.
- (2) Using the above conditions, reduce the support at the bottom and then at the sides of the tunnel simulating piping and loss of support from pipeable strata found to occur along the tunnel base in all areas and along the tunnel sides in Distressed Areas 1, 2, and 3.

Structural

Concrete investigations

72. The following list of documents was used in preparing and evaluating the information and data contained in the Concrete Investigations portion of this report:

- a. "Tests of Cement," Pittsburgh Testing Laboratory Report, Order No. 71956, Date: October 19, 1971, to the City of Detroit (Huron Portland Cement Type IA).
- b. "Test Sample Identification Report," P. O. No. D16667, Date: September 15, 1971, Detroit Metropolitan Water Service, Engineering Division (Huron Portland Cement Type IA).
- c. "Physical Portland Cement Test Results," T.E.C. Report No. 9275-8, Date: 3 November 1970, Testing Engineers and Consultants, Inc., Detroit, MI, for Detroit Metropolitan Water Services (Peerless Type I Portland Cement).
- d. "Mechanical Analysis Report, Test No. 168, 6A Natural Aggregate," Metro Water Department-Detroit, Division of Engineering, Date: 15 July 1971.
- e. "Mechanical Analysis Report, Test No. 169, 2NS Sand," Metro Water Department-Detroit, Division of Engineering, Date: 15 July 1971.
- f. "Concrete Test Cylinder Reports," Detroit Metropolitan Water Service, DE 9187:

<u>Report No.</u>	<u>Date</u>
614	25 April 72
627	2 May 72
632	3 May 72
644	9 May 72
659	16 May 72
710	19 June 72
720	27 June 72

- g. "Inspector's Report," City of Detroit, Department of Water Supply, Division of Engineering, Form D-144-B0-A for the period 15 April 1972 through 12 June 1972.
- h. "Contract Documents for Oakland-Macomb Interceptor System, Corridor Interceptor - Section III, Division 2, Concrete," Detroit Metropolitan Water Services, Pollution Control Program, Contract No. PCI-7, September 1969.
- i. Letter from Charles Beckham, Detroit Water and Sewerage Department to Lawrence Maloney, Detroit District, Corps

of Engineers, Date: 20 June 1980, regarding: Sewer Tunnel Failure - 15 Mile Road and Edison Corridor, Sterling Heights, Michigan.

- j. Compilation of 163 color photographs taken between May and July 1980 of the entire tunnel from Sta 110+00 to 133+79.

73. Visual observation

- a. Visits were made to the site by the WES team on 12-29 May 1980 and 19-20 June 1980. The first visit involved a visual inspection of the tunnel, photographic documentation, loose sample collection, tunnel deformation measurements, drilled core location selection, and the starting of the concrete drilling operation. The second visit was to ensure that all concrete sampling was satisfactorily completed before the drilling equipment was dismantled and removed from the tunnel. Upon entering the site, several piles of large concrete blocks and debris could be seen stored to the side. The blocks were approximately 1/2 cu yd in size and mostly irregular in shape. From close inspection of the debris, small holes had been drilled for easier removal of a portion of the tunnel concrete down to the springline for installation of the access shaft. The holes were approximately 2 in. in diameter and apparently drilled through the entire blocks. Each block had several holes spaced 5 or 6 in. apart.
- b. Entrance into the Oakland Macomb Interceptor Sewer was by a 4-ft-diam manhole about 50 ft deep. In the tunnel the lighting was inadequate and visibility was poor. Hand-held flashlights had to be used to supplement the lighting. Inspection of the invert was impossible because of the sludge remaining in the sewer. Interest was concentrated on the crown and two springlines until the sludge could be removed.
- c. Distressed Area No. 3, located between Stas 115+50 and 111+25, was the longest damaged area of three distressed areas. Area No. 3 had a series of longitudinal cracks along the crown, almost the entire length of the break area. The width of the longitudinal cracks was 1-1/2 in. at the widest point near Sta 114+00. These longitudinal crown cracks appeared to be fractured the entire depth of the concrete, with most cracks running perpendicular to the surface. This was confirmed as a steel rod was slid into the crack and the approximate angle was noted.
- d. Branches of cracks diverged from the longitudinal cracks down to the springlines where they joined two rows of small fractures on both walls. The fractures appeared similar to those of a shear failure, where the fractures

were short and angular and primarily in a straight row.

- e. Following the final clean-up of the sludge in Distressed Area No. 3, the invert was noted to have several longitudinal cracks along much of the break area. Along Sta 114+25, the longitudinal crack appeared to be up-lifted some 3 in. This looked as though the invert was under pressure, finally cracked, and lifted up on one side. Seepage of groundwater was occurring through the cracks in the invert.
- f. With construction joints located every 105 ft, the circumferential cracks that existed were easily distinguished from the normal construction joint. These circumferential cracks looked very similar to the construction joints in that the cracks were almost perfectly straight and smooth. Seepage of ground water could be seen coming in through the cracks that were as wide as 3/4 in.
- g. At Sta 114+42 some material had filled a void near the springline in the concrete. The material was some type of silty sand. It appeared that the void was from construction and that the sand had seeped in to fill the void. With much of the material removed, the void was measured to a depth of at least 15 in.
- h. Also at this station (Sta 114+42), the north end of a 105-ft section that began at Sta 113+37, the invert from the 5:00 o'clock to the 7:00 o'clock position had sunk 4-1/2 in. Water and sludge had begun to pool from the seepage.
- i. Several locations in Area No. 3 had small cracks and crevices where groundwater was springing up about 1-1/2 in. This was caused from the water table being up near the springline. Water pumps were on continuously to keep the water in the tunnel to a minimum.
- j. Moving upstream from Area No. 3 in the nondistressed area, lines representing the cold joints in the concrete could easily be seen. The concrete apparently flowed downstream or south as it was being placed from the angle of the cold joints. The WES drill crew took concrete core samples from a cold joint to determine whether it had any detrimental effects on the concrete. Also at this station (Sta 119+15), another core was taken from another cold joint that exhibited some efflorescence. Efflorescence is a deposit of salts, usually white, formed on the surface of concrete. For efflorescence to occur, water is needed to carry the salts contained in the concrete to the surface of the concrete, either by vapor transfer or by liquid diffusion. In liquid form, appreciable

quantities of soluble salts are deposited at or near the surface of the concrete when the water evaporates. If there are cracks or joints present, the water moves quickly along these surfaces carrying the salts with it. The core revealed a clay-like sludge just under the surface and extending back several inches through the core. Then the sludge appeared to extend perhaps the entire thickness of the concrete wall.

- k. Of the three distressed areas, Area No. 2 was the only area where no concrete had fallen into the tunnel. Area No. 2 was highly fractured with longitudinal cracks in the crown and invert. Cracks at an angle of 50 to 60 deg with the horizontal were all along the springlines, extending up to the longitudinal cracks in the crown. Massive pieces of concrete appeared to just dangle in the crown and springlines. The invert had a few locations where the concrete sunk an inch or two. In a couple of circumferential cracks, efflorescence and water appeared seeping through the concrete.
- l. Distressed Area No. 1 was the most damaged area. Here the massive pieces of concrete along with the steel ribbing and wood lagging had collapsed into the tunnel. Area No. 1 had concrete that was actually dangling from the crown. For safety reasons the new ribs and lags were installed in this area first, both on the north and south ends of the collapsed area. Concrete in Area No. 1 exhibited similar cracks as those in the previous areas--longitudinal cracks in the crown and invert, with angular cracks in the walls. There appeared to be more cracks running in other directions than before. The concrete did not exhibit any efflorescent deposit, nor was ground water seepage visible. The concrete in Area No. 1 had no rebars (or no rebars that were visible). The concrete thickness appeared to be adequate when observed.
- m. Figure 43 shows a typical horizontal cold joint accompanied by slight honeycombing. This type of condition was prevalent throughout the tunnel except that most cold joints were inclined from 10 to 20 deg from the horizontal. Figure 44 shows another typical cold joint but with efflorescent deposits due to passage of liquid through the joint. Figure 45 shows a large inclusion of mud that either fell into the concrete during casting or that was extruded into a honeycomb void in the concrete. Table 17 is a summary of the concrete data.

74. Crack patterns

- a. Photographic documentation (163 photographs) was made for the entire length of tunnel in question (Sta 110+00 to 113+79). These photographs show the extent of cracking




Figure 4.3. Typical horizontal cold joint and slight honeycombing seen on interior wall of culvert; this was not an area of failed concrete



Figure 44. Cold joint on inner culvert wall in another nonfailed area;
this joint shows efflorescent deposits due to
passage of liquid through the joint



Figure 45. Inner surface of culvert wall at Sta 114+42; the blob in the center of the photograph is what fell into place between concrete lifts during the construction of the culvert. The blob was extruded into a honeycomb void, the size of which was at least 15 in. deep into the wall.


that existed at any location during this study. In order to obtain a composite view of the cracks, an overlapping series of 35-mm photographs were taken of the fractured surface area between Stas 113+25 and 114+75. This 150-ft section approximates Area 3. The photographs, which were taken at the invert, water line, springline, center line, and crown at each location, were put together in an overlapping manner to form a one-dimensional mosaic of the tunnel. Because of the photographic technique used to make the photo mosaic, the magnification of pictures near the invert was greater than that of the pictures made near the crown. The cracks in the photographs were then sketched on paper and scaled down to a more manageable size. The resulting crack pattern for Area 3 is shown in Figure 46. Insufficient photographs at Areas 1 and 2 prevented a complete mosaic compilation in those areas, but the patterns are similar to Area 3. The perspective in viewing Figure 46 is that the round culvert is drawn as if it were flat. The true orientation of the cracks can be obtained by rolling a copy of Figure 46 into a tube around the longitudinal axis of the tunnel and placing the crown or invert in the proper location. Figure 46 shows all forms of cracking, i.e., longitudinal, circumferential, and diagonal. Evidence of crushing at the springline also can be seen. The water line indicated is actually the water mark that existed at the time of the survey. It was very pronounced due to the collection of solid matter left on the wall.


- b. Cracks were also present in several of the drilled cores that were obtained from the tunnel. Figures 47, 48, 49, and 50 show some typical cracks in cores.

75. Nondestructive measurements

- a. Nondestructive measurements were obtained from the collapsed tunnel using a testing apparatus called the Schmidt Concrete Test Hammer. These measurements are used to estimate concrete strength. The Schmidt Hammer is a calibrated spring-operated impact device that is triggered as it is pressed against any hardened concrete surfaces. As the plunger impacts against the concrete surface and rebounds back through the hammer, the spring measures the amount of impact exerted and displays a numerical "Rebound Number." Empirically the correlation between rebound number and strength of the concrete has been derived from a great number of hammer tests.
 - b. In the WES evaluation of the concrete, compression tests were performed on several cored concrete specimens taken from the sewer tunnel. Prior to compression tests, the Schmidt hammer was used on all the specimens. Rebound

Blank






SCALE IN FEET

5 0 5 10




2

V



NOTE: NO EXACT SCALES CAN BE ASSIGNED
BECAUSE OF SOME PHOTOGRAPHIC
DISTORTION. THE POSITIONS OF THE
CROWN, SPRINGLINE, AND WATER
MARK WERE APPROXIMATED FROM THE
PHOTOGRAPHS.

Figure 46.



46. Crack pattern, Distressed
Area 3



Figure 47. Six-in. diameter culvert core DET-4 CON-21 drilled over a crack at Sta 113+45 in Distressed Area 3




Figure 48. Above are DET-4 CON-21 crack surfaces opened along crack to show sediment coating




Figure 49. Six-in. diameter culvert floor core DEF-4, CON-26 that intersected a crack, Sta 14+70, in Distressed Area 3



Figure 50. Above core DET-4, COM-26 opened on the crack; this crack was not coated with sediment; the powdery material is sawdust

numbers were taken on both the inside sewer surface and on the ends and the sides of twenty-four 6- by 12-in.-long cores. The results of the compressive tests ranged from 4440 to 7870 psi. The actual compressive strengths and the accompanying Schmidt hammer readings are shown in Table 18.

- c. In obtaining the rebound numbers from inside the sewer tunnel, a 10-ft ladder or a special platform was needed to obtain readings taken from the crown and the two springlines. The curved tunnel surface and the slippery greasy sludge on the concrete surface made it difficult to reach the springlines and also the 12-ft-9-in. diameter of the tunnel made it difficult to test the concrete in the crown.
- d. Rebound numbers were obtained at every station location that was involved in any other part of the concrete investigation. That is, when the core drilling crew took a concrete sample at a particular station, the Schmidt hammer was used to obtain rebound numbers from the crown, the invert, and the two springlines. Readings were also taken at all diameter change measurement stations. Four hammer readings were obtained from each of the four locations at each of the 35 stations evaluated by the WES (Table 19).
- e. Measurements were made as close to specified locations as possible. Cracks, irregular surfaces, large coarse aggregates, and sludge hindered the measuring at several locations. In Distressed Area 1 the ribbing and lagging were being installed as a safety precaution and as part of the repair work. This caused most of the measurements at these particular stations to be taken off-center of the four locations.
- f. The Schmidt hammer is designed to measure concrete that is in the vertical position with the hammer perpendicular to the surface or horizontal. Any deviations from the normal position, such as measurements taken from the crown and the invert, had to be corrected for inclination.
- g. Detroit District personnel assisted the WES in obtaining the Schmidt hammer readings and also in obtaining a spare Schmidt hammer when the one from the WES was inoperative.
- h. Rebound numbers obtained ranged from a low of 16 in the invert to a high of 48 in the crown. The rebound numbers suggest that for the most part the concrete in the crown and walls is fairly similar over the entire length of the sewer studied. The rebound numbers obtained in the invert are consistently lower, however, suggesting a

poorer quality of concrete in this location. The strength values for invert cores do not bear this out, however. Upon closer examination of the rebound numbers taken on the drilled cores from the invert, the following trend results:

Station	Rebound Number	
	Core End	Core Side
132+50	29	37
127+50	38	33
117+25	34	39
114+70	30	43
113+45	28	34
112+18.5	31	41

With one exception (Station 127+50), the rebound numbers obtained from the surface that had been in contact with the sewage are consistently lower than the rebound numbers obtained from the portion of the core (center 12 in.) that was tested for compressive strength. As the rebound number is solely a measure of surface hardness, this suggests that there apparently was a softening or deterioration of the surface of the concrete in the invert but that once past the surface the concrete was similar to all the remaining concrete in the portion of the sewer studied.

- i. In summary, the Schmidt hammer rebound numbers indicate that the quality of concrete between Stas 133+50 and 111+00 is fairly uniform. No significant deviations were observed.

76. Drilled core program

- a. The objective of the drilled core program was to obtain representative samples of the concrete from all three break areas plus some cores from nondistressed areas and areas of special significance. In the break areas and nondistressed areas, cores were obtained from the crown, invert, and springline at each location. In general, care was taken not to include any visible cracks in the cores unless specifically desired. All cores were 6 in. in diameter. A total of 32 cores was obtained from the following locations:

Station No.	No. of Cores Taken	Locations and/or Purpose Represented
133+13	3	One each crown, invert, springline. Location north of break area 1. Minimally distressed.

<u>Station No.</u>	<u>No. of Cores Taken</u>	<u>Locations and/or Purpose Represented</u>
132+50	3	One each crown, invert, springline. Location just at beginning of break area 1.
131+84 (approx)	2	Two cores from a chunk of crown concrete excavated from that location in break area 1.
131+60 (approx)	2	Two cores from a chunk of crown concrete excavated from that location in break area 1.
127+50	3	One each crown, invert, springline. Location approximately center of break area 2.
119+15	2	Two cores. One drilled through an efflorescing cold joint; the other through a nonefflorescing cold joint.
118+35) 117+70)	2	One core at each location but representing both ends of the same concrete placement.
117+25	3	One each crown, invert, and springline in a non-distressed area.
115+47	1	One core taken through the construction joint.
114+70	4	One each at crown and springline. Initial core in invert contained a large crack and was redrilled next to the crack. Location approximately at north end of break area 3.
113+45	4	One each at crown and invert. Initial springline core was badly fractured and an additional core was drilled. Location approximately at center of break area 3.

<u>Station No.</u>	<u>No. of Cores Taken</u>	<u>Location and/or Purpose Represented</u>
112+20) 112+18.5)	3	One each at crown, invert, and springline. Location approximately at south end of break area 3.

- b. All cores were drilled on the site except those from Sta 131+84 which were drilled at WES from a large piece of the crown concrete. The cores were crated and shipped to WES for evaluation.

77. Concrete thickness determinations

- a. The requirements of the job called for a 16-in. liner thickness. The Detroit Water and Sewerage Department policy used on Contract PCI-7 allowed variations in thickness in those mined areas where it was considered impractical to remine to achieve required wall thickness and maintain plan alignment. In those cases a reduction in concrete wall thickness of up to a maximum of 25 percent was allowed providing the reduced concrete sections were reinforced with circumferential steel (#6 or #7 bars @ 6-in. centers) with longitudinal tie bars (#4 or #5 bars @ 12-in. centers). The reinforcing was to be placed such that it was embedded in the concrete at the inside face at the crown and invert and on the outside face at the springline. Verification of the concrete thickness was obtained by drilling both air hammer holes and cores out of the liner at selected locations. The concrete thicknesses measured in air hammer holes are shown in Table 11. The measurements made in drilled core holes are shown in Table 20.
- b. The holes produced by the air hammer extended through the concrete and lagging into the surrounding soil. The thickness of the concrete was measured with a tape measure. No concrete was recovered from these holes. The thicknesses reported in Table 11 are only approximate as it was not always possible to drill perpendicular to the inside concrete surface. Variations from the perpendicular of 15 deg (which is probably the worst case) will only cause the measurements made to be 1/2 to 3/4 in. too long for the thicknesses of concrete involved. Attempts were made, however, to keep the air hammer as perpendicular to the inside surface as possible.
- c. The drilling of the 6-in. concrete cores only extended to the lagging. The depth of the hole was again measured with a tape measure. As considerable care was used in aligning the drilling machine, the direction of drilling

was as close to perpendicular as possible, thus producing fairly representative concrete thickness determinations.

- d. Of the 63 air hammer hole measurements and the 25 drilled core hole measurements, only four locations (six measurements) gave an indication of having less than 16-in. (approximate) thickness. These were:

Station	Method of Drilling	Location		Concrete Thickness ft
		Tunnel Side	Clock hr North	
133+13	DC	Invert	6:00	1.2
133+13	DC	E. Wall	3:00	1.2
132+50	AH	E. Wall	4:00	1.25
132+50	AH	W. Wall	8:00	1.25
117+25	DC	Crown	12:00	1.1
113+45	DC	Crown	12:00	1.15

The core recovered at Sta 117+25 in the crown did contain reinforcing steel. No steel was observed in the other three drilled cores. The Inspector's Reports indicate that reinforcing steel was placed in the invert of the placement between Stas 133+32 to 132+27 and in the crown between Sta 117+57 to 116+52. The exact location of the steel with regard to station numbers is not clear from the reports, but the reports suggest that the locations did not include the entire length of the placement. No steel was included in the placement which contained Sta 113+45. The air hammer drilling did not permit material recovery, hence it was not possible to tell if reinforcing was present in these locations.

78. Physical tests. The concrete was evaluated for compressive strength, modulus of elasticity, and Poisson's ratio, as well as being examined petrographically to determine its constituents and any problems they may be experiencing. Each drilled core was examined and marked for cutting into a 2 to 1 length-to-diameter ratio to be used in the compressive strength test. After cutting, the ends of the cores were used for the petrographic examination. Not all cores were suitable for physical testing because of the cracks or other inclusions (waterstops) they contained. Only 24 of the 32 cores were tested in compression, but all were examined petrographically and all had Schmidt hammer readings taken on them. A summary of the compressive strength, modulus of

elasticity and Poisson's ratio results are shown in Table 21.

- a. Compressive strength. Compressive strength tests for cores were done in accordance with CRD-C27 (ASTM C42), "Standard Method of Obtaining and Testing Drilled Cores and Sawed Beams of Concrete." The core strength ranged from 4440 psi to 7870 psi with an average strength of 6600 psi for 24 cores. The drilled core concrete was approximately 8 years old when tested. A more meaningful presentation of the strength data is as follows:

105-ft Placement Station Nos.	No. of Drilled Cores	Average Core Comp. Strength psi	Single, As-Cast Cylinder Strength (age) psi (days)
133+32 - 132+27	3	7150	3450 (14)
132+27 - 131+22	4	7690	3150 (7)
128+07 - 127+02	3	7400	4000 (7)
119+67 - 118+62	1	7060	3640 (7)
118+62 - 117+57	2	6310	3450 (7)
117+57 - 116+52	3	6590	3890 (13)
115+47 - 114+42	3	5330	3060 (7)
114+42 - 113+37	2	6570	2920 (7)
112+32 - 111+27	2	5875	3420 (7)

Increases in strength with time were approximately 2300 to 4500 psi which is consistent with the expected strength given behavior of concrete cured in an essentially 100 percent relative humidity environment such as the submerged sewer provided.

b. Modulus of elasticity and Poisson's ratio

- (1) The chord modulus of elasticity and Poisson's ratio under longitudinal compressive stress were determined for selected concrete cores in accordance with CRD-C19 (ASTM C469), "Standard Method of Test for Static Modulus of Elasticity and Poisson's Ratio of Concrete in Compression." The longitudinal and transverse strains on each core were determined using two sets of two each 4-in.-long electrical resistance strain gages bonded to the core. Load was applied at a constant rate using a 440 kip Universal testing machine. All cores were tested to failure. The results are shown in Table 21. These results were not meant to be indicators of concrete quality, but were needed in the structural analysis of the liner.
- (2) The average modulus of elasticity for the 15 cores that were evaluated for this property was 4.97×10^6 psi. The range was from 4.05×10^6 psi to 6.50×10^6 psi.

The average Poisson's ratio was 0.20 with a range of 0.15 to 0.29. Both the modulus and Poisson's ratio average values are reasonable for concrete of this age and strength.

- c. Petrographic examination. The ends or pieces of the following cores were sawed along their longitudinal axis:

<u>Station</u>	<u>Tunnel Side</u>	<u>Clock hr North</u>	<u>Break Area</u>
133+13	Invert	6:00	1
119+15	E. Wall	2:00	Nondistressed
117+25	E. Wall	3:00	Nondistressed
112+20	Crown	12:00	3

One sawed surface from each of these cores was ground smooth and then examined with a stereomicroscope. The stereomicroscope was also used to examine the old and/or fresh fracture surfaces on the other cores as well as the sawed surface on the end pieces of each core. Powder samples of various pieces of core were also prepared for use in X-ray diffraction analysis.

d. Concrete (general)

- (1) The examination indicated that the concrete was not air-entrained. The test report on cement for this job dated 19 October 1971 indicates that Huron Portland Cement Type IA was being considered for use. As Type IA is an air-entraining cement, the cement in question either did not perform satisfactorily in this regard or was not the Type IA represented by the test report. Only Type I was specified, however. In either case, it should have no bearing on the problem at hand. There was no evidence of any chemical attack such as caused by sulfates or acid common to sewers.
- (2) The concrete cores, with few exceptions, appeared to be well consolidated, homogeneous, and in good condition. The sawed and ground surfaces of cores from Stas 117+25 and 119+15 (nondistressed areas) shown in Figures 51 and 52, and Sta 133+13 (break area 1) shown in Figure 53 illustrate the appearance of the concrete. Visually, there is no significant difference in the appearance of the concrete in cores from either the distressed or non-distressed areas of the liner. One notable exception occurred in a piece of concrete recovered on 22 August 1980 by the Detroit District personnel during the



Figure 51. Sawed surface of core DET-4 CON-15 from sand area as shown in Figure 55; it did not show efflorescence



Figure 52. Cut and ground surface of piece of 6-in.-diam culvert wall
core DET-4 CON-10, Sta 117+25, a nondistressed area



Figure 53. Similar surface as Figure 26, culvert floor core DET-4 CON-22,
Sta 133+13, in Distressed Area 1

cleanout of the collapsed material from Distressed Area No. 1. The concrete came from the topmost quarter at Sta 131+48 and contained seams of a soil-like material. The seams began at the inside surface of the concrete forming an arc back into the concrete and then reappeared on the inside surface some distance away from their origin. The maximum depth of arc into the concrete was 5 to 10 in. Three seams of 1/4-in. thickness parallel each other approximately 1/2 in. apart. Aggregate was not visible near the seams. The concrete adjoining the seams appeared to have an excessive amount of air voids in it. A microscopic examination of the air void system showed that the voids were due to a lack of consolidation and that inadequate paste-aggregate contact resulted. The seam material was found to be sediment consisting of several nonclay minerals and minor clay minerals.

- e. Aggregate. The examination also indicated that the coarse aggregate was 3/4-in. maximum size natural gravel made up of sedimentary, igneous, and to a lesser extent metamorphic rocks. The sedimentary rocks were primarily limestone and chert. The fine aggregate rocks were of the same composition as the coarse aggregate. There was no evidence of any deleterious chemical reactions between the aggregate and other constituents such as alkali-silica reaction. Some of the carbonate rock particles contained rims (Figures 52 and 53), but these were probably due to weathering before they were incorporated into the concrete as aggregate.

f. Cement

- (1) Cement paste concentrates were prepared from the following cores:

<u>Station</u>	<u>Tunnel Side</u>	<u>Clock hr North</u>	<u>Break Area</u>
132+50	Crown	12:00	1
132+50	Invert	6:00	1
119+15	E. Wall	2:00	Nondistressed
117+25	Invert	6:00	Nondistressed
112+20	Crown	12:00	3
112+18.5	Invert	6:00	3

The paste was concentrated by gentle crushing of the concrete and then passing the fragments over a 150-mm (No. 100) sieve and then a 45-mm (No. 325) sieve. The material passing the 45-mm sieve was then packed in an appropriate slide mount and examined by X-ray diffraction,

using nickel-filtered copper radiation.

- (2) Comparison of the X-ray diffraction patterns of the paste concentrate from each core showed that all six samples contained the same crystalline paste constituents; i.e., tetracalcium aluminate carbonate-II-hydrate (monocarboaluminate), calcium hydroxide, and ettringite. These are all normal paste constituents. The calcium silicate hydrate which is the amorphous "glue" that binds the constituents together was present in all samples, but is not readily detected by X-ray diffraction.
- (3) Some contamination of the cement paste concentrate by aggregate substances was also present in the diffraction patterns. This included quartz, calcite, dolomite, and plagioclase feldspar. Amphibole, potassium feldspar, and kaolinite were also present.
- (4) Since all of the paste examined was similar and normal in composition, and represented both concrete from distressed and nondistressed locations, it can be reasonably concluded that paste composition was not a significant factor in the cause of the problem.

g. Waterstop

- (1) The Detailed Specifications, Section 2.II.9 Waterstop, allow the waterstop to be either metal (with coating), rubber or vinyl. Section 2.III.8c also requires that a waterstop, in addition to the joint coatings, shall be placed in each construction joint, where called for on the drawing, to produce water tightness. The Inspector's Reports indicate that, for the area of interest, waterstops were installed in construction joints at the following locations:

Station 111+27	Station 115+47
Station 112+32	Station 116+52
Station 113+37	Station 117+57
Station 114+42	Station 118+62

Using an electric drill and geologist hammer, the WES drill crew verified the waterstop presence by exposing it at Stas 111+27, 112+32, 113+33, and 114+42. A drilled concrete core at Sta 115+47 intersected the waterstop at that location and was included in the recovered core (Figure 54). No attempt was made to verify the waterstop at Stas 116+52, 117+57, and 118+62 as those locations were not exhibiting any apparent distress.

- (2) The waterstop recovered from Sta 115+47 was a 6-in. corrugated (center bulb) polyvinyl chloride (PVC) made by Vinylex in Knoxville, Tenn. The piece was evaluated for



Figure 54. Six-in. diameter culvert wall core DET-4 CON-24 drilled at Sta 115+45; core was drilled through a plastic waterstop at a construction joint; note wood block at end of core (outer culvert surface) and color change of concrete at construction joint; this core was in Distressed Area 3

tensile strength and elongation in accordance with ASTM D412-68 (CRD-C573-74), "Standard Method of Tension Testing of Vulcanized Rubber," and CRD-C572-74, "Corps of Engineers Specifications for Polyvinylchloride Waterstop," with the following results:

Test	Specimen No.	Requirement	Results Obtained
Tensile strength psi (CRD-C573)	1	Not less than 1750 psi	2185 psi
	2		2350 psi
	3		2295 psi
	4		2175 psi
	5		<u>2285</u> psi
	Average		2285 psi
Ultimate Elongation, % (CRD-C573)	1	Not less than 300 %	330 %
	2		320 %
	3		340 %
	4		310 %
	5		<u>330</u> %
	Average		330 %

This piece of waterstop appears to still have satisfactory material properties after 8 years in service.

- (3) The waterstop location verification procedures could not give any indication of whether or not the waterstop had been properly installed and was functioning properly. The recovered piece was also not much help in this regard. The waterstops observed did appear to be in the proper location in the concrete and had the proper amount of embedment. Both of these factors are not indicators of watertightness, however.

h. Other materials

- (1) Samples of sediment which were found in the concrete and as coatings on fractured surfaces were ground and examined by X-ray diffraction. Some samples were also heat treated.
- (2) Small samples of sediment from a void in the concrete at Sta 114+42 (Figure 45) and from the invert floor of the tunnel at Sta 120+71 were weighed and then heated at 110 deg C for one hour to remove free moisture. The samples were then weighed repeatedly until they reached a constant weight. They were then heated at 375 deg C for 16 hours and a final weight obtained. The weight differences were used to determine how much organic material was in them. Both samples were essentially free of organic matter, thus indicating they were not an accumulation of sewage.

- (3) Portions of the samples noted in the previous paragraph along with material from a sediment inclusion in a core from Sta 119+15 (Figure 55) and sediment coatings on crack surfaces contained in the core from Sta 113+45 (Figures 47-48) were examined by X-ray diffraction. They all contained chlorite and clay-mica,* plagioclase feldspar, quartz, dolomite, and calcite. There were traces of vermiculite and kaolinite. The samples from Stas 114+40 and 120+71 also contained a little potassium feldspar, amphibole, and magnetite. The sample from Sta 114+40 contained a trace of gypsum. In general, all four samples were similar in composition and can be considered as a soil. Some of this soil had been included in the concrete during construction (Figures 54-55) and some had entered through cracks in the concrete (Figures 47-48).
- (4) A sample of a stalactite from the crown of the tunnel between Stas 114+25 and 114+50 was ground and examined by X-ray diffraction. It was found to be composed of calcite plus a little clay and possibly some quartz. The occurrence and composition of the stalactite were not considered significant other than its presence demonstrated that water had passed through the concrete at that point. This passage of water had also been indicated by deposits or accumulations on the tunnel walls (efflorescence and rust stains) and by accumulations of soil in open cracks in other locations in the tunnel.

79. Diameter change measurements

- a. The physical shape of the sewer tunnel was another phase of the investigation into the collapse of the tunnel. From the visual observations of the tunnel, it was noted that the tunnel was no longer circular but was elliptical in shape, particularly in the distressed areas. Deviations in the diameters of the cross sections from the nominal 12 ft 9 in. would give an indication of the magnitude of distortion.
- b. A device to measure the inside diameters of the tunnel was designed and fabricated by Detroit District. This device consisted of a surveyor's leveling rod, a circular protractor, a measuring arm, and a pointer. The instrument was constructed around a central element, the surveyor's leveling rod which served as the stationary pivotal point. When the rod was extended from tunnel side to tunnel side and tightened, the pivot point was fixed. The protractor, graduated from 0 deg to 360 deg in 22.5-deg increments, was centered at the pivot point

* Clay-sized mica or illite clay or both.




Figure 55. Six-in. diameter culvert wall core DEE-4 (Cell-16); it was drilled over the cold joint where it showed efflorescence and a sediment inclusion; Sta 119+15 nondistressed area

and zeroed with a surveyor's plumb bob. It was at these 16 angles that diameter measurements were taken for each station. The measuring arm consisted of a metal sleeve of fixed length of 5.66 ft and a 3-ft rod calibrated and marked at 0.01-ft increments. A pointer was attached to locate each angle. The entire instrument when in position rested on the shelf of a 6-ft stepladder.

- c. Diameter measurements were taken at several critical stations along the entire tunnel, both in distressed and nondistressed areas. This was accomplished by positioning the ladder so that the edge of the shelf was at a particular station. The instrument was placed on the shelf and extended until both ends of the leveling rod were flush against the tunnel wall, then tightened. The protractor was positioned with the 180-deg angle toward the invert, the 270-deg angle to the west, the 0-deg angle toward the crown, and the 90-deg angle to the east. Any deviations from this position was noted and later corrected to the standard position. A plumb bob was used to zero the protractor with respect to the vertical.
- d. The 5.66-ft sleeve of the measuring arm slid up and down along the calibrated 3-ft rod giving a maximum reading of 8.66 ft with a minimum reading of 5.66 ft. Readings were made by sliding the sleeve out until it was flush with the tunnel wall and recording the length of extension of the sleeve. The length of the extension plus the 5.66-ft sleeve equaled the distance from the fixed point to the tunnel wall. With the 16 measurements, the shape of the cross section of the tunnel was established at each station.
- e. Two stations in Distressed Area No. 1, where severe cracking had occurred and where repairs had proceeded with placement of the ribbing and wooden lags, were measured using a shorter sleeve, 3.84 ft long, for accessibility over the ribs and lags that were being installed. With the shorter sleeve, several readings were made using the 3-ft rod and a cloth measuring tape to compensate for the shorter length.
- f. The shape of the tunnel was graphically expressed by plotting the fixed point and each of the 16 measurements at their respective angles. Constructing lines connecting two points with the center point conveys the actual diameter of the tunnel. Any difference from the nominal 12-ft-9-in. diameter indicates the magnitude of the distortion. The results are shown in Appendix F.
- g. The analysis of the diameter change measurement will be discussed further under the section Structural Analysis.

Summary of concrete investigations

80. The results of the concrete investigations are summarized as follows:

- a. The coarse aggregate was a 3/4-in. maximum size gravel composed of sedimentary, igneous, and metamorphic rocks. The fine aggregate was composed of the same material. There was no indications that the aggregate was a contributing factor to the problem.
- b. The cement paste was normal in composition and similar in all areas examined. The cement paste should not have been a significant factor in the cause of the problem.
- c. The concrete was generally homogeneous and its quality was similar whether it came from distressed or non-distressed locations. Exceptions were the presence of continuous cold joints along both sides of the sewer. In these locations honeycombing, mud contamination, and seepage occurred. The concrete did not appear to be air entrained.
- d. There was no evidence of any chemical attack on the concrete although rebound measurements on the sewer floor suggest a slight degradation of the surface skin of the concrete due to prolonged contact with the flowing sewage.
- e. Cracks were present in the concrete, especially in the distressed areas. The presence of sediment coatings on some of the cracks indicates that the cracks were pre-existing before the concrete cores were taken. It is impossible to tell, however, the age of the cracks. Efflorescence around the cracks and in the form of stalactites was composed of calcium carbonate and indicated that water and, in some cases, soil had been leaking through the cracks.
- f. Most of the joints in the concrete appeared to be intact although leaking. Those leaking joints generally did not contain waterstops. The sediment associated with the leakage appears to be soil from outside the sewer. Some joints did contain waterstops. A recovered piece of waterstop indicated that the desired physical characteristics of the waterstop were still functional.

Mechanics of the structural failure

81. In this portion of the report, the mechanics of the structural failure of the sewer tunnel are discussed. This discussion begins with a description of the bypassed section of the interceptor

following its failure. Then, the loading assumed in the design of this structure is reviewed. Next, the resistance against this and other loadings implicitly required by the contract specifications are considered. Subsequently, based on the previously described results of the investigation of concrete material properties within the failed tunnel, the structural resistance available in the sewer tunnel is analyzed. Finally, using the previously discussed results of the geotechnical investigation of soil properties surrounding the sewer, the loadings imposed on this structure are investigated.

Description of structural failure

82. Figures 56 through 59 are photographs of a nondistressed and the three distressed areas of the tunnel which were taken in May 1980. In contrast to the nondistressed areas, the distressed areas are characterized by cracks and spalls running generally along the longitudinal direction of the tunnel for large distances compared with the diameter of the tunnel. Although some deviations from this pattern occur at circumferential construction joints and at the transition between distressed and nondistressed regions, these photographs suggest that the essential features of this structural failure should be explained by considering a representative transverse plane cross section of the tunnel perpendicular to its longitudinal axis. The photographs also show the cracking to occur mainly near the crown or the invert of the tunnel and the spalling to occur generally near the springline.

83. The deformation of the sewer tunnel along its length following its failure is depicted in Figure 60. The figure shows the difference between the structure's nominal 12-ft-9-in. inner diameter and the crown-invert diameter as a fraction of the nominal diameter. The points indicated by asterisks in this figure are based on a survey of crown and invert elevations performed for the Detroit Water and Sewage Department by the firm of Hubbell, Roth, and Clark in May 1980. It is notable that the crown-invert diameter was compressed to a value as much as 8 percent less than the nominal diameter in the distressed areas of the bypassed section. The consistent 2 percent compression of the crown-invert diameter in the nondistressed areas is probably



Figure 1. Top of runway tunnel 11-7, (Feb. 1960). In the background, a small, light-colored rectangular mark is visible.



Figure 56. Detroit Sunitary Tunnel PCI-7, Sta: 114+50 Photo: 50 (19 May 80) South; 10m;
Grout & wall faces C & W wall; (M 114+50)



Figure 58. Detroit Military Tunnel 17-1, Station 107+50. Photo taken (W May 80) North, displaced 10m
2 m and 10m at 10 m distance from 10 m distance.



Figure 59. Detroit secondary tunnel P.I.-1, Sta: 131+50. Photo: 136 (1/10/50) north; close up of south end break area #1; settlement pin in cavity; rubbing & rubbing; the photo.




Figure 60. Owalling profile

attributable to inner form out of roundness and deformation during construction of the tunnel.

84. This description of the structure's deformation was supplemented by measurements of its ovalled shape in the planes perpendicular to its longitudinal axis at 29 selected locations along its length. These measurements were made in May 1980 by the U. S. Army Engineer District, Detroit. The measurements were obtained by fixing the pivot point of a custom fabricated profile meter at the approximate center of the tunnel as shown in Figure 61. Then the distance from this fixed pivot point to the inner surface of the tunnel along 16 equally spaced rays was recorded.

85. The 29 figures in Appendix F show the results of these measurements. In each figure the solid curve represents the nominal 12-ft-9-in. inner surface of the tunnel. The asterisks depict the actual shape of the cross section measured with the custom fabricated profile meter. The dotted curve is a theoretical periodic deflected shape selected to have the minimum sum of the squared distances from these measurements. The value given for w/r is equal to the maximum diametrical change of this theoretical deflected shape as a fraction of the nominal diameter. It is observed that the springline diameter was stretched to a value greater than the nominal diameter along the entire bypassed section. The crown-invert diameter changes obtained from the ovaling measurements are superimposed on the results of the crown-invert elevation survey in Figure 60. It is seen that the two independently acquired data bases are reasonably consistent with one another.

Design loading

86. In response to a request for design calculations of the failure sewer, the data sheet shown in Figure 62 was the information furnished by the Detroit Water and Sewage Department pertaining to the concrete tunnel walls. In these computations, the loading on the sewer was assumed to be entirely resisted by the concrete wall of the tunnel. This loading was a uniform pressure equal in magnitude to the weight per unit area of the soil between the springline and the





Figure 1. A person in a small boat on a body of water, with a large, dark, curved structure in the background.

DETROIT
WATER
SERVICE
DESIGN
SECTION 10-1
10-1

SUBJECT OAKLAND-MACOMB INTERCEPTOR SYSTEM
COMPRESSIVE STRESS ON CONCRETE
TUNNEL WALLS (SECONDARY LINING)

BY 1-11
CHECKED BY 1-11
SHEET NO. 1 OF 1 DATE 1-11

CONTRACT No.	SIZE I.D.	WALL t	COVER d *	* SURFACE TO SPRINGLINE
PCI-4	17'-6"	20"	40'	$f_c = wd \left(\frac{I.D. + 2t}{2} \right) \div 12t$
PCI-5, 6 & 7	12'-9"	16"	100'	$f_c = \text{conc. compr. stress}$
PCI-8	9'-6"	12"	60'	$w = \text{unit wt. of soil}$
PCI-9	8'-9"	12"	36'	$= 120 \text{ p.c.f.}$
PCI-12	11'-0"	14"	58'	$d = \text{depth of cover (ft.)}$
	10'-6"	14"	61'	$I.D. = \text{inside dia. of sewer}$
				$t = \text{wall thickness (in.)}$



Note:
Assumed full earth
load without con-
sidering arching
action nor shearing
resistance of soil.

PCI-4

$$f_c = 120 \times 40 \left(\frac{17.5 + 2 \times 1.67}{2} \right) \div 12 \times 20$$

$$= 208 \text{ psi}$$

PCI-5, 6 & 7

$$f_c = 120 \times 100 \left(\frac{12.75 + 2 \times 1.33}{2} \right) \div 12 \times 16$$

$$= 482 \text{ psi}$$

PCI-8

$$f_c = 120 \times 60 \left(\frac{9.5 + 2 \times 1.0}{2} \right) \div 12 \times 12$$

$$= 287 \text{ psi}$$

PCI-9

$$f_c = 120 \times 36 \left(\frac{8.75 + 2 \times 1.0}{2} \right) \div 12 \times 12$$

$$= 161 \text{ psi}$$

PCI-12

$$f_c = 120 \times 58 \left(\frac{11.0 + 2 \times 1.17}{2} \right) \div 12 \times 14$$

$$= 275 \text{ psi (11'-0")}$$

$$f_c = 120 \times 61 \left(\frac{10.5 + 2 \times 1.17}{2} \right) \div 12 \times 14$$

$$= 280 \text{ psi (10'-6")}$$

Figure 62. Original design calculations

ground surface. An average compressive stress of 482 psi in the trial 16-in.-thick concrete wall consistent with this uniformly distributed pressure was then computed. Under the presumed loading q , the axial thrust N resulting from this compressive stress would uniformly compress the tunnel's circular cross section as shown in Figure 63. This assumed behavior differs from the pattern of crown-invert cracking and springline spalling observed in the distressed areas of the tunnel.

Resistance specified

87. The contract specifications prescribed a tunnel wall thickness of 16 in., a minimum cement content, a maximum water content ratio, and an approximate ratio of fine to coarse aggregate for the concrete mixture to be used in the tunnel walls, but did not explicitly require the mixture to meet any strength standard. We have, however, been told by the Detroit Water and Sewer District that the compressive strength of the concrete from similar projects using this particular mixture is 3500 psi. This strength provides a comfortable margin of safety against the uniform loading assumed in the design.

88. As the distressed areas of the tunnel may have experienced a loading condition different from the uniform condition assumed in its design, it is appropriate to consider the inherent resistance of the tunnel walls against nonuniform loadings q , as shown in Figure 64. In order to satisfy the conditions of static equilibrium for such loadings, the thrust N must now vary with position in the tunnel wall. Further, transverse resultant shear forces V and resultant bending moments M must be developed which vary with position in the tunnel wall. Bending moments acting in the direction of those in Figure 64 would tend to flex the tunnel wall inward as indicated and cause cracking on the inner surface of the structure as observed near the crown and invert of the distressed areas. On the other hand, bending moments acting opposite to the direction of those in Figure 64 would tend to flex the tunnel wall outward and cause crushing and eventually spalling on the inner surface of the structure as observed near the springline of the distressed areas.




Figure 63. Behavior of circular tunnel wall under uniform external pressure




Figure 64. Behavior of circular tunnel wall under nonuniform external pressure

89. When loaded in such a nonuniform fashion, the resistance of a plain concrete tunnel wall depends upon its tensile strength as well as its compressive strength and thickness. The specific combinations of moment M and thrust N which can be resisted without concrete cracking or crushing can be computed from the values of tensile strength, compressive strength, and wall thickness using the techniques discussed by Pfrang, et al (1964). These techniques involve first assuming a set of linear strain distributions across the wall corresponding to a cracking or a crushing failure; then, for each strain distribution, the distribution of stress is computed from the stress-strain relation for concrete which is approximated by a parabola in compression and a straight line in tension. Finally, the axial thrust N and bending moment M which are statically equivalent to this stress distribution are calculated. A TEKTRONIX 4050 series BASIC mini-computer subroutine program to perform these computations is listed in Appendix G. For the concrete mixture specified, it was estimated that the tensile strength would be about 8 percent of the compressive strength or 280 psi (Grieb and Werner, 1962). From these strength and thickness values, the resistance of the structure specified by the contract was then computed to be the dotted line of Figure 65. Combinations of bending moment M and axial thrust N caused by the loading which fall between this line and the coordinate axes can be resisted by the tunnel wall, while combinations of moment and thrust in excess of this resistance line cause the failure of the tunnel wall. This resistance line indicates that the specified structure offers some resistance against nonuniform loading although this was not explicitly considered in the design calculations furnished us. In the absence of any axial thrust, this resistance is small due to the low strength of concrete in tension. However as the axial thrust increases up to the point of inducing crushing of the concrete in compression, the resistance to bending moments induced by nonuniform loading increases.

Resistance constructed

90. As discussed in the previous section, the resistance against




Figure 65. Structural reliability of concrete lining under external pressure

external loading offered by a plain concrete section is determined by the concrete strength and the section thickness. Figure 66 is a histogram which shows the distribution of concrete compressive strength in the tunnel. This figure was drawn from the results of the laboratory tests which were discussed in the concrete material properties portion of this report. Figure 67 is a histogram of section wall thickness which was obtained from the core measurements made during the geotechnical explorations through the tunnel wall as well as these concrete material investigations. It is clear that the resistance offered by the structure as constructed varies throughout the tunnel in accordance with the distributions of these histograms and the dependence of resistance on strength and thickness.

91. In order to estimate this distribution of resistance in the tunnel as built, a probabilistic technique called Monte Carlo simulation (Benjamin and Cornell, 1970) was employed as follows. First, the concrete compressive strength was modeled by a computer-generated value of a random variable whose theoretical distribution roughly approximated that of Figure 66 and was independent of location in the tunnel. Specifically the mean and standard deviation of the theoretical distribution, which are measures of its central value and dispersion, respectively, were set equal to those of the sample shown in Figure 66. Similarly, a computer-generated value for section thickness was obtained from a theoretical distribution having the same mean and standard deviation as the sample in Figure 67. Next, a tensile strength was generated from a theoretical distribution whose mean was 8 percent of the compressive strength which has been previously explained to be the estimated central value for this mix design. The standard deviation of this distribution was assumed to be 13 percent of this mean value as this is the ratio of standard deviation to mean for the sample of concrete compressive strength in Figure 66. From these simulated values of strength and thickness, a bending moment and axial thrust resistance curve was then drawn just as the dotted line was drawn for the contract specified values of these variables in Figure 65. This simulation procedure was replicated by a computer




Figure 66. Histogram - compressive strength of drilled concrete cores (psi)




Figure 67. Histogram - thickness of concrete liner (ft)

100 times resulting in 100 such resistance curves. Finally, the mean and standard deviation of these 100 curves were computed. The two solid curves in Figure 65 represent the mean plus one standard deviation and the mean minus one standard deviation resistances obtained by this procedure.

92. The hashed region between these solid curves is expected to contain the resistance constructed in the majority of the sewer. However, the structure's resistance is probably greater or less than these curves at some locations. One finds from this figure that the as-built resistance generally exceeded the resistance specified by the contract.


Loadings imposed

93. As discussed by Peck (1969), the loads imposed on any tunnel are the result of a complex interaction mechanism which takes place between the lining structure and the medium surrounding it. At one hypothetical extreme, if the lining is perfectly flexible compared to the medium, the lining will distort until a uniform pressure exists between the lining and the medium. This lining will satisfactorily support the surrounding soil if the associated axial thrust does not induce crushing or buckling. At the other theoretical extreme, if the lining is absolutely rigid relative to the soil, the nonuniform pressure distribution which would exist in the undisturbed medium is imposed on the lining. To perform acceptably, this lining must be capable of resisting the internal bending moments induced by this non-uniform loading. In the present case, the primary rib and lagging lining preserved the integrity of the excavation during the construction of the secondary concrete lining. Any post-construction change in loading, such as that caused by the removal of dewatering wells or by the piping of surrounding material, must be shared by the two linings in accordance with the rigidities. Studies such as that by Meyer and Flathau (1967) have shown that when a partial failure of the buried structural system occurs, these interaction mechanisms can sometimes change drastically.

94. With these complications in mind, stress analyses were

conducted of the combined structure-soil system to bracket the loadings imposed on the concrete lining by the various geotechnical conditions discussed in an earlier portion of this report. Since the concrete lining was constructed in intimate contact with the primary rib and lagging lining and since the concrete lining has approximately 100 times the flexural rigidity of the primary ribs, it was assumed that all of the external loading following construction was carried by the concrete lining. Accordingly, these analyses are useful in discussing the initiation of failure in the concrete lining and do not necessarily reflect in detail the complex interaction among concrete lining, primary lining, and surrounding medium to the point of severe structural collapse which now exists in some areas in the sewer.

95. The interaction between the concrete lining and the surrounding soil was modeled by loading the soil at a distance of one tunnel diameter from the structure with the loading which would exist at this location if there were no structure present as shown in Figure 68. In these stress analyses both the soil and structure were assumed to behave with linear elastic material properties consistent with previously discussed test data and with compatible displacements at the soil structure interface. The effects of the stratification and the piping discussed in the geotechnical portion of this report were modeled through a nonhomogeneous distribution of soil material properties. To simplify the analyses, the loading conditions considered were assumed to be symmetric about the tunnel's vertical axis as shown. Along the horizontal boundary located one tunnel diameter above the crown, a uniform vertical pressure was applied corresponding to the weight of the overburden material as previously computed in Figure 40. On the vertical boundary one tunnel diameter from the springline, a horizontal pressure was applied corresponding to K_p as indicated in Figure 41. The horizontal boundary one diameter below the invert was assumed to rest on a linear elastic foundation whose modulus $k = 300 \text{ psi/in.}$ was selected to be representative of the soil material encountered below this depth. In addition to these boundary loadings, the weight distribution of the lining and soil material within these



SOIL PROPERTIES			
MATERIAL	E_s , PSI	ν	γ , PCF
1. SILT & CLAY	3000	0.44	138
2. SILT & CLAY	3000	0.44	140
3. SAND	6000	0.44	125


Figure 68. Postconstruction loading conditions;
no piping, $K = 0.8$

boundaries was also included in the analyses.

96. These stress analyses were conducted using a numerical technique called the finite element method (Desai and Abel, 1972). In this method, constant material properties and a particular form of the distribution of stress is assumed within each quadrilateral element of the grid in Figure 68, but the magnitude of these stresses is determined by the requirement for static equilibrium with the externally applied loads. The analyses were performed on the WES digital computer using the computer code SAPV (Bathe, et al., 1973). The soil materials were modeled by isoparametric, plane strain, quadrilateral elements with incompatible bending modes of deformation suppressed. The concrete lining was modeled by beam elements which considered flexural, shear, and axial flexibilities, and which were located at the linings nominal central 84.5-in. radius. In all the analyses, the stiffness properties of these beam elements were computed for a nominal thickness of 16 in., a modulus of elasticity of $E = 6 \times 10^6$ psi and a Poisson's ratio of $\nu = 0.20$.

97. The first two analyses were conducted to bracket the loading imposed on the structure if no surrounding material piped into the sewer. The soil stratification and loading in these analyses are shown in Figures 68 and 69. The stratigraphy shown is a simple idealization of the complex condition which has been discussed earlier in this report. The loadings assumed in these two cases bracket those associated with the range of lateral earth pressure coefficient $0.7 < K < 0.8$ previously determined for the surrounding material.

98. The results of these analyses are summarized in Figures 70 through 73 as a function of location from the invert at $\theta = 0$ to the springline at $\theta = \pi/2$ to the crown at $\theta = \pi$. The pressure q exerted on the liner by the surrounding soil is seen to be nonuniform due to the variation of load with depth and the stratification of the soil. The shearing stress τ exerted at and parallel to the structure soil interface is small relative to these normal pressures and could probably be transmitted without slip along this surface as assumed in the analyses. The bending moments M induced in the tunnel wall by



SOIL PROPERTIES			
MATERIAL	$E, \text{ PSI}$	ν	$\gamma, \text{ PCF}$
1. SILT & CLAY	3000	0.41	138
2. SILT & CLAY	3000	0.41	140
3. SAND	6000	0.41	125

Figure 69. Postconstruction loading conditions;
no piping, $K = 0.7$




Figure 70. Pressure distribution on tunnel liner; no piping




Figure 71. Interface shear distribution; no piping




Figure 72. Internal bending moment distribution; no piping





Figure 73. Axial thrust distribution; no piping

these loadings are noted to stretch the inner surface of the liner near the invert and crown and to compress this surface near the springline. The corresponding axial thrusts N are observed to vary as a function of position in the lining to maintain equilibrium with the nonuniform loading.


99. In both of these loadings the most severe combinations of moment and thrust occur at the invert, crown, and springline. The severity of this combination increases as the lateral pressure coefficient K decreases. The range of these ideal invert loading combinations has been superimposed on the previously drawn resistance curves of Figure 65. It is not believed that this range of loadings would exceed the capacity of the constructed tunnel system. Figure 70 does admit that if the concrete lining in the weaker areas of the sewer tunnel was surrounded by piped material with a low value for the lateral earth pressure coefficient, some minor cracking could have initiated in these areas. Some of the loading would then be transferred from the concrete lining to the rib and lagging lining. A comparison of Figures 40 and 41 indicates that this primary lining was subjected to a more nonuniform loading condition during the tunnel's construction. Accordingly, the primary lining and surrounding competent soil material could be expected to intersect and successfully carry this post-construction loading.

100. Two other analyses were then conducted to bracket the loading imposed on the structure if some of the surrounding material piped into the sewer. The stratigraphy and loading assumed in these analyses are shown in Figures 74 and 75. The soil stratification shown represent two simple idealizations which bracket the complex layering of pipable material which have been previously shown to exist around some areas in the tunnel. The boundary loadings assumed in these two cases are consistent with the estimated central value $K = 0.75$ for lateral earth pressure coefficient. In Figure 74 the effect of piping-susceptible material near the invert is modeled by a reduction in this material's stiffness and by a void adjacent to the concrete lining. In Figure 75 the layer of pipable material is moved to the springline



SOIL PROPERTIES			
MATERIAL	E, PSI	ν	γ , PCF
1. SILT & CLAY	3000	0.43	138
2. SILT & CLAY	3000	0.43	140
3. SAND	3000	0.43	125
4. VOID	1	0.43	1

Figure 74. Postconstruction loading conditions;
invert piping



SOIL PROPERTIES			
MATERIAL	E_s PSI	ν	γ_s PCF
1. SILT & CLAY	3000	0.43	138
2. SILT & CLAY	3000	0.43	140
3. SAND	3000	0.43	125
4. VOID	1	0.43	1

Figure 75. Postconstruction loading conditions; springline piping

and the effect of its piping is similarly simulated at that location. In both cases, the pressure exerted on the lining by the water in these voids is taken to be the product of the density of water and the depth below the water table as indicated.

101. The results of these analyses are summarized in Figures 76 through 79. In both cases the interface pressure q and the shearing stress τ across the structure medium interface are seen to be markedly nonuniform near the voids assumed to be caused by piping. The effect of this loading on bending moment M and axial thrust N is not particularly harmful for the case of a void under the invert. In this case the regions in which the tunnel's inner surface is stretched or compressed change from the unpiped cases, but the severity of the critical moment and thrust combination does not change appreciably from these unpiped cases. On the other hand, if a void occurs near the springline, the severity of the critical moment and thrust combination increases dramatically from the unpiped case. In this case the inner surface of the tunnel near the springline is compressed while the corresponding surfaces near the invert and crown are stretched. This pattern of deformation is similar to the distressed condition existing in the tunnel which has been previously discussed in paragraph 82.

102. These critical moment and thrust loading combinations are connected by a dotted line on the previous plot of resistance curves in Figure 65. This range of loadings suggests that piping of material near the invert would probably not directly cause the collapse of the constructed tunnel system. Such piping could possibly initiate the structural failure of the concrete lining in the weakest areas of the sewer. However if such a failure did begin, it is again believed that the subsequent interaction among the concrete lining, primary lining, and the competent soil material remaining adjacent to the springline could have prevented the severe structural failure of the tunnel which did occur in some areas.

103. In contrast, Figure 65 suggests that the piping of material near the springline would be expected to initiate the structural failure of the concrete lining in even the strongest areas of the




Figure 76. Pressure distribution on tunnel liner; piping




Figure 77. Interface shear distribution; piping




Figure 78. Internal bending moment distribution; piping




Figure 79. Axial thrust distribution; piping

sewer. If such a failure did initiate, some of the loading would attempt to transfer from the concrete lining to the primary rig and lagging lining. However, lacking any competent soil material adjacent to the springline with which to interact, this flexible primary lining would have little capacity to sustain this loading. Eventually, as severe a collapse of the tunnel as did occur in the distressed areas could be expected.

104. One additional stress analysis was conducted to assess the effect of a continuous void extending longitudinally along the invert due to extensive piping of material. In this analysis the concrete lining was modeled to be an infinitely long flexural beam of rigidity EI as shown in Figure 80. The beam is loaded by a uniform pressure p corresponding to the weight of the overburden material above it and it is supported by an elastic foundation whose modulus k represents the stiffness of the soil material on which it rests. A void of length L exists under the beam to model a complete loss of support due to piping of surrounding material. Using the methods described by Timoshenko (1930), one can derive the expression given in Figure 80 for the bending moment M imposed in the beam at the center of the void. This moment would tend to crack the lining circumferentially rather than longitudinally as would the previously discussed moments induced by nonuniform external pressure.

105. Figure 81 shows the magnitude of this bending moment M as a function of the void length L . It was drawn for the springline overburden pressure $p = 7800$ psf previously computed in Figure 41, for a lining modulus of elasticity $E = 6 \times 10^6$ psi and for a moment of inertia $I = 3.06 \times 10^7$ in.⁴ corresponding to a hollow circular cylinder with inner and outer diameters equal to the nominal values of 153 in. and 185 in. The effect of foundation modulus variation between $k \approx 200$ psi/in. and $k = 500$ psi/in., which bracket the stiffness of the material under the tunnel, is also illustrated in this figure.

106. This loading should be compared to the resistance of the concrete lining in longitudinal bending without axial thrust. This




Figure 80. Longitudinal bending of concrete lining by loss of foundation support




Figure 81. Reliability of concrete lining in longitudinal bending

resistance is approximated by the product of the concrete tensile strength and the elastic section modulus of the tunnel in longitudinal bending. Accordingly, for the contract-specified 16-in. wall thickness and concrete mixture discussed in paragraph 89, the resistance to longitudinal bending is approximately 93×10^6 in. lb as shown in Figure 81. The distribution of resistance in the lining as built depends on the distribution of wall thickness and tensile strength constructed. Using the Monte Carlo technique and the assumptions previously described in paragraph 91, it was estimated that the resistance of the majority of the concrete lining is contained within the hashed region of Figure 81. It is seen that the constructed lining has a resistance to longitudinal bending which generally exceeds that implicitly specified by the contract. It is further observed that the loss of foundation support due to invert piping for a longitudinal distance on the order of 200 in. could cause the tunnel to fail in longitudinal bending. This event would be accompanied by a circumferential cracking similar to that described in paragraph 73 near Distressed Area No. 3.

AD-A096 440

ARMY ENGINEER WATERWAYS EXPERIMENT STATION VICKSBURG--ETC F/G 13/2
15 MILE ROAD/EDISON CORRIDOR SEWER TUNNEL FAILURE STUDY, DETROIT--ETCII
JAN 81 D ALBERT, G C HOFF, B LORENCE


NCE-IA-80-055

UNCLASSIFIED

WES/TR/GL-81-2

NL

3 OF 5
4 - 120



PART IV: SUMMARY

Findings

107. Specific findings are presented sequentially as follows:

- a. A note on the contract drawings states "Waterstops not required on this Contract." This refers to waterstops at construction joints.
- b. During construction, Change Orders Nos. 2 and 4 were issued which provided for the installation of waterstops at construction joints not yet constructed. The construction records show that no waterstops were installed north of Sta 118+62.
- c. The concrete placement lengths for the concrete liner were generally 105 ft. These substantial placement lengths directly increased the potential for cold joints in the concrete liner. This potential was frequently realized due to the late arrival of concrete trucks and plugged concrete drop pipes, resulting in pour delays.
- d. The construction records show that numerous areas of the concrete liner required patching and repair of cold joints, honeycombing, and stone or rock pockets immediately following the removal of forms.
- e. Stratification of the glacial lake deposits along the tunnel showed uniformly fine to medium graded beach sand unit along the base of the tunnel. In Distressed Areas Nos. 1 and 2, silt and sand strata also existed along the sides of the tunnel. Between Distressed Areas Nos. 2 and 3, silty to sandy clay existed along the sides of the tunnel above the sand along the base. In Distressed Area No. 3, thin strata of sand occurred in the silty clay along the sides of the tunnel and silt strata existed near the crown in the northern half of this section. On the basis of blow count comparisons, loose soil conditions were found in borings along all three distressed areas.
- f. Special laboratory piping tests showed that fine to medium sands, silty sands, and silts from the site were susceptible to piping through small crack openings under water pressures of less than 2 psi, but the uniformly graded fine to medium sands were highly susceptible to piping under water pressures of less than 1 psi. Standard pinhole tests on silty clay indicated that this material was not susceptible to piping.

- g. Groundwater conditions at the site in 1980 away from the area of dewatering, showed that the beach sand unit at the base of the tunnel had artesian water pressures that produced an equivalent groundwater level near the crown in Distressed Area No. 2 and up to 6 ft above the crown north and south of this area. These levels were more than sufficient for piping to occur.
- h. Rainfall and river discharge data indicated 1976 to be the wettest year since construction, suggesting higher groundwater levels during 1976 than those found in 1980.
- i. Staining in construction joints and from cold joints indicated leakage through these joints. Evidence of sand infiltration through construction joints and cold joints was found during field work.
- j. Significant seismic activity did not occur from 1972 to 1980.
- k. The concrete composition, homogeneity, and quality were satisfactory. No significant differences were found in the concrete between distressed and intact areas.
- l. Seepage, honeycombing, and contamination occurred in continuous cold joints in the side walls of both the distressed and intact areas.
- m. The distressed areas are characterized by longitudinal cracking near the crown and invert, longitudinal spalling near the springlines, a contraction of crown-invert diameter, and an expansion of springline diameter.
- n. The loading condition assumed in the original design of the concrete tunnel wall was a uniformly distributed external pressure equal to the estimated weight per unit area of the soil between the ground surface and the springline.
- o. The specifications in the contract provided for a resistance which exceeded the assumed uniform design loading.
- p. The as-built structure had a resistance against external loading which exceeds that specified in the contract.

Conclusions

108. Conclusions are presented sequentially as follows:

- a. Seismic activity was not a factor.

- b. Concrete composition, homogeneity, and quality were not factors and there was no evidence of detrimental chemical reactions.
- c. At end of construction, the concrete liner contained open construction joints and/or cold joints at several locations.
- d. The fine to medium sands, silty sands, and silts will pipe through openings as narrow as 0.01 in. under water pressures less than 2 psi.
- e. After construction, the external water pressure on the tunnel invert ranged from 4 to 8 psi.
- f. Soil piped into the tunnel in varying amounts depending on the location of the strata of piping soil with respect to open construction joints and/or cold joints. As material piped into the tunnel, the tunnel lost bottom and side support.
- g. When loss of support occurred beneath the invert, the resulting loading caused the structure to crack circumferentially as was observed in Distressed Area No. 3.
- h. When loss of support occurred at the springline, the resulting nonuniform loading caused the resistance of the structure to be exceeded and initiated the pattern of ovaling and longitudinal cracking and spalling observed in all distressed areas.

109. In summary, the distress actually began immediately following construction as soon as the groundwater level was sufficiently high to initiate piping of soil through open construction and cold joints. This piping took place over a significant period of time. As greater loss of support occurred, the concrete liner deformed, the cracks opened wider, and more soil was allowed to pipe into the tunnel. These events progressed until the distress was manifested by the crack pattern found, and by total collapse at Distressed Area No. 1 and partial collapse at Distressed Area No. 3. Varying degrees of distress were experienced depending upon the location of the strata of piping soil with respect to open construction and/or cold joints.

REFERENCES

- Bathe, K. J., Wilson, E. L., and Peterson, F. E. 1973. "SAP IV Structural Analysis for Static and Dynamic Response of Linear Systems."
- Benjamin, Jack R., and Cornell, C. Allin. 1970. Probability, Statistics, and Decision for Civil Engineers, McGraw-Hill Book Co., New York.
- Brooker, E. W., and Ireland, H. O. 1965. "Earth Pressures at Rest Related to Stress History," Canadian Geotechnical Journal, Vol II, No. 1, Feb., National Research Council of Canada, University of Toronto Press, Ontario.
- Consumers Power Company. 1980. "Midland Plant, Units 1 and 2, Final Safety Analysis Report," Vols 3 and 4 with Revision 27 3/80, Ann Arbor, Michigan.
- Department of the Army Corps of Engineers. 1980. Engineer Manual, EM 1110-2-1906, "Laboratory Soils Testing," with Change 1, OCE Publications Depot, Alexandria, Virginia.
- Department of the Army Corps of Engineers. 1980. TM 5-818-1/AFM 8-3, Chapter 7, "Soils and Geology: Procedures for Foundation Design of Buildings and Other Structures (Except Hydraulic Structures)," USA AG Publication Center, St. Louis, Missouri.
- Desai, Chandrakant W., and Abel, John F. 1972. Introduction to the Finite Element Method, Van Nostrand Reinhold Co., New York.
- Dreimanis, A. 1970. "Effect of Groundwater Levels on Stress History of the St. Clair Clay Till Deposit: Discussion," Canadian Geotechnical Journal, Vol 7, No. 2, May, National Research Council of Canada, University of Toronto Press, Ontario.
- Dunlop, Peter, Duncan, J. M., and Seed, H. B. 1968. "Finite Element Analyses of Slopes in Soils," Contract Report S-68-6, U. S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.
- Flint, R. F. 1971. Glacial and Quaternary Geology, John Wiley, N. Y.
- Grieb, W. E., and Werner, G. 1962. "Comparison of Splitting Tensile Strength of Concrete with Flexural and Compressive Strengths," Proceedings, American Society for Testing and Materials, Vol 62, Philadelphia, Pennsylvania.
- Hough, Jack L. 1958. "Geology of the Great Lakes," University of Illinois Press, Urbana.

Housel, W. S. 1970. "Suggested Method of Test for Ultimate Shearing Resistance of Cohesive Clay Soils," Special Procedures for Testing Soil and Rock for Engineering Purposes, 5th Edition, ASTM Special Technical Publication 479, American Society for Testing and Materials, Philadelphia, Pennsylvania.

Huffman, G. C. 1979. "Ground-Water Data for Michigan, 1978," Open-File Report 80-002, U. S. Geological Survey, Lansing, Michigan.

Meyer, G. D., and Flathau, W. J. 1967. "Static and Dynamic Laboratory Tests of Unreinforced Concrete Fixed-End Arches Buried in Dry Sand," Technical Report No. 1-758, U. S. Army Engineer Waterways Experiment Station, CE, Vicksburg, Mississippi.

Mozola, Andrew, J. 1973. "Geologic Considerations for Southeastern Michigan Wastewater Treatment," Special Report to Detroit District, Contract No. DACW35-72-C-0008, U. S. Army Engineer District, Detroit, Michigan.

Mozola, Andrew J. 1969. "Geology for Land and Ground-Water Development in Wayne County, Michigan," Report of Investigation 3, State of Michigan, Department of Natural Resources, March, Lansing, Michigan.

Peck, R. B. 1969. "Deep Excavations and Tunneling in Soft Ground," Proceedings, 7th International Conference on Soil Mechanics, Mexico, State-of-the-Art Volume.

Pfrang, E. O., Siess, C. P., and Sozen, M. A. 1964. "Load-Moment-Curvature Characteristics of Reinforced Concrete Cross Sections," Proceedings, American Concrete Institute, Vol 61, No. 7.

Radhakrishna, H. S., and Klym, T. W. 1974. "Geotechnical Properties of a very Dense Till," Canadian Geotechnical Journal, Vol 11, No. 3, August, National Research Council of Canada, University of Toronto Press, Ontario.

Soderman, L. G., and Kim, Y. D. 1970. "Effect of Groundwater Levels on Stress History of the St. Clair Clay Fill Deposit," Canadian Geotechnical Journal, Vol 7, No. 2, May, National Research Council of Canada, University of Toronto Press, Ontario.

Timoshenko, S. 1930. Strength of Materials, Part II, Van Nostrand Company, Inc., New York.

Twenter, F. R. 1975. Ground Water and Geology, Southeastern Michigan Water Resources Study, Department of the Interior U. S. Geological Survey in cooperation with U. S. Army Engineer District, Detroit, Michigan.

Wisler, C. O., Stramel, G. J., and Laird, L. B. 1952. Water Resources of the Detroit Area, Michigan, Geological Survey Circular 183, Department of the Interior, Washington, DC.

Table 1

Excavation Summary

Date	Start Sta.	Stop Sta.	Mined (feet)	Ribs (#)	Soil	Construction Problems and Significant Events	
10-30-71	135+86	135+83	6	2			
11-02-71	135+83	135+79	4	NS	Clay w/sand		
11-08-71	135+47	135+43	4	NS	Hard grey plastic clay w/rocks and sand	Grade is .50' high. Top Jack Not working.	
11-09-71	135+43	135+35	8	2	"		
11-10-71	135+35	135+23	12	3	Firm to soft gray plastic w/sand and rocks		
11-11-71	135+23	135+07	16	4	Firm to soft gray clay w/sand and rocks		
11-12-71	135+07	135+95	12	3	"	Conveyor belt giving trouble.	
11-13-71	134+95	None	0	0		Repair conveyor belt.	
11-15-71	134+95	134+83	12	3	Firm to soft gray clay w/some rocks		
11-16-71	134+83	134+63	20	5	Plastic gray clay w/small stones		
11-17-71	134+63	134+35	28	7	Firm to soft plastic like clay	PI #5 is 2.10'W. PI #6 is 2.20'W. Rib #431 is 1.8' high and Rib #438 is 1.2' high.	
11-18-71	134+35	134+19	16	4	Gravel and sand w/firm gray clay and rocks	PI #7 is 2.40'W PI #8 is 2.10'W. Rib #42 is .56' high. Sand in rollers. Top of Mining is gray clay. Face is 75% dry sand. Cavity 4.0' ahead of machine.	
11-19-71	134+19	133+99	20	6	Gravel and sand w/firm gray clay	Rib #46 is .46' high. Rib #50 is .70'E.	

Table 1 (continued)

11-19-71	133+99	133+83	16	4	Gravel-sand w/gray clay	Rib #53 is .20' low and 1.40'E Incline on machine is .27' low.
11-23-71 ¹	133+83	133+63	20	5	Sand and gravel w/gray clay	Rib #9 is .14' low. Can't check line.
11-24-71 ¹	133+63	133+31	32	8		
11-26-71 ¹	133+31	None	0	0		Remove sand and debris from heading.
11-27-71 ¹	133+31	None	0	0		Remove secondary conveyor used in curve.
11-28-71 ¹	133+31	None	0	0		Place sled and conveyor.
11-30-71 ¹	133+31	None	0	0		Place hydraulic system and conveyors.
12-01-71 ¹	133+31	None	0	0		Hydraulic, electrical and conveyor system assembly troubles.
12-02-71 ¹	133+31	None	0	0		"
12-03-71 ¹	133+31	None	0	0		"
12-04-71 ¹	133+31	None	0	0		"
12-06-71 ¹	133+31	133+35	4	NS	Very hard grey sand w/stones and clay	Cable between machine and sled broke.
12-07-71 ¹	133+35	133+20	15	3	Very hard gray sandy clay w/stone and gravel vein in bottom	Rocks and hydraulic system problems.
12-07-71 ¹	133+20	132+95	20	5	Hard gray clay w/stone	Rib #73 is .60' high and .80'E. Rib #75 is .56 high and .75'E. At both ribs machine is inclined .05' looking west.
12-08-71 ¹	132+95	132+85	10	2	Very hard gray sandy clay w/stones	Failure of hydraulic system. Rocks - 2' in diameter.
12-08-71 ¹	132+85	132+70	15	3	Hard gray clay	Rib #80 is .45' high. Laser lite hitting carrier.

Table 1 (continued)

12-09-71 ¹	132+70	132+50	20	4	Gray sand w/very hard	Hoisting crane down and mud cars off track.
12-09-71 ¹	132+50	132+25	25	5	Gray sand & clay w/rocks	Problems with rocks, clean up, electrical relay, hydraulics and mud car derailment. Grade is .30' high. machine is moving to the west.
12-10-71 ¹	132+25	132+05	20	4		Soft wood lagging broke - (3 pieces). Hoisting crane will not start. Rib #93 is 1.42'W and .14 high.
12-10-71 ¹	132+05	131+80	25	5	Same	Distance from correct alignment at ribs #91 is 1.0', #92 is .87', #93 is .68', #94 is .58', #95 is .33', #96 is .28', #97 is .15' and #98 is .00'. Rock, hand mining and hydraulic problems. Machine still mining to west, some roll corrected.
12-11-71 ¹	131+80	131+65	15	3	Hard sandy gray clay w/stones	Hydraulic system problems. Rib #101 is 1.75'W.
12-11-71 ¹	None					Mining machine repairs.
12-13-71 ¹	131+65	131+60	5	1		Add to conveyor.
12-13-71 ¹				1	Big boulder	Hydraulic system problems.
12-14-71 ¹	131+55	131+25	30	6	Very hard gray clay w/stones at bottom Stoney soft clay above springline	Rocks, teeth and alignment problems.
12-14-71 ¹	131+25	131+05	20	4	Hard clay to springline & sandy clay on top	Rock, conveyor and dinkie problems. Machine moving to east.
12-15-71 ¹	131+05	130+90	15	3	Very hard gray sandy clay w/stones	Mining machine's rear can developed radial crack from springline to crown. Machine grade is 15.1' high.
12-15-71 ¹	130+90	130+65	25	5	Sand gray clay. Dry	Rocks, and mud car derailment problems.

Table 1 (continued)

12-16-71	130+65	130+35	30	6	Hard gray sandy clay w/stones	Slow dinkies. Machine is .50'W.
12-16-71	130+35	130+25	10	2		Machine coming on to line. Grade is .20'+ high. Dinky broke. Fan electrical line cut.
12-17-71	130+25	130+00	25	4	"	Electrial, track, derailment and rock problems.
12-17-71	130+00	129+90	10	1		Dinky problems. Line and grade good.
12-18-71	129+90	None	0	0		Power supply cut.
12-18-71	129+91	129+56	35	7	Same	Rock and conveyor problems.
12-20-71	129+56	129+16	40	8	Very hard gray clay w/hard sandy spots w/stones	Sled, conveyor, hydraulic and rock problems.
12-20-71	129+16	128+76	40	8	Rocky gray clay & sand	Rock problems.
12-21-71	128+76	128+26	50	10	Gray sand w/firm gray clay w/stones	Rock problems.
12-21-71 ²	128+26	127+76	50	10	Same	Spilled ribs & lag.
12-22-71 ²	127+26	127+56	20	4	Clay very rocky	Shot boulder. Hydraulic, conveyor and rock problems.
12-22-71 ²	127+56	127+21	35	7	Same	Rock and teeth problems.
12-23-71 ²	127+21	126+96	25	6	Very rocky, sandy gray clay, large boulders.	Blasting rocks.
12-23-71 ²	126+96	126+76	20	4	Clay & rock	Rock and mining machine problems. Line is 0.35W.
12-23-71 ²	126+76	126+61	15	2	Very hard gray sandy clay w/traces of soft clay in crown & stones	Conveyor problems. Machine grade is .15' high.

Table 1 (continued)

12-27-71 ²	126+61	126+21	40	8	Same	Rock problems. Machine is .30' low. Line is .10' E.
12-27-71 ²	126+21	125+81	40	8	Sandy clay & rock	Blasting rock. Machine is .25' low. Derrailment, and clean up problems. Line is .10' W. Grade is .20' high.
12-28-71	125+81	125+36	45	9	Hard clay & sand w/ rocks some water.	Blasting and removal of large rock. Machine is .05' high.
12-28-71	125+36	125+01	35	7	Clay & rocks	Shield for mining machine split more on East side. Dinky (train) problems. Line is .20' East.
12-29-71	125+01	124+81	20	5	Same	Hydraulic problems.
12-29-71	124+81	124+41	40	8	Clay & large rock	Blasting rock. Line is East. Grade is obstructed but coming out.
12-30-71	124+41	124+11	30	6	Same	Rock and conveyor problems. Machine and conveyor rolled. Laser still not clear.
12-30-71	124+11	123+76	35	7	Large rock & clay	Machine back on line. Blasted rock. Line is .06' E.
12-31-71	123+76	123+46	30	6	Very hard gray clay w/stones & damp. at top	Hydraulic problems.
01-03-72	123+46	123-01	45	9	Gray clay & sand	Small problems. Ribs #190 and #210 shims fell out.
01-03-72	123+01	122+71	30	7	Same	Mud car derailment and tooth problems. Blasted rocks. Replace shims at ribs #190 and #210. Machine is .30' E & .15 low.
01-04-72	122+71	122+31	40	8	Same	
01-04-72	122+31	122+16	15	3	Hard & full of rocks	Line is .20' East. Conveyor problems. Blasting rock.
01-05-72	122+16	121+86	30	6	Very hard rock gray sandy clay	Rock problems.

Table 1 (continued)

01-05-72	121+86	None				Rib jack, conveyor and rib jacking frame problems.
01-06-72	121+86	121+51	35	7	Firm gray sandy clay w/stones	Rock, rib jack and dinky problems. Grade is .07' high to .04' high.
01-06-72	121+51	121+21	30	6	Sandy clay w/rocks	Blasting rock. Grade good. Line good.
01-07-72	121+21	120+96	25	5	Very hard gray clay w/large rocks	Problems with large rock. Grade is .05' to .00' high. Line is .19'E to .24'E.
01-08-72	120+76	None	0	0		Broke tail section of machine.
01-08-72	120-76	120+61	15	3	Very hard & rocky clay some sand showing on top	Grade is .35' high. Excessive jacking pressures required from tight mining. Dinky problems. Skin was welded.
0108-72	120+61	120+46	15	3		Grade is .32' high to .24' high.
01-10-72	120+46	120+06	40	8	Very hard gray sandy clay w/stones	Thirty inch diameter hole drilled at 120+46 + for ventilation. Rock problems. Rib grade is .23' high to .00'. Line is .05'W to .00".
01-10-72	120+06	119+91	15	3	Rocky	Hydraulic system, mud car derailment and cut electrical power problems.
01-11-72	119+91	None	0	0		No machine operator. Clean up mud from mud car derailment.
01-11-71	119+91	119+26	65	13	hard gray clay & rockly	Blasting rock. Mud car derailment Line is OK.
01-12-72	119+26	118+81	45	9	Very hard gray sandy clay w/stones	Rocks, dinky and fan line problems. Grade is .10' low to .05' low.

Table 1 (continued)

01-12-72	118+81	118+56	25	5	Hard gray clay	Mud car derailments (2), and dinky problems. Blasting rocks. Grade is .10' high. Line is .20'E.
01-13-72	118+56	118+21	35	7	Very hard gray stoney clay w/soft clay at top	Dinky, rock hydraulic and grubber clamp problems. Grade is .01' high to .05' high. Line is .10'E to .05'E.
01-14-72	118+21	117+81	40	8	Extremely hard sandy	Mechanical and rock problems. Grade is .06' high to .03' high. Line is .06'E to .03'E.
01-14-72	117+81	117+46	35	7	Hard clay & rocks	Rocks problems.
01-15-72	117+46	117+06	40	8	Very hard gray sandy clay	Rock and mechanical problems. Machine is .30' low.
01-15-72	117+06	116+81	25	5	Sand on bottom. Hard gray clay w/rocks	Conveyor and rock problems. Grade is .05' low. Line is .10'E.
01-17-72	116+81	116+41	40	8	Very firm gray sandy clay w/sandy bottom & stones	Rock, mechanical and dinky problems. Grade is .06' low to .00'. Line is .05'W to .00'.
01-17-72	116+41	116+01	40	8	Hard gray clay w/boulders	Mechanical, track, electrical and rock problems. Line and grade are good.
01-18-72	116+01	115+76	25	5	Very hard gray rocky clay with a sand seam throughout drive	Hydraulic, mechanical and rock problems. Grade is .22' low to on grade. Line is .04E to .21E.
01-18-72	115+76	115+41	35	7	Hard gray clay w/large rocks	Toothholder, conveyor and rock problems. Grade is .10' high to .00'. Line is .15'E to .00'. At rib #312, lagging board hanging at top (Set on 1-7-72).
01-19-72	115+41	None	0	0		Two rocks, motor on machine and power supply problems.
01-19-72 ³	115+41	115+11	30	7	Clay/sand on bottom	Hydraulic and conveyor problems. Roll in power trailer.

Table 1 (continued)

01-20-723	115+11	114+86	25	5	Very hard gray clay w/large stones	Rock and conveyor problems. Two motors damaged on mining machine. No operator. Grade is 07' high to .18' high. Line is .03'E to .09'W.
01-20-723	114+86	114+66	20	4	Hard gray clay & rocks w/sand	Radial hydraulic motor removed. Hydraulic problems. Blasted rocks. Grade is 05' low.
01-21-723	114+66	114+36	30	6	Very hard gray clay w/sand seam in bottom w/stones	Hard ground, conveyor and rock problems. Rib #9 is pushed out. Grade is .10' high to .05' high. Line is OK.
01-21-723	114+36	114+06	31	NS		
01-22-723	114+06	113+71	35	7	Firm gray sandy clay w/stones, dampness in bottom	Blasted rocks. Grade is .08' high to .04' high.
01-22-723	113+71	113+31	40	8	Hard clay w/rocks sandy layer at springline	Rock problems. Grade is OK. Line is .04'W to .25'E.
01-24-723	113+31	113+11	20	4	Hard gray clay w/sandy bottom and top & stones	Dinky, conveyor, electrical and rock problems. Grade is .17' high. Line is .31'W to .02'W.
01-24-723	113+11	112+76	35	7	Rocky, hard clay with traces of sand, small amount H ₂ O.	Hydraulic problems. Grade is .17' high to .02' high. Line is .05'W to .00'.
01-25-723	112+76	112+46	30	6	Firm gray sandy clay w/stones	Rock, conveyor and hydraulic problems. Line is .15'W to .09'W. Grade is .12' low to .02' high.
01+25+723	112+46	112+16	30	7		Rock and conveyor problems. Line is OK. Grade is .25' high.
01-26-723	112+16	111+91	25	5	Hard gray clay w/stones	Rock, conveyor and electrical problems. Line is .15'W to .00'. Grade is .17' high to .00'.
01-26-723	111+91	111+56	35	7	Sand layer at springline. Hard clay w/rocks	Conveyor, dinky and rock problems. Grade is .15' high.

Table 1 (continued)

01-27-72	111+56	111+31	25	5	Firm gray clay w/large stones. Signs of water in bottom	Conveyor and rock problems. Grade is .03' high. Line is .00' to .05'E.
01--27-72	111+31	111+01	30	6	Hard gray clay	Conveyor and hydraulic problems. Blasting rock. Line is .15'W to .05'W. Grade is .08' high to .00'.
01-28-72	111+01	110+71	30	6	Hard gray clay w/sandy wet bottom & stones	Rocks blasted 4 times. Mud car derailment problem. Grade is .04' low to .09' low.
01-28-72	110+71	110+41	30	6		Rocks and mechanical problems.
01-29-72	110+41	110+16	25	4	Hard ground	Hard ground problems. Rocks blasted 6 times. Grade is .04' low to .02' low. Line is .10'W to .02'E.
01-29-72	110+16	110+01	15	3	Hard clay	Lack of cutting edge. Blasting rocks. Grade is .10' high.
01-31-72	110+01	109+71	30	6	Very hard gray clay w/large rocks	Rock and mechanical problems. Grade is .00' to .18' high. Line is .05'W to .18'W.
01-31-72	109+71	109+36	35	7	Hard clay & stones	Rock, hard ground and motor problems. Blasted rocks. Grade is .15' high to .01' high. Line is .19'W to .24'W.
02-01-72	109+36	109+16	20	4	Very soft mushy clay w/stones	Sand above last two ribs caused a void approximately 5' above machine. Grade is .01' high. Line is .19'W to .21'E.
02-01-72	109+16	108+93	23	NS	Sand & gravel. Little clay.	Face slipping in eight foot over mine on crown. Face is on a slope out 8 to 10 feet from the machine. Void in the crown starting at Station 109+26. Line is .26'E to .46'E.
02-02-72	108+93	108+88	5	2	Adverse soil, w/water, sand, silt, some stones	Sand above machine is still falling, causing an approximate 8' void above machine. Conveyor problems. Machine is .02' low and .04'W.

Table 1 (continued)

02-02-72	108+88	108+86	2	0	Conveyor problems. Mud is sticky, hard to work and won't come out of machine. Water running in sides clear. Void in crown is 15' above mining machine.
02-03-72	108+86	108+85	3	1	Cave in above machine which progressed to surface. Void at surface was approx. 35' in diameter and 20' deep. It was backfilled.
02-03-72	None	None	0	0	Dug sump hole in east side in invert. Reinforced ribs are taking load. Water pump working good down hole.
02-04-72	108+85	108+78	7	3	Mud along tracks and conveyor problems.
02-04-72	108+78	108+63	15	7	Conveyor and dinky motor problems. Water coming in fast around bottom shield. Face still falling in on face of machine. Closing holes in wheel. Pumped water out down hole.
02-05-72	108+63	108+58	5	2	Conveyor problems.
02-05-72	108+58	108+43	5	6	Pumping water out down hole.
02-07-72	108+43	108+36	13	5	Conveyor problems. Sand and silt around sleds is causing excess pressure on hydraulic system. Operator is attempting to carry machine .20' high to compensate for possible rib deflection in crown.
02-07-72	108+36	108+31	5	2	Conveyor belt problems. Conveyor and mole separated. Pumping water out top hole.

Table 1 (continued)

02-08-72	None				Clean up silt and mud from around sleds, tracks and conveyor. Water continues to enter heading at and behind machine. Contractor now using two pumps to transport water up alignment hole and out of heading.
02-08-72	108+31	108+11	20	9	Face still spalling in 6' to 8' on crown and face.
02-09-72	108+11	107+78.5	32.5	14	Void above machine, with signs of settlement clear to surface. Loose sand with some sharp sand and gravel also chunks of clay which appear to be falling from above machine
02-09-72	107+78.5	108+65.5	15	NS	Crown coming in. Large void at surface. Crack from void over top of gas pipe. Stopped mining.
02-10-72	None				Face of mining falling in. Mining stopped. Surface settlement. More openings covered on wheel to prevent sand from coming in.
02-11-72	None				Plugging holes in lagging to prevent water and silt from coming in.
02-16-72	None				Test holes drilled 5' in front of machine wheel. Hole at 5' West of cylinder to 62' which showed firm clay. Hole on centerline showed firm clay to a point 5' above machine, from this point to approx. 1' above concrete invert showed white sand with slight traces of clay.
02-16-72	None				DMWS recommend last 5 ribs be reinforced because of overloading.

Table 1 (continued)

02-17-72	None	Ribs started to take weight and deflected. Three jump sets were placed and welded. Holes where water coming in were plugged.
02-18-72	None	
02-21-72	None	Checked lagging for leaks and checked pumps.
02-22-72	None	Packing straw in and place plywood over cracks between lagging where slit and water entered heading through crown.
02-23-72	None	Closing Red Run north of cofferdam. Water entering cofferdam at SE corner.
02-24-72	None	Plugging space between lagging through wet area where water and silt enter into heading. Pumping water and trying to plug hole at SE corner of cofferdam.
02-25-72	None	Pour retaining wall in cofferdam.
02-28-72	None	Heading OK - per Mr. Jim Heath.
02-29-72	None	Retaining wall resteeled OK. Water entered cofferdam and stopped work.
03-01-72	None	At cofferdam a bulkhead was being installed to prevent water from entering the tunnel south of Red Run.
03-01-72	None	Add 6" electrical pump in cofferdam.
03-01-72	None	Remove silt and sand from cofferdam.
03-03-72	None	Some settlement at cave in area approx. 3 cubic yards loss. However, there is no sign of a loss of ground in heading.

Table 1 (continued)

03-07-72	None	No further settlement at cave in area.
03-09-72	None	Remining started where machine was 2.20' high. Ribs through caved in section showed no further signs of deflection.
03-10-72	None	Plugged some cracks between lagging in heading to prevent silt from filtering through.
03-13-72	None	In the remined section. 32' of lagging boards from invert up to springline were removed.
03-14-72	None	Plugging cracks between lagging where water and silt coming into heading.
03-15-72	None	Remining continued. Seven ribs were cut, lowered and rewelded so that 12" concrete with resteel can be used.
03-16-72	None	No further deflection on ribs throughout caved in area. Sheeting and wales in cofferdam showed deflection due to excessively heavy ground around bracing.
03-17-72	None	Extra bracing placed in cofferdam.
03-18-72	None	At cofferdam knee braces placed and welded on three top wales at North end.
03-20-72	None	At the ribs in the heading, no further deflection other than that caused by initial over loading. Removed from cofferdam silt and washed in during flooding.
03-22-72	None	Ribs throughout caved in area had not deflected any more than on 02-12-72.

Table 1 (continued)

03-23-72	None	Bottom now changed from sand to hard sandy gray clay.	Remined section South of Station 136+00 in curve.
03-24-72	None		Cutting, lowering and rewelding 3 ribs.
03-25-72	None	Bottom is very hard sandy gray clay w/stones	Removed 3 ribs at springline, remined bottom and replaced ribs to accomodate 16" concrete.
03-28-72	None		Removed 5 ribs, remined to planned grade and replace ribs by welding in place.
03-30-72	None		First pour of concrete at 135+82 to 135+67.
04-08-72	None		Removed boards at west springline 134+92 to 134+12.
04-21-72	None		Downtime due to malfunction of hydraulic system on form carrier.
04-25-72	None		Took shots on ribs at cave in area and found no additional settlement.
05-04-72	None		Carrier motor problem.
05-06-72	None		Plugged space around alignment pipe at Station 108+26 where approx. 8 cubic yards of silt and sand entered heading over night. Line check not made because of silt and sand blocking tunnel.
05-08-72	107+65	107+63 2.5 1	Clean up silt and sand at Station 108+26. Track and electrical problems.
05-08-72	107+63	107+58 5 1	Conveyor problems. Muck coming in is slowing down conveyors and stopping them. More holes closed in wheel. Overexcavated 20 mud boxes (about 49 cu. yards.).

Table 1 (continued)

05-09-72	107+58	107+48	10	4	Mixed clay, sand, gravel & water, firm silty clay bottom of mining to 4 foot above, sand and gravel to top quarters with dry sand above top quarters.	More holes on wheel were closed. Overexcavated 7 mud boxes (about 17-1/2 cubic yards.)
05-09-72	107+48	107+38	10	4	Soft gray clay mixed with sand, gravel, & water	Ground stable. Void in front of mining machine approx. 9' wide, 4' high and 3' ahead of machine. Over excavated about 12 cubic yards. Blasted rock.
05-09-72	107+38	107+25.5	12.5	5	Moist sand (hardpan)	Mud car off track. Over excavated about 12.5 cubic yards. No ground settlement.
05-10-72	107+25.5	107+09	14.5	6	Full face of clay, very hard with considerable amount of rocks throughout	No excess mining. Problem with rocks. Machine is .80'W and .29' high.
05-11-72	107+09	106+71.5	27.5	11	Very hard gray clay w/many rocks throughout	Grubbler tooth, rock and mud car derailment problems.
05-12-72	106+71.5	106+58	22.5	5		Rib #643 is .15' high and .75'W. Compressor, hydraulic, conveyor and mud box problems.
05-12-72	106+58	106+38	20	4	Hard gray clay w/scattered stones	Sand and silt infiltrating through lagging on east side throughout day. Machine is out .65'W and .28' high.
05-12-72	106+38	106+18	20	5	Hard gray clay w/many rocks.	Machine is .60'W and .40' high. Mud car derailment problems.
05-12-72	106+18	106+03	15	3	"	Machine is .45' high and .35'W. Wheel hung up. Jack broken. Rocks were spaded out.
05-13-72	106+03	105+88	15	3	Very hard gray clay w/stones and some wet spots in top quarters and crown.	Machine at end of 3rd rib was .15'W and .25' high. Mud car derailment and mechanical problems.

Table 1 (continued)

05-13-72	105+88	105+78	10	2	Mostly sand and small amount of clay and then hard gray clay mixed with rocks & sand	Void above rib #662 approx. 7' high and 12' wide. Mud car derailment and hydraulic problems. Mining machine to .15' high and .05'W.
05-13-72	105+78	105+68	10	2	Dry sand with some clay w/stone throughout	Removed 23 boxes of mud for each rib (over excavated about 45 cubic yards total). Blasted rock.
05-15-72	None					Loss of ground above machine. Large wheel holes on mining machine were closed.
05-15-72	105+68	105+58	10	4	Hard gray clay, mixed with sand & rocks throughout.	Rock problems. Over excavated about 37 cubic yards of clay.
05-15-72	105+58	105+44.5	13.5	4	Hard gray clay mixed w/sand & rock	Rib #670 is .15' high and .12'E. Wheel hunk up. Blasted rock.
05-16-72	105+44	105+33	11.5	4	Very hard gray sandy clay	No excess earth removed. Blasted rocks. Conveyor problems. At 4th rib machine was .15'W.
05-16-72	105+33	105+12	21	7	Very hard gray clay w/traces of sand & many rocks.	Machine is .30'W and on grade. Rock problems.
05-16-72	105+12	104+97	15	6	Hard gray clay with stones and sand throughout	Machine is .25'W and .05' high. No excessive mud. Top of ground over tunnel holding. Conveyor problems.
05-17-72	104+97	104+89.5	7.5	3	Very hard gray clay w/scattered stones, 1.5' of top of mining is wet sand and silt.	No loss of ground. Rock, hydraulic and compressor problems. At rib #693 machine was .50'W and on grade.
05-17-72	104+89.5	104+72	17.5	7	Hard gray clay w/many rocks throughout. Wet silty sand in crown.	No excessive mud boxes. Machine is .20' high and .15'W.
05-17-72	104+72	104+60.5	15	6	Soft clay & sand in top w/hard pan in bottom w/rock.	Corrected stationing from 104+57 to 104+60.5. Machine is .05'E and .25'. Blasted rock. Compressor and dinky problems.

Table 1 (continued)

05-18-72	104+60.53	104+55.53	5	2	Very hard gray clay approx. 3' above spring line w/silt & sand above machine	Void approx. 6' above machine on SE side. Over excavated approximately 30 cubic yards. Wheel was plugged from falling earth.
05-18-72	104+55.53	104+28.03	22.5	9	Hard gray clay some clay w/considerable amount of rocks throughout. Crown shows silty sand & water.	Over excavation from rib #709 to #711. Machine is .10'E and .15' high. Blasting rock. Rocks were spaded.
05-18-72	104+28.03	104+18.03	10'	4	Very wet running in top, soft clay and sand with stone throughout in bottom	Machine is .15' high and .20'E. Void in crown. At ground level the ground is holding. No significant signs of ground moving. Overmined 60 cubic yards.
05-19-72	104+28	104+15.5	2.5	1	Face of mining was firm gray clay w/silt running into wheel from top west quarter.	10 cubic yds overmined.
05-19-72	104+15	None				A grout hole was drilled at approx. Station 10+35. It was decided to fill the void at a later date with grout or concrete.
05-20-72	None					At Station 10+30 a grout hole drilled approx. 4' East of the centerline showed a void 30' deep which was grouted. At Station 104+30 a grout hole drilled approx. 4' West of the centerline showed no void. At Station 104+25 a grout hole drilled 3' west of the centerline showed a void. The void was filled. At Station 104+10 a grout hole was drilled and a void approx. 7' above the machine was found and filled. Forty cubic yards of pea gravel was used. One half a cubic yard of grout came through wheel.
05-22-72	None				Soft ground w/silt water & rocks	Eight boxes of mud for a 6 inch shove. (Over excavated about 16 cubic yards)

Table 1 (continued)

05-22-72	None					Wheel plugged up. Check at ground level showed ground holding. Cover plates were placed over the wheel openings.
05-22-72	None					Silt and sand infiltrating into heading through lagging. Electrical problems.
05-23-72	104+15.5	104.03	12.5	5	Very soft mud like clay mixed w/silt and water	Machine is .25'E and .45' high. Void in crown approx. 12' ahead of the machine 10' high and 12' from the centerline toward East of tunnel. Check at ground level showed ground holding. Removed 14 mud boxes for each rib. (Over excavated about 82 cubic yards total)
05-23-72	104+03	103+93	10	4	Very soft mud & sand mixed with rock	Machine is .20'E and .40' high. At ground level the ground is holding. Over excavated about 60 cubic yards. Mud cars off track.
05-24-72	103+98 per report	103+83.5	14.5	5	Silty ground. At sixth rib very hard gray clay	Excessive infiltration. Eighteen cubic yards overmined. A void of 90 cubic yards occurred at ground surface at station 104+20. No sign of ribs and lagging in heading taking excessive load.
05-24-72	103+85.5 per report	103+65.5	20	8	Hard to firm gray clay w/rocks	Full face is holding in front of machine. Machine is .05'E and .05' high.
05-24-72	103+65.5	103+63	2.5	1	Hard & firm gray clay w/rock	Mining wheel hit steel sheeting at cofferdam.
05-30-72	119+67	South				At approximately 118+57 a drop hole was drilled through a field tile. Water came in "very fast" with clay mixed in. Tried to stop and/or plug it. Got it plugged up but then it

Table 1 (continued)

failed, all the fill used in plug ended up in the tunnel. Lagging was put back in and pump started. Approx. 8 mud boxes in tunnel. (About 20 cubic yards) Water entered just as the concrete pour was completed up to Station 119+67.

06-05-72	115+47	114+27	Cleaned up mud and water.
06-06-72	114+42	113+22	Cleaned up mud and water.
06-07-72	113+37	112+17	Cleaned up mud and water.
06-08-72	112+32	111+12	Cleaned up mud and water.
06-09-72	111+27	110+19	Cleaned up mud and water.
06-10-72	110+22	109+17	Cleaned up mud and water.
06-12-72	109+17	108+07	Cleaned up mud and water. Electrician called in to start up pumps. Weather was rain.
06-19-72	104+97	103+92	Cleaned up invert. Removed boards that were sticking up in invert.
06-20-72	111+27	South	Finishers cannot finish invert because of standing water.
06-22-72	Cofferdam	North	Crew climbed out of shaft at Red Run and used 10 cubic yards of concrete to stabilize bottom where sand was bubbling in. (Concrete tunnel lining was up to 103+47 on this date. No notes as to cofferdam sheeting being cut.)
06-23-72	Cofferdam		Bottom of tunnel in cofferdam was poured up to the springline.

Table 1 (concluded)

06-28-72	135+65	120+71	Grout holes between these stations were drilled and only the concrete at Station 135+68 was not tight to lagging.
06-29-72	126+12	111+26	Grout holes between these stations were drilled and only the concrete at Station 126+12 was not tight to lagging, and a void in the crown was noted.
07-05-72	108+17	103+91	Grout holes between these stations were drilled. All concrete was tight to lagging.
07-07-72	126+12		Filled void at Station 126+12.
07-07-72	12+42		Filled power drop hole.
07-14-72	Cofferdam		Backfilled 3 feet over tunnel.
08-03-72	Cofferdam		Removal of sheeting was started.
08-16-72	Cofferdam		During the night the river came in and filled the shaft to the level of the river.

1. Represents work in distressed area number 1.
2. Represents work in distressed area number 2.
3. Represents work in distressed area number 3.
4. NS under the column Ribs means that the number of ribs set that shift were not specified in the inspector's reports.

Table 2
Concrete Summary

Date	Concrete Placed		Time		Operation/Problem/Notes
	From	To	From	To	
3-31-72	135+82	135+67	1300	1445	Pour//Resteel in lower east quarter from station 135+67 to 135+82.
4-05-72			0700	1330	Form
4-06-72	135+67	134+92	1645	2145	Pour/Void in arch at bulkhead 31 high and back approx. 32'/Restee at lower west quarter at station 135+52
4-08-72			0700	1530	Form
4-10-72	134+92	134+12	1820	2345	Pour/Void over old work may only be partly filled/Resteel at west springline from Station 134+87 to 134+42. Resteel at invert from Station 134+12 to 134+27
4-11-72					Strip//Section fair
4-12-72				2400	Strip/Stone pockets from west quarter point to east quarter point Station 134+97
¹ 4-13-72	134+12	133+32	1230	1615	Pour 80'. Stripped bulkhead with 15' arch and invert. Form 15'//Resteel at west springline at Station 133+82
¹ 4-14-72					Strip/Rock pockets at Station 134+12
¹ 4-14-72			0700	1500	Strip/Rock pocket 3' Dia. west springline
¹ 4-14-72			1600	2400	Form 15' arch and invert. Strip 15" arch.
¹ 4-15-72			0700	2400	Strip and form. Sixty feet formed

1. Represents work in distressed area number 1.
2. Represents work in distressed area number 2.
3. Represents work in distressed area number 3.

Table 2 (continued)

Date	Concrete Placed		Time		Operation/Problem/Notes
	From	To	From	To	
4-17-72 ¹	133+32	132+27	1125	1650	Pour/Pour progressed very slowly due to slow arrival of concrete trucks./Resteel in bottom 1/2 from Station 132+57 to 133+17
4-20-72 ¹					Strip/Honeycomb at springline east and west Station 133+32
4-20-72 ¹			1600	0100	Form 35' of invert and remove bolts for next 35'
4-21-72 ¹			Day	SHift	Strip and form 70' each
4-21-72 ¹	132+27	131+22	1800	2215	Pour/Malfunction in hydraulic from carrier
4-24-72 ¹			0700	1630	Strip and Form 105' each/Malfunction in hydraulic from carrier
4-24-72 ¹	131+22	130+17	1600	1945	Pour
4-24-72 ¹			1600	2430	Clean up ahead of pour
4-25-72 ²	130+17	129+12	1300	1630	Pour and strip/1.5 cubic yards short on pour, rock pocket east side Station 130+17, three cold joints east and west sides Station 130+17 and 130+35
4-25-72 ²			1600	2430	Strip and form 105' each
4-26-72 ²	129+12	128+07	1220		Pour strip and form 105' each/concrete was poured somewhat wet and with ground water caused forms to shift eastward and rise above setting.05'. It was suggested to foreman that more trucks are needed for a pour of this length. Small rock pockets top quarters Station 130+17. Cold joint lower east quarter Station 130+17/Ten Feet of resteel at east springline at Station 128+92

Table 2 (continued)

Date	Concrete Placed		Time		Operation/Problem/Notes
	From	To	From	To	
2 4-27-72	128+07	127+02	1205	1530	Pour and strip/Small honeycombed spots at bulkhead Station 128+07
2 4-28-72	127+02	125+97	1300	1720	Pour/After pouring 260 cubic yards drop shaft plugged up, could not move even from top, void in crown approx. ten cubic yards (15'x8') not covering forms
2 4-29-72	125+97	124+92	1300	1550	Pour and strip/Ordered ten cubic yards extra to fill void left on 4-28-72
5-01-72	124+92	123+87	0815	1335	Pour and strip/At Station 125+8 a stone pocket 4'x1' in the east quarter. At Station 125+45 a stone pocket 6"x5' in the west quarter
5-02-72	123+87	122+82	1000	1255	Pour and strip/V type cold joint at invert Station 123+20 and 13' long cold joint at west side of Station 123+30/Resteel at crown from Stations 122+82 to 122+93
5-04-72	122+82	121+77	1640	1940	Pour and strip/Rock seam 14' long lower west quarter at Station 123+87 to 123+73. A 2' dia. rock pocket at Station 123+87 at east springline. Finish grade is .01' down/Resteel in top east quarter from Station 122+47 to 122+82
5-04-72			Day & Afternoon		Strip and form 105' each
5-05-72	121+77	120+72	1300	1630	Pour and strip
5-30-72	120+72	119+67	1355	1715	Pour and strip
5-01-72	119+67	118+62	1700	2130	Pour and strip/One hour and fifteen minute delay due to both drop holes plugging up, went through top doors to start concrete moving/Waterstop at Station 118+62
5-02-72	118+62	117+57	1600	1930	Pour and strip/Small amount of cold joint east and west lower quarters/Waterstop at Station 117+57.

Table 2 (continued)

Date	Concrete Placed		Time		Operation/Problem/Notes
	From	To	From	To	
6-03-72	117+57	116+52	1445	1725	Pour and strip/2'x4' honeycomb at lower quarter east side Station 118+61/Thirty feet of resteel crown at Station 117+42. Waterstop at Station 116+52
6-05-72	116+52	115+47	1425	1825	Pour and strip/2'x1' trace of clay in crown at Station 117+22/Waterstop at Station 115+47
6-05-72			1700	0100	Remove form bolts for 105'
6-06-72	115+47	114+42	1225	1610	Pour and strip/Small rock pockets at start of pour and small cold joints/Waterstop at Station 114+42
6-06-72			1700	2430	Remove form bolts for 105'
6-07-72	114+42	113+37	1205	0304	Pour and strip/Several cold joints both east and west sides approx. 1/2" wide/Waterstop at Station 113+37
6-07-72			1700	2400	Remove form bolts for 105'
6-08-72	113+37	112+32	1230	1540	Pour and strip/Waterstop at Station 112+32
6-08-72			1700	0100	Remove form bolts for 105'
6-09-72	112+32	111+27	1300	1640	Pour and strip/Four small cold joints east and west sides/Thirty five feet of resteel in top from Station 111+47 to 111+82. Waterstop at Station 111+27
6-09-72			1700	0130	Remove form bolts for 105'
6-10-72	111+27	110+22	1430	1650	Pour and strip/Rock pockets east and west springline Station 110+82. Waterstop at Station 110+22
6-12-72	110+22	109+17	1450	1730	Pour and strip/3'x3' honeycomb a east and west side Station 111+27 at springline/Resteel in bottom 1/2 from Station 109+17 to Station 109+52. Waterstop at Station 109+17

Table 2 (concluded)

Date	Concrete Placed		Time		Operation/Problem/Notes
	From	To	From	To	
6-14-72	108+17	108+12	1250	1645	Pour and strip//Resteel in top 1/2 from Station 108+12 to 108+47. Steel around entire tunnel from Station 108+47 to 109+02. Waterstop at Station 108+12
6-16-72	108+12	107+07	0925	1300	Pour and strip/Resteel in invert from Station 107+07 to 107+97. Resteel in crown from Station 107+47 to 108+12. Waterstop at Station 107+07
6-17-72	107+07	106+02	1320	1545	Pour and strip/Minor honeycomb east and west side/Resteel in invert from Station 106+02 to 106+67. Waterstop at Station 106+02
6-19-72	106+02	104+97	1415	1745	Pour and strip/Small rock pockets around construction joint at Station 107+07 also clay in crown Station 106+57/Resteel in bottom 1/2 from Station 104+97 to 105+87. Waterstop at Station 104+97
6-20-72	104+97	103+92	1245		Pour and strip/Few small rock pockets throughout pour due to stoney concrete. Surface of concrete is generally good/Resteel at bottom 1/2 from Station 104+27 to 104+82. Two bars in invert entire pour. Waterstop Station 103+92
6-21-72	103+92	103+47	1400	1545	Pour and strip/Minor roughness at invert/Twenty feet of resteel in upper 1/2 at Station 103+77. Waterstop at Station 103+47
6-27-72					Core removed at springline west side at Station 135+73
6-29-72					Two cores removed at Station 123+17 at springline and lower quarter east side
7-05-72					Core removed at crown Station 104+17
7-07-72 ²					Filled void at Station 126+12 and filled power drop hole at Station 123+42

Table 3
Available Information Used in Geotechnical Study

Source	Project	Description of Information
City of Detroit Water and Sewerage Department	Contract PCI-7 PCI-3 and PCI-16	Preconstruction boring logs and soil test data and plans showing boring locations.
	Contract PC-433	Construction boring logs and plans showing boring locations.
	Contract PCI-7	Design calculations. Specifications and as-built drawings. Tunnel Rib, Drawing No. 109-6. Construction Photographs. DMWS construction inspector's shift reports. DMWD Sewer construction daily reports. Project summary reports. "Summary of Contract PCI-7, Inspectors Mining Reports Compared to PCI-3 Boring Logs," by E. Kulick.
	Contract CS-858	Contract drawings for the temporary bypass and pumping shaft. Photographs and video tape of tunnel Distress Areas 1 and 2. Complete set of logs for test borings, piezometer borings, settlement pin borings and dewatering well borings. Daily Inspection Reports for 1 Feb 80 to 10 Mar 80. Tunnel profiles. Piezometer readings through 23 May 80.
	General	DMWS Soil laboratory test descriptions and legends.
Corps of Engineers Detroit District	PCI-7	Color Photographs of PCI-7 tunnel interior after initial cleanup, Sta 133+75 to Sta 110+15.
	Flood Control Study	Boring logs, plan of boring locations and laboratory test data along Red Run, vicinity of PCI-7.
	Wastewater Management	"Special Report, Geologic Considerations for South East Michigan Wastewater Management," Feb 73 by Andrew Mazola.
U. S. Geological Survey in cooperation with U. S. Army Corps of Engineers	Water Resources	Southeastern Michigan Water Resources Study, Groundwater and Geology, 1975, by F. R. Twenter

Table 4
WES Surface Borings

Boring No.	Location		Sample Type	Purpose
WES-1	116+42	20'E	Split spoon/ Undisturbed	Soil stratification, in situ soil conditions and undisturbed samples from 45 to 67 ft depth in nondistressed area.
WES-2	125+18	22'E	Split spoon	Soil stratification and in situ conditions in nondistressed area.
WES-3	130+20	20'E	Undisturbed	Soil stratification, in situ soil conditions, and undisturbed samples close to south end of Distress Area 1.
WES-4	112+81	18'E	Undisturbed	Soil stratification, in situ soil conditions, and undisturbed samples in Distress Area 3.
WES-5	126+85	25'E	Undisturbed	Soil stratification, in situ soil conditions and undisturbed samples in Distress Area 2.
WES-6	128±50	±20'E	None	Define extent and depth of landfill found in WES-2, WES-3, and WES-5.
WES-7	122±80	±20'E	None	
WES-8	124±00	±20'E	None	
WES-9	114+25	12'E	Split spoon	Define soil strata and in situ conditions adjacent to tunnel in Distress Area 3 between depths of 45 to 65 ft.
WES-10	113+25	13'W	Split spoon	

Table 5. Location of Construction Dewatering Wells
15 Mile Road to Red Run (Source: DMWD Daily Reports,
10-20-70 to 12-14-70)

Station*	Depth of Well ft	Depth to Water During Drilling	Remarks
136+33	-		20 ft west and 20 ft north of 9' 6" tunnel stub
134+05	93	65	Hit rock and water at depth of 65 ft.
133+05	93	65	
132+05	92	68	
131+05	92	70	
130+05	93	68	
129+10	93	65	
128+10	94	68	
126+98	92	72	
125+92	92	67	
124+95	91	61	
124+20	92	67	
123+25	91	63	
122+20	89	69	
121+25	86	69	
120+20	89	61	
119+20	91	57	
118+05	86	57	
116+80	93	55	
115+80	91	57	
114+80	98	-	
113+80	96	72	
112+20	52	52	Hit rock and water at 52 ft.
111+80	99	65	
111+70	50	-	
111+20	105	43	

Table 5 (Continued)

Station*	Depth of Well ft	Depth to Water During Drilling ft	Remarks
110+70	70	-	
110+20	88	43	
109+20	85	-	
108+67	73	68	
108+22	96	40	
107+65	62	50	Hit rock at 62 ft.
107+35	87	73	Hit water and sand at 73.
107+05	91	50	
106+75	65	40	Hit rock at 65
106+20	97	53	
105+80	85	40	

* All wells located 25 ft east of tunnel centerline.

Table 6. Extracts Concerning Dewatering from
Detroit Metropolitan Water Department Daily Inspection Reports

Date	Shift	Inspector	Log Entry
10-26-70	Day	E. Karsten	"Tri-State Drilling put down well No. 122 at sta 110+20, depth 88 ft and well No. 123 at sta 111+20, depth 105 ft. No Gas by test with well full of water."
10-27-70	Day	E. Karsten	"Tri-State Drilling put down well No. 124 at sta 106+20, depth 97 ft, no explosive gas by test, but well full of water."
8-4-72	Day	H. Ezekiel	"3 operators and 3 men started removing and pulling deep well casings N. of cofferdam shaft."
8-7, 8, 9, 10, 11, 13, 14-72	Day	H. Ezekiel	"3 operators and 3 men continued to pull deep well casings N. of cofferdam shaft."
8-15, 16-72	Day	H. Ezekiel	"Continued to pull deep well casings S. of 15 Mile Rd, 3 men and 3 operators working."

Table 7

Soil Conditions Noted in DMWS Inspector Daily (Shift) Reports

Date	Station		Ground Condition
	From	To	
11-02-71	135+83	135+79	Plastic-like clay with <u>sand</u> throughout
11-08-71	135+47	135+43	Hard, gray plastic-like clay with rocks and <u>sand</u>
11-09-71	135+43	135+35	Firm, gray plastic-like clay with rocks and <u>sand</u>
11-10-71	135+35	135+23	Firm to soft gray plastic-like clay mixed with <u>sand</u> and rocks
11-11-71	135+23	135+07	Firm to soft gray clay with <u>some sand</u> and rocks
11-12-71	135+07	134+95	Firm to soft gray clay with <u>some sand</u> and rocks
11-15-71	134+95	134+83	Firm to soft gray clay with some rocks
11-16-71	134+83	134+63	Plastic-like gray clay with small stones throughout
11-17-71	134+63	134+35	Firm to soft plastic-like gray clay
11-18-71	134+35	134+19	<u>Gravel and sand</u> mixed with firm gray clay, some rocks included
11-19-71	134+19	133+99	<u>Gravel and sand</u> mixed with firm gray clay
11-19-71	133+99	133+83	<u>Gravel and sand</u> mixed with gray clay throughout
11-23-71	133+83	133+63	<u>Sand and gravel</u> with gray clay throughout
11-24-71	133+63	133+35	not recorded
12-06-71	133+35	--	Very <u>hard gray sand</u> mixed with scattered stones and traces of clay
12-07-71	133+35	133+20	Very hard gray sandy clay with stones of various sizes, above lower 1/4 point; <u>gravel vein</u> in very bottom of tunnel
12-07-71	133+20	132+95	Hard gray clay with stones throughout
12-08-71	132+95	132+85	Very hard gray sandy clay with some scattered stones throughout
12-09-71	132+50	132+25	<u>Gray sand</u> and clay with rocks
12-09-71	132+70	132+50	<u>Gray sand</u> mixed with very hard gray sandy seams and scattered stones throughout
12-10-71	132+25	132+05	not recorded
12-10-71	132+05	131+80	not recorded
12-11-71	131+80	131+65	Hard sandy gray clay with scattered stones
12-14-71	131+25	131+05	Hard clay to spring line and sandy gray clay on top
12-14-71	131+55	131+25	Very hard gray clay with stones throughout the bottom and stoney softer clay above spring line
12-15-71	130+90	130+65	<u>Sand</u> and gray clay; dry condition

Table 7 (Continued)

Date	Station		Ground Condition
	From	To	
12-15-71	131+05	130+90	Very hard gray sandy clay with scattered stones
12-16-71	130+65	130+35	Hard gray sandy clay with scattered stones of various sizes throughout
12-16-71	130+35	130+25	not recorded
12-17-71	130+25	130+00	Hard gray sandy clay with scattered stones
12-17-71	130+00	129+90	not recorded
12-18-71	129+91	129+56	not recorded
12-20-71	129+56	129+16	Very hard gray clay with <u>hard sandy spots</u> ; also many stones of various sizes throughout
12-20-71	129+16	128+76	Rock and gray clay and <u>sand</u>
12-21-71	128+76	128+26	<u>Gray sand</u> mixed with traces of firm gray clay, also pebbles to large stones are prevalent throughout
12-21-71	128+26	127+76	Same as above
12-22-71	127+76	127+56	Clay, very rocky
12-22-71	127+56	127+21	Same as above
12-23-71	127+21	126+96	Very rocky sandy gray clay; large boulders
12-23-71	126+96	126+76	Clay and rocks
12-24-71	126+76	126+61	Very hard gray sandy clay with traces of soft clay in the crown; also scattered stones throughout
12-27-71	126+61	126+21	Same as above
12-28-71	125+81	125+36	Hard clay and <u>sand</u> with rocks; <u>some water started to appear</u>
12-29-71	125+01	124+81	Same as above
12-29-71	124+81	124+41	Clay and large rocks
12-30-71	124+41	124+11	Same as above
12-30-71	124+11	123+76	Large rocks and clay
12-31-71	123+76	123+46	Very hard clay with many stones of various sizes; also some <u>signs of dampness throughout</u>
01-03-72	123+46	123+01	Gray <u>sand</u> and clay with rocks
01-03-72	123+01	122+71	Same as above
01-04-72	122+71	122+61	Same as above
01-04-72	122+31	122+16	Hard, full of rocks
01-05-72	122+16	121+86	Very hard rocky gray sandy clay
01-06-72	121+86	121+51	Firm gray sandy clay with many stones

Table 7 (Continued)

Date	Station		Ground Condition
	From	To	
01-06-72	121+51	121+21	Sandy clay and rocks
01-07-72	121+21	120+96	Very hard gray clay with many large rocks
01-07-72	120+96	120+76	Hard clay with stones
01-08-72	120+76	120+61	Very hard and rocky clay, some sand showing on top
01-10-72	120+46	120+06	Very hard gray sandy clay with many stones throughout
01-10-72	120+06	119+91	Rocky
01-11-72	119+91	119+26	Hard gray clay, rocky
01-12-72	119+26	118+81	Very hard gray sandy clay with scattered stones throughout
01-12-72	118+81	118+56	Hard gray clay with boulders
01-13-72	118+56	118+21	Very hard gray stoney clay with some soft clay in top
01-14-72	118+21	117+81	Extremely hard sandy gray clay with a lot of stones of various sizes
01-14-72	117+81	117+46	Hard clay and rocks
01-15-72	117+46	117+06	Very hard gray sandy clay
01-15-72	117+06	116+81	Hard gray clay with rocks; <u>sand on bottom</u>
01-17-72	116+81	116+41	Very firm gray sandy clay with <u>sandy bottom</u> and scattered stones throughout
01-17-72	116+41	116+01	Hard gray clay with boulders
01-18-72	116+01	115+76	Very hard gray rocky clay, with a <u>sandy seam</u> throughout
01-18-72	115+76	115+41	Hard gray clay with large rocks
01-19-72	115+41	115+11	Clay with <u>sand on bottom</u>
01-20-72	115+11	114+86	Very hard gray clay with many large stones
01-20-72	114+86	114+66	Hard gray clay and rocks with traces of sand
01-21-72	114+66	114+36	Very hard gray clay with <u>sand seams in bottom</u> ; also many stones of various sizes
01-21-72	114+36	114+06	Hard clay with rocks
01-22-72	114+06	113+07	Firm gray sandy clay with scattered stones throughout
01-22-72	113+71	113+31	Hard clay with rocks; <u>sandy layer in face</u> at springline
01-24-72	113+31	113+11	Hard gray clay with <u>sandy bottom</u> and top; also scattered stones
01-24-72	113+11	112+76	Rocky hard clay with traces of sand and <u>small amount of water</u>

Table 7 (Continued)

Date	Station		Ground Condition
	From	To	
01-25-72	112+76	112+46	Firm gray sandy clay with many stones of various sizes
01-25-72	112+46	112+16	Same as above
01-26-72	112+16	111+91	Hard gray clay with scattered stones
01-26-72	111+91	111+56	Hard clay with rocks
01-27-72	111+56	111+31	Firm gray clay with many large stones throughout
01-27-72	111+31	111+01	Hard gray clay but getting softer as indicated by mining machine
01-28-72	111+01	110+71	Hard gray clay with <u>sandy wet bottom</u> and scattered stones
01-28-72	110+71	110+44	Same as above
01-29-72	110+44	110+16	Hard ground and many large rocks
01-29-72	110+16	110+01	Hard clay
01-31-72	110+01	109+71	Very hard gray stoney clay with many large rocks throughout
01-31-72	109+71	109+36	Hard clay and stones throughout
02-01-72	109+36	109+16	Very soft mushy clay with a lot of stones
02-01-72	109+16	108+93	<u>Sand and gravel</u> , little clay
02-02-72	108+93	108+88	Adverse soil mixed with <u>water</u> , <u>sand</u> , silt, and some stones
02-03-72	108+88	108+85	Plastic clay
02-04-72	108+78	108+63	not recorded
02-04-72	108+85	108+78	<u>Sand</u> , silt, <u>water</u> , with some gray clay throughout
02-05-72	108+63	108+58	<u>Sand</u> , gravel, and <u>water</u> , with traces of clay
02-05-72	108+58	108+43	<u>Sand</u> with hard-pan gravel
02-07-72	108+43	108+36	Entire base of mining consists of <u>sand</u> mixed with <u>coarse sand</u> and <u>gravel</u>
02-07-72	108+36	108+31	not recorded
02-08-72	108+31	108+11	not recorded
02-09-72	108+11	107+78.5	<u>Loose sand</u> mixed with sharp <u>sand</u> and <u>gravel</u> ; also chunks of clay which appeared to be falling from the above machine, thereby causing voids with signs of settlement clear to the surface
02-09-72	107+78.5	107+65.5	not recorded
05-08-72	107+65.5	107+63	<u>Wet sand</u> mixed with traces of <u>wet</u> clay
05-08-72	107+63	107+58	<u>Very wet</u> mud and <u>sand</u>

Table 7 (Continued)

Date	Station		Ground Condition
	From	To	
05-09-72	107+58	107+48	Mixed clay, <u>sand</u> , <u>gravel</u> , and <u>water</u>
05-09-72	107+48	107+38	Soft gray clay, mixed with <u>sand</u> , <u>gravel</u> and <u>water</u>
05-10-72	107+25.5	107+09	Very hard gray clay, with considerable amount of rocks throughout
05-11-72	107+09	106+71.5	Very hard gray clay, with many rocks throughout
05-11-72	107+09	106+86.5	Very hard clay with scattered stones throughout
05-12-72	106+58	106+38	Hard gray clay with scattered stones
05-12-72	106+38	106+18	Hard gray clay with many rocks throughout
05-12-72	106+18	106+03	Hard gray clay with rocks throughout
05-13-72	106+03	105+88	Very hard gray clay with scattered stones and some <u>wet spots</u> within 1/4 of the top and crown
05-13-72	105+88	105+78	Hard gray clay mixed with rocks and <u>sand</u>
05-13-72	105+78	105+68	<u>Dry sand</u> with some clay and stones throughout
05-15-72	105+68	105+58	Hard gray clay mixed with <u>sand</u> and rocks throughout
05-15-72	105+58	105+44.5	Hard gray clay mixed with <u>sand</u> and rocks
05-16-72	105+44.5	105+33	not recorded
05-16-72	105+33	105+12	Very hard gray clay with traces of sand and many rocks
05-16-72	105+12	104+97	Hard gray clay with <u>sand</u> and stones throughout
05-17-72	104+97	104+89.5	Very hard gray clay with scattered stones
05-17-72	104+89.5	104+72	Hard gray clay with many rocks throughout; <u>wet silty sand</u> in crown
05-17-72	104+72	104+60.53	Soft clay and <u>sand</u> in top with hard-pan in bottom; also rocks
05-18-72	104+60.53	104+55.53	Very hard clay approximately 3 ft above springline, with silt and <u>sand above machine</u>
05-18-72	104+55.53	104+28.03	Hard gray clay with considerable amount of rocks throughout; crown shows <u>silty sand</u> and <u>water</u>
05-18-72	104+28.03	104+18.03	Soft clay and <u>sand</u> with stones throughout
05-19-72	104+18	104+15.5	Firm gray clay
05-23-72	104+15.5	104+03	Very soft, mud-like clay mixed with silt and <u>water</u>
05-23-72	104+03	103+93	Very soft mud and <u>sand</u> mixed with rocks throughout

Table 8
Summary of Grouting Operations
15 Mile Road/Edison Corridor Tunnel Failure Study

<u>Grout Hole</u>	<u>Location</u>	<u>Date Installed</u>	<u>Date Grouted</u>	<u>Quantity of Grout</u>
2	128+66 - 10' E	2/2/80	2/7/80	0 cu ft
3	128+67 - 12' W	2/5/80	2/7/80	0 cu ft
4	131+83 - 12' W	2/3/80	2/4/80	110 cu ft
5	131+83 - 9' E	2/1/80	2/2&3/80	570 cu ft
6	132+23 - 8' E	2/5/80	2/6/80	150 cu ft
8A	132+40 - 9' E	2/5/80	2/6/80	0 cu ft
10	131+66 - 11' E	2/4/80	2/5/80	200 cu ft
11	131+51 - 11' W	2/4/80	2/6/80	50 cu ft
12	131+72 - 11' W	2/4/80	2/4&5/80	313 cu ft
15	128+46 - 9' E	2/6/80	2/7/80	0 cu t
16	128+52 - 12' W	2/6/80	2/7/80	0 cu ft
17	128+26 - 9' E	2/6/80	2/7/80	27 cu ft

Table 9
Summary of Dates of TB Borings Pressure Grouting and First Settlement Pin Reading

Station	West Side of Tunnel			Tunnel Crown Settlement Pins		East Side of Tunnel			Tunnel Segment
	TB Boring	Date Completed	Date/ Cu. Ft. Grouted	Pin No.	First Reading	TB Boring	Date Completed	Date/ Cu. Ft. Grouted	
133+75	26	2-8-80	NG			8A	2-5-80	2-6/0	
						8B	2-5-80	NG	
				7	2-5-80	6	2-5-80	2-6/150	Distressed
	13	2-5-80	NG	6	2-5-80	9	2-3-80	NG	Area
	4	2-3-80	2-4/110	5	2-5-80	5	2-1-80	2-2, 2-3/570	No.
130+75 129+10	12	2-4-80	2-4, 2-5/313	9	2-6-80	10	2-4-80	2-5/200	1
	11	2-4-80	2-6/50	8	2-5-80	24	2-7-80	NG	
	23	2-7-80	NG	4	2-5-80	22	2-7-80	NG	North
	20	2-7-80	NG	2	2-5-80	19	2-7-80	NG	of
	3	2-5-80	2-7/0	1	2-5-80	2	2-2-80	2-7/0	Distressed
128+25	16	2-6-80	2-7/0						Area
	18	2-6-80	NG	3	2-5-80	15	2-6-80	2-7/0	No.
						17	2-6-80	2-7/27	2

NG = Not Grouted

Table 10

Summary of Water Leakage from Mineral Buildup at Joints,
Sta 123+00 to 115+00, Nondistressed Area

<u>Station</u>	<u>Type of Joint</u>	<u>Tunnel Side</u>	<u>Type of Mineral and/or Amount of Staining or Crust</u>
122+35	Circumferential crack	--	Heavy
122+07	Cold	--	
121+75	Construction	East and West	Heavy iron crusts
120+70	Construction	East and West	Heavy iron crusts
119+70	Construction	East and West	Heavy iron crusts
119+20 to 119+30	Cold	East and West	Numerous zones, heavy
119+00	Cold	East	Slight stain
118+62	Construction	East and West	Slight stain
117+07	Unknown	East and West	Moderate
116+50	Construction	East and West	Heavy
116+10	Unknown	East and West	Heavy
116+00 to 115+95	Cold	--	Moderate
115+45	Construction	--	Slight
115+35	Crack	--	Moderate (had been epoxied)

Table 11. Summary of Soil Conditions Behind Tunnel Wall

Station	Location		Concrete Thickness [†] ft	Lagging Thickness ft	Pipe Sample ft	Soil Description and Remarks	Cone Penetration Data (30 deg cone, 0.5 in.) ²	
	Tunnel Side	Clock Hr North					Cone Reading psi	Remarks
132+70	E Wall	4:00	1.3	0.3	1.6 - 3.0	Lean silty clay and sand, gray, dense, 1-in. R-bar at 0.7 ft	-	Not tested
132+70	Invert	6:00	1.3	0.15±	2.5 - 3.0*	Sandy silt, gray	-	Not tested
132+70	W Wall	8:00	1.3	0.30	1.6 - 3.4	Silty clay, gray	-	Not tested
132+60	E Wall	4:00	1.35	-	1.65 - 2.05	Sand, fine, gray	-	Not tested
132+60	Invert	6:00	1.3	0.2±	2.5 - 3.0*	Sandy silt, gray	-	Not tested
132+60	W Wall	8:00	1.55	0.30	1.85 - 2.3	Silty sand, fine, clay lenses, gray	-	Not tested
132+50	E Wall	4:00	1.25	0.30	1.6 - 2.0	Silty sand, same as above	-	Not tested
132+50	Invert	6:00	1.35	0.15±	2.5 - 3.1*	Sandy silt, gray, dense, clay lenses	-	Not tested
132+50	W Wall	8:00	1.25	0.3	1.6 - 2.0	Silty sand, clay lenses	-	Not tested
132+42	E Wall	4:00	1.4	0.3	1.7 - 2.1	Silty clay, small gravel	-	Not tested
132+42	Invert	6:00	1.5	0.15±	2.2 - 2.8*	Sandy silt, gray	-	Not tested
132+42	W Wall	8:00	1.4	0.3	1.7 - 2.1	Silty sand, fine, gray	-	Not tested
132+36	E Wall	3:30	1.5	0.3	1.9 - 2.4	Silty sand, fine, gray, frozen, One 1/2-in. piece gravel	-	Not tested
132+35	E Wall	4:00	1.35	0.3	1.8 - 2.2	Silty clay and silt, gray, frozen	-	Not tested
132+35	Invert	6:00	1.4	0.15±	2.5 - 2.8*	Sandy silt, gray, dense, moderate cohesion	-	Not tested
132+35	W Wall	8:00	1.35	0.30	1.7 - 2.0	Silty sand, fine, gray, frozen	-	Not tested
132+22	E Wall	3:00	1.4	0.3	1.7 - 2.0	Silty sand, fine with clay lenses, gray, semi-frozen	-	Not tested
132+22	E Wall	4:00	1.45	0.30	1.8 - 2.2	Silty sand, fine, gray, semi-frozen	-	Not tested
132+22	Invert	6:00	1.45	0.15±	1.8 - 2.4*	Silty sand, fine, gray, dense, moderate cohesion	-	Not tested
132+22	W Wall	8:00	1.45	0.35	1.8 - 2.2	Sandy silt, gray semi-frozen	-	Not tested
132+22	W Wall	9:00	1.55	0.30	1.85 - 2.3	Silty clay and silt, gray semi-frozen	-	Not tested

(Continued)

Table 11 (Continued)

Station	Tunnel Side	Location		Concrete Thickness† ft	Lagging Thickness ft	Pipe Sample ft	Soil Description and Remarks	Cone Reading psi	Cone Penetration Data (30 deg cone, 0.5 in.)	
		North	South						Remarks	Remarks
132+12	E Wall	3:00		1.3	0.3	1.6 - 2.0	Silty clay and silt, gray, frozen, one piece 1/2-in. gravel	-	-	Not tested
132+12	E Wall	4:00		1.3	0.3	1.6 - 2.0	Silty clay and silt, gray, frozen	-	-	Not tested
132+12	Invert	6:00		1.4	0.15±	1.7 - 2.0	Sandy silt, gray, dense, moderate cohesion	-	-	Not tested
132+12	W Wall	8:00		1.35	0.35	1.7 - 2.1	Silty sand, fine, gray, frozen	-	-	Not tested
132+12	W Wall	9:00		1.5	0.3	1.9 - 2.2	Silty clay, gray, frozen, 0.5 percent fine gravel	-	-	Not tested
130+25	E Wall	3:00		1.35	0.3	1.7 - 2.3	Clay, gray, firm, moist, CL, 5 percent fine gravel	170**		
130+25	W Wall	9:00		1.35	0.3	1.6 - 2.7	Sand, very fine, gray, moderate cohesion, clay seam, gray, dense, CL	170**		
130+10	E Wall	3:00		1.3	0.3	1.6 - 2.4	Clay, gray, firm, moist, CL, 5 percent gravel	170**		
129+12	E Wall	3:45		-	-	-	Silty sand, moderate cohesion, dry	220**		
129+12	W Wall	8:00		1.4	0.3	1.7 - 2.6	Silty sand, no cohesion, dry	240**		
128+52	E Wall	3:00		1.4	0.3	1.7 - 2.6	Silty sand and sand	140**		
128+52	W Wall	9:00		1.5	0.3	1.8 - 2.9	Silty sand, moderate cohesion, dry	170**		
128+39	E Wall	3:00		1.3	0.3	2.1 - 2.6	Silty sand, moderate cohesion, dry	300+		Pushed to cone shoulder (1.5-in. penetration)
128+07	E Wall	3:00		1.3	0.3	1.6 - 3.3	Silty sand, very fine, gray, moderate cohesion, moist	180		1.5-in. penetration
128+07	E Wall	4:00		1.6	0.3	1.9 - 3.0	Clay contact at lagging into silty sand, moderate cohesion, dry	170		6-in. penetration
128+07	W Wall	8:00		1.6	0.3	1.9 - 2.8	Clay contact at lagging into silty sand, moderate cohesion, dry	300		1.5-in. penetration

(Continued)

Table 11 (Continued)

Station	Location		Concrete Thickness† ft	Lagging Thickness ft	Pipe Sample ft	Soil Description and Remarks	Cone Penetration Data (30 deg cone, 0.5 in.) ²	
	Tunnel Side	Clock Hr North					Cone Reading psi	Remarks
127+02	E Wall	3:30	1.3	0.3	1.9 - 3.0	Clay, gray, soft, moist, CL	220	5.4-in. penetration
127+02	W Wall	8:30	1.4	0.3	1.7 - 2.8	Clay, same as above	140	1.5-in. penetration
126+12	E Wall	3:00	1.7	0.3	2.2 - 2.8	Sandy clay, very fine, sand with approximately 30 percent clay, gray, moist, dense	170**	
126+12	E Wall	3:30	1.8	0.3	2.3 - 3.2	Silty sand, fine, gray, moderate cohesion, moist	180**	
126+12	W Wall	8:30	1.3	0.3	1.7 -	Silty sand, fine, gray, moderate cohesion, moist	240**	
125+97	E Wall	3:30	1.5	0.3	2.0 - 3.0	Clay, gray, dense, CL, wet at lagging, dryer with depth	220**	
125+97	W Wall	8:30	1.5	0.3	1.9 - 2.4	Silty sand, fine, gray with clay, moist, dense	250**	
124+92	E Wall	3:30	1.7	0.3	2.1 - 3.6	Silty sand (same as above)	220**	1.5-in. penetration
124+92	W Wall	8:30	1.5	0.3	1.9 -	Silty sand (same as above)	200**	
123+87	E Wall	4:00	1.5	0.3	1.9 -	Sandy silt, very soft, moderate cohesion, gray, CL, moist	60 - 80	18-in. penetration
123+87	W Wall	8:00	1.6	0.3	2.1 - 2.8	Silty sand, fine, gray, moist	210	5.4-in. penetration
122+82	E Wall	4:00	1.5	0.3	1.8 - 3.3	Sandy clay, gray, moist, CL (very soft at the back of lagging)	210**	
122+82	W Wall	8:00	1.7	0.3	2.3 - 3.5	Sandy clay, gray, dense, CL	230	1/2-in. penetration
121+77	E Wall	4:00	1.4	0.3	1.7 - 3.0	Silty sand, fine, gray	220**	Previously sampled hole, dry
121+77	W Wall	8:00	1.55	0.3	1.85 - 3.0	Silty sand, fine, gray	170**	Previously sampled hole, dry
120+20	E Wall	4:00	1.5	0.3	1.8 - 3.0	Silty sand, fine, gray	140**	Previously sampled hole, wet
120+20	W Wall	8:00	1.5	0.3	1.8 - 3.0	Silty sand, fine, gray	165**	Previously sampled hole, wet

(Continued)

Table 11 (Concluded)

Station	Location		Concrete Thickness† ft	Lagging Thickness ft	Pipe Sample ft	Soil Description and Remarks	Cone Penetration Data (30 deg cone, 0.5 in.)	
	Tunnel Side	Clock Hr North					Cone Reading psi	Remarks
119+67	E Wall	4:00	1.6	0.3	1.9 - 2.5	Silty sand, fine, gray	160**	Previously sampled hole, wet
119+67	W Wall	8:00	1.4	0.3	1.7 - 2.5	Silty sand, fine, gray, wet, no cohesion, dense	190**	Previously sampled hole, wet
118+00	E Wall	4:00	1.6	0.3	1.9 - 3.0	Silty sand same as above	185**	Previously sampled hole, filled in and wet
118+00	W Wall	8:00	1.6	0.3	1.9 - 2.8	Silty sand, same as above, Rib at 1.4 ft	140**	Previously sampled hole, filled in and wet
116+50	E Wall	3:45	1.5	0.3	1.8 - 2.5	Sandy clay, clay (CL) is firm, moist with 5 percent fine gravel	160**	Previously sampled hole, water at 0.8 ft depth
116+50	W Wall	8:15	1.6	0.3	1.9 - 2.6	Sandy clay, same as above	150**	Pushed in previously sampled hole, wet
115+45	E Wall	3:00	1.5	0.3	1.8 - 2.5	Silty sand, fine, gray, dense, little cohesion, 5 percent fine gravel, dry, dewatered	-	Not tested
115+45	W Wall	9:00	1.65	0.3	1.95 - 2.60	Silty sand, fine, gray, dense, dry	-	Not tested
113+25	E Wall	4:00	1.4	0.3	1.9 - 2.8	Silty sand to sandy silt, gray moist, moderate cohesion	180**	
113+25	W Wall	8:00	1.4	0.3	1.9 - 2.5	Silty sand to sandy silt, gray, moist, moderate cohesion	140**	

† Holes not always perpendicular to wall and concrete thickness may not be minimum value

* Used 2-in.-diameter hand auger

** Maximum force possible by hand pushing, no apparent penetration

Table 12

Construction Joint Conditions, Distressed Area 3

<u>Station</u>	<u>Remarks</u>
114+42	Sandy silt inclusion behind 4-in. loose core piece, waterstop, piece of wet, partially decayed wood, lower east quarter; waterstop and wood higher up in joint on west side
113+37	Waterstop and piece of wood in keyway, east and west sides of tunnel
112+32	Piece of waterstop visible where fractured concrete had fallen out of crown
111+27	Waterstop and wood in keyway, west side, lower quarter, joint leaking water, "epoxy" written on wall

Table

BORING NO.	SAM. NO.	Aver. DEPTH OF SAMPLE	LABORATORY CLASSIFICATION	MECHANICAL ANALYSIS				ATTERBERG LIMITS		SPECIFIC GRAVITY G	NAT WATER CONT %	NATURAL DRY DENSITY LBS/CU FT	COMPACTION DATA	
				GRAVEL %	SAND %	FINES %	D ₁₀	LL	PL				OPT WATER %	MAX DRY DENSITY LBS/CU
WES-1	32	53.8	Sandy Clay CL	3	15	82		27	15	2.74				
	34	60.3	Silty SandSP-SM	0	93	7						131.4*		
	38	64.9	Sand SP	0	98	2						107.6*		
WES-3	6	37.1	Silty Clay CH								20.6	110.6		
	9	41.6	Silty Clay CL					22	11	2.76	14.6	124.7		
	12	46.6	Silty Clay CL					24	13	2.70	18.8	108.3		
	16	52.4	Grav.Silty Sand											
			SC-SM	14	48	38		20	14		11.4	127.7		
	18	55.3	Sandy Clay CL					25	13	2.74	12.4	125.0		
	19	56.0	Silty Clay CL					26	14	2.74	16.7	117.7		
	19	56.0	" " "								11.9	125.9		
	23	62.0	Silty Clay CL	0	3	97					14.9	123.0		
	24	63.0	SiltySandSP-SM								15.2	118.5		
	31	75.2	Sandy Silt ML	0	50	50						117.0*		
WES-4	4	4.8	Silty Clay CL					30	18		26.1	101.3		
	8	10.7	Silty Clay CL					32	18	2.74	29.3	95.7		
	12	21.4	Silty Clay CL					29	16	2.76	14.0	121.4		
	13	25.8	Silty Clay CL					31	16	2.75	15.5	122.9		
	17	36.6	Silty Clay CL					24	14	2.75	12.4	131.3		
	20	45.2	Clayey Sand SC							2.72		129.6*		
	22	47.8	Sand w/Grav.SP	6	93	1		14	9		9.2	139.5		
	24	50.6	Sandy Clay CL	4	13	83		28	12	2.74	16.5	126.2		
	24	50.6	" " "								13.9	121.2		
	25	52.5	Sandy Clay CL	0	18	82		24	12	2.75**	10.5	132.6		
	27	55.5	Silty Clay CL					24	13	2.73	12.0	142.2		
	30	64.5	Silt ML	0	3	97					18.3	112.6		
	31	66.6	Sandy Silt ML	0	38	62					19.2	114.0		
	32	69.5	Sandy Silt ML	0	13	87						120.6*		
WES-9	3	51.8	Silty ClayCL-ML	0	24	76		16	10					
	4	60.8	Silt ML	0	16	84		17	14					
	6	64.3	Silty Sand SM	0	80	20		NP						
WES-10	2	48.8	Clayey Silt ML	0	34	66		13	10					
	5	57.8	Silty ClayCL-ML	0	18	82		17	12					
	7	63.8	Silty ClayCL-ML	0	22	78		16	12					

SECRET

[illegible]

DIRECT SHEAR S - CONSOLIDATED DRAINED
CONSOLIDATED UNDRAINED R - CONSOLIDATED UNDRAINED

3

Table 14
List of Samples and Results of Special Piping Tests

Test No.	Sample		Saturation		Piping Water Pressure, psi		Cumulative Piping Time min	Material					
	Number	Depth ft	Time hr	Pressure psi	Initial	Final		Classification	Density pcf	Dry Wt g	Wt Piped g	% Piped	
1	WES-1-38-1*	63.9-64.9	3	20	1/2	3/4	5	7	Sand (SP) Gray	107.56	2100	67	3.12
2	WES-1-38-2*	64.9-65.9	3	90	1/2	2	3	53	Sand (SP) Gray	--	--	--	--
3	WES-4-20*	44.7-45.8	5	19.33	1/2	2	2	1	Clayey Fine Sand (SC)	129.60	5808	--	--
4	WES-4-20 [†]	44.7-45.8	5	1.25	1/4	2	8	70	Clayey Fine Sand (SC)	129.60	"	--	--
5	WES-4-32	69.0-70.0	3	19	3-1/4	3	5	55	Sandy Silt (ML)	120.60	2336	370	15.84
6	WES-1-34	59.5-61.1	5	41	2-1/2	3	8	55	Soft Silty Sand (SM)	131.36	8830	248	2.81
7	WES-3-31	74.4-76.0	5	98	1/2	5	9	35	Sandy Silt (ML)	117.00	8921	94	1.05
8	WES-5-10	65.0-66.0	5	114	1	1-3/4	8	55	Clay and Silt (CL-ML)	--	5328	21	0.39

* Slot cut longitudinally.

[†] Longitudinal slot plugged and circular slots cut in a second test.

-- No material piped out of slot.

Table 15
Summary of K_o Triaxial Compression Tests

Boring No.	Sample No.	Depth, ft	Soil Class.	Water Content, %	Wet Unit Weight, pcf	σ'_3 End of Consol., tsf	K_o	E_1 Modulus, psi	c Cohesion, tsf	ϕ' Degrees
WES-3	19	55.6/56.4	CL	11.9	141.4	0.83	0.40	3470	0	33.9
WES-3	24	62.6/63.4	SP&ML	15.4	135.9	1.03	0.45	4550	0	35.9
WES-4	24	50/51.1	CL	13.9	137.4	1.30	0.42	1820	0.06	31.7
WES-4	30	64/65	ML	18.3	132.4	1.50	0.42	3900	0	36.4

Table 16

Modulus and Shear Strength Data, Midland Nuclear Power Station, Michigan
(from Midland Final Safety Analysis Report, Vol 4, Revision 21, 5/79)

Depth Ft	Soil Description	w %	γ_d/γ_m pcf	G_s	Consol σ_3 tsf	Strain Rate %/Hr	E_i (1) psi	c' tsf	ϕ' deg
17.0	Gray sandy silt	8.1	136/147	--	0.5	0.69	3470		
--	and silty clay	13.4	125/142	--	1.0	0.16	1736		
14.5	with some sand	7.3	139/149	2.62	2.0	0.77	6940		
--	and gravel	9.6	135/148	2.71	0.5	0.74	2080	0.3	32
17.5	same as above	8.9	136/148	--	0.5	0.42	2080		
--		10.7	131/145	2.70	1.0	0.17	2290		
44.5		7.3	140/150	--	2.0	0.20	4650	0.3	35

Table 17
Summary of Concrete Information from Various Sources

Date of Placing	Location	Mix- ture Re- port No.	Mixture Proportions					Time of Place- ment hr:min	Approx Rate of Placing, cu yd/hr	Cylinder Test Report No.	Compressive Strength psi	Remarks from Inspector Reports
			Coarse Aggre- gate lb	Fine Aggre- gate lb	Type I Cement lb	Water gal	Admix- ture oz	Slump in.				
17 Apr 72	133+32-132+27	614	1850	1540	517	23	3.2	6	5:25	50	627	14 3450 Small honeycombs on springing line east and west, Sta 133+32
21 Apr 72	132+27-131+22	NA*	--	--	--	--	--	5-1/2	4:15	64	627	7 3150 (Inspectors report shows concrete was placed on 20 Apr 72 whereas the cylinder test report shows it being placed on 21 Apr 72)
24 Apr 72	131+22-130+17	NA	--	--	--	--	--	5-1/2	3:45	71	632	7 2210 Rock pocket, east side Sta 130+19 three cold joints east and west-sides, Sta 130+17 to 130+35
25 Apr 72	130+17-129+12	627	1850	1540	517	21	3.2	6	3:30	77	632	7 3380 Small rock pockets in top 1/4 Sta 130+17; cold joint in lower 1/4 east Sta 130+10
26 Apr 72	129+12-128+07	NA	--	--	--	--	--	5	**	**	644	7 3890 Small honeycombed spots at bulk-head, Sta 128+07
27 Apr 72	128+07-127+02	632	1850	1540	517	23	3.2	5-1/2	3:25	78	644	7 4000
28 Apr 72	127+02-125+97	NA	--	--	--	--	--	4-1/2	**	**	644	7 3910 Section appeared okay. (No in-spectors report for the placement)
29 Apr 72	125+97-124+92	NA	--	--	--	--	--	6	2:50	99	644	9 4260 Stone pockets: 1 ft by 4 ft, east 1/4, Sta 125+80 and 6 in. by 5 ft, west 1/4, Sta 125+45
1 May 72	124+92-123+87	644	1850	1540	517	22	3.2	5	5:20	50	659	14 3930 "Y" type cold joint in invert, Sta 124+30; 13 ft long cold joint westside Sta 124+30
2 May 72	123+87-122+82	NA	--	--	--	--	--	5-1/2	2:45	98	659	7 4070 Rock seam, 14 ft long, lower 1/4 west, Sta 123+87 to 123+73; 2 ft diam pocket, Sta 123+87, east springline
4 May 72	122+82-121+77	NA	--	--	--	--	--	6	3:00	90	659	7 2820
5 May 72	121+77-120+72	NA	--	--	--	--	--	5	3:30	77	659	7 3450
9 May 72	--	659	1850	1540	517	22	3.2	--	--	--	--	-- 72 (No placement recorded on 9 May 72)

(Continued)

* Not available.
** Not given.

Table 17 (Continued)

Date of Placing	Location	Mix- ture Re- port No.	Mixture Proportions							Time of Place- ment hr:min	Approx Rate of Placing, cu yd/hr	Cylinder Test Report No.	Compressive Strength Age, days	Remarks from Inspector Reports	
			Coarse Aggre- gate lb	Fine Aggre- gate lb	Type I Cement lb	Water gal	Admix- ture oz	Slump in.	Cyl in.						
30 May 72	120+22-119+67	NA	--	--	--	--	--	--	5	3:20	80	710	7	3630	Small amount of cold joint, east and west, L/Q
1 Jun 72	119+67-118+62	NA	--	--	--	--	--	--	4-1/2	4:30	60	710	7	3640	2 ft by 4 ft honeycomb L/Q, east side, Sta 118+61
2 Jun 72	118+62-117+57	NA	--	--	--	--	--	--	5	3:30	76	710	7	3450	2 ft by 1 ft trace of clay in crown at Sta 117+22
3 Jun 72	117+57-116+52	NA	--	--	--	--	--	--	5	2:40	100	710	13	3890	Small rock pockets at start of pour and small cold joints
5 Jun 72	116+52-115+47	710	1850	1540	517	23	--	3.2	5-1/2	4:00	67	720	7	3640	Several cold joints both east and west side, approx 1/2 in. wide
6 Jun 72	115+47-114+42	NA	--	--	--	--	--	--	5-1/2	3:45	70	720	7	3060	4 small cold joints, east and west sides
7 Jun 72	114+42-113+37	NA	--	--	--	--	--	--	6	3:00	87	720	7	2920	Rock pockets, east and west, springing live, Sta 112+32
8 Jun 72	113+37-112+32	NA	--	--	--	--	--	--	5	3:10	**	720	7	3360	3 ft by 3 ft honeycomb, east and west sides, Sta 111+27 at springing line
9 Jun 72	112+32-111+27	NA	--	--	--	--	--	--	6	3:40	72	720	7	3420	
10 Jun 72	111+27-110+22	NA	--	--	--	--	--	--	6	2:20	112	720	13	4170	

** Not given.

Table 18

Summary of Schmidt Hammer Rebound
Number Measurements on Drilled Cores

Station	Tunnel Side	Clock hr North	Rebound Number			Compressive Strength of Core psi
			Tunnel Location	Core End	Core Side	
133+13	Crown	12:00	--	48	41	7260
	Invert	6:00	--	--	34	--
132+50	Invert	6:00	33	29	37	7510
	W. Wall	9:00	33	41	35	--
	Crown	12:00	26	41	33	6690
131+84	Crown	Not known	--	33	31	6620
	Crown	Not known	--	36	37	7220
131+60	Crown	Not known	--	34	34	7790
	Crown	Not known	--	36	32	7590
127+50	Invert	6:00	27	38	33	7870
	W. Wall	9:00	42	36	35	7640
	Crown	12:00	36	34	25	6690
119+15	E. Wall	2:00	38	42	37	--
	E. Wall	4:00	38	38	33	7060
118+35	E. Wall	1:00	25	45	40	6250
117+70	E. Wall	5:00	38	42	37	6370
117+25	E. Wall	3:00	41	46	34	6280
	Invert	6:00	35	34	39	6440
	Crown	12:00	48	41	39	7060
115+47	W. Wall	8:00	--	--	--	--
114+70	Invert	6:00	31	--	--	--
	Invert	6:30	31	30	43	4440
	W. Wall	9:00	42	44	34	6070
	Crown	12:00	40	39	34	5480
113+45	E. Wall	3:00	34	39	35	6740
	Invert	6:00	28	28	34	6400
	W. Wall	7:00	37	--	--	--
	Crown	12:00	40	37	34	5260
112+20	E. Wall	3:00	37	38	38	5560
	Crown	12:00	46	42	38	--
112+18.5	Invert	6:00	31	31	41	6190

Table 19
Summary of Schmidt Hammer Rebound
Number Measurements on In-Place Concrete

<u>105-ft Placement Station Numbers</u>	<u>Location of Readings</u>	<u>Average Rebound Number for Specific Wall Locations</u>			
		<u>Crown</u>	<u>East Wall</u>	<u>Invert</u>	<u>West Wall</u>
134+37 - 133+32	133+50	42	39	32	44
133+32 - 132+27	132+50	26	32	33	33
132+27 - 131+22	--	--	--	--	--
131+22 - 130+17	131+00	45	43	22	39
130+17 - 129+12	130+00	38	34	19	45
129+12 - 128+07	128+50	38	42	19	38
128+07 - 127+02	127+50	36	43	27	42
127+02 - 125+97	126+25	35	43	16	42
125+97 - 124+92	--	--	--	--	--
124+92 - 123+87	124+00	37	39	41	39
123+87 - 122+82	--	--	--	--	--
122+82 - 121+77	--	--	--	--	--
121+77 - 120+72	121+00	33	37	26	35
120+72 - 119+67	--	--	--	--	--
119+67 - 118+62	119+15	43	38	25	43
118+62 - 117+57	118+55	41	35	25	36
	118+35	32	25	25	41
	118+00	41	39	23	40
	117+70	41	38	23	40
117+57 - 116+52	117+25	48	41	35	42
116+52 - 115+47	--	--	--	--	--
115+47 - 114+42	115+00	46	33	26	38
	114+75	42	40	21	43
	114+70	40	43	31	42
	114+50	41	35	26	32
114+42 - 113+37	114+25	46	35	37	42
	114+00	42	41	39	42
	113+75	38	38	33	37
	113+50	42	36	32	41
	113+45	40	34	28	37

Table 19 (concluded)

105-ft Placement Station Numbers	Location of Readings	Average Rebound Number for Specific Wall Locations			
		Crown	East Wall	Invert	West Wall
113+37 - 112+32	113+25	42	44	20	40
	113+00	39	41	20	40
	112+75	37	40	39	37
	112+50	43	42	24	39
112+32 - 111+27	112+20	46	37	31	35
	112+15	43	32	32	37
	112+00	42	26	27	40
	111+75	42	39	33	34
	111+50	43	38	29	41
111+27 - 110+22	111+25	42	25	18	37
	111+00	38	32	26	41

Table 20
Summary of Concrete Thicknesses from Drilled
Core Measurements

Station	Location		Concrete Thickness ft
	Tunnel Side	Clock hr North	
133+13	Invert	6:00	1.2
	E. Wall	3:00	1.2
	Crown	12:00	2.0
132+50	Invert	6:00	1.35
	W. Wall	9:00	1.5
	Crown	12:00	1.5
131+84	Crown	Not known	1.65
	Crown	Not known	1.65
131+60 (Approx)	Large Piece	--	1.1*
	Assumed to be from the Crown	--	1.1
127+50	Invert	6:00	1.35
	W. Wall	9:00	1.4
	Crown	12:00	1.7
119+15	E. Wall	4:00	1.45
	E. Wall	2:00	1.35
118+35	E. Wall	1:00	1.35
117+70	E. Wall	5:00	1.6
117+25	Invert	6:00	1.9
	E. Wall	3:00	1.45
	Crown	12:00	1.1
115+47	W. Wall	8:00	1.5
114+70	Invert	6:00	1.6
	Invert	6:30	1.6
	W. Wall	9:00	1.3
	Crown	12:00	1.65
113+45	Invert	6:00	1.65
	W. Wall	7:00	1.6
	E. Wall	3:00	1.6
	Crown	12:00	1.15
112+20	E. Wall	3:00	1.6
	Crown	12:00	1.7
112+18.5	Invert	6:00	1.35

*Not actual liner thickness

Table 21
Summary of Physical Test Data from Drilled Concrete Cores

Station	Tunnel Side	Clock hr North	Compressive Strength psi	Modulus of Elasticity 10 ⁶ psi	Poisson's Ratio
133+13	E. Wall	3:00	--	--	--
	Invert	6:00	--	--	--
	Crown	12:00	7260	--	--
132+50	Invert	6:00	7510	5.05	0.20
	W. Wall	9:00	--	--	--
	Crown	12:00	6690	4.80	0.19
131+84	Crown	Not known		--	--
	Crown	Not known		--	--
131+60	Crown	--	7790	5.90	0.29
	(Assumed)	--	7590	5.05	0.20
127+50	Invert	6:00	7870	4.05	0.15
	W. Wall	9:00	7640	6.50	0.24
	Crown	12:00	6690	5.15	0.28
119+15	E. Wall	2:00	--	--	--
	E. Wall	4:00	7060	--	--
118+35	E. Wall	1:00	6250	4.80	0.20
117+70	E. Wall	5:00	6370	4.75	0.20
117+25	E. Wall	3:00	6280	4.75	0.16
	Invert	6:00	7060	4.75	0.20
	Crown	12:00	6440	4.85	0.19
115+47	W. Wall	8:00	--	--	--
114+70	Invert	6:00	--	--	--
	Invert	6:30	4440	--	--
	W. Wall	9:00	6070	--	--
	Crown	12:00	5480	--	--
113+45	E. Wall	3:00	6740	5.00	0.22
	Invert	6:00	6400	4.70	0.16
	W. Wall	7:00	--	--	--
	Crown	12:00	5260	4.40	0.19
112+20	E. Wall	3:00	5560	--	--
	Crown	12:00	--	--	--
112+18.5	Invert	6:00	6190	--	--

APPENDIX A

BORING LOGS

BORING LOG **FIELD DATA**

Project <u>DETROIT SEWER</u> Date _____										
Location <u>STA 116 + 42, 20' E & SEWER</u> Job No. _____										
Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. <u>WES-1</u>										
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Blows	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
		0.0						Fish tail		Cleanest Clay fill.
			4.0							
		4.0		5.8	6.3				1	10 blms/ft. Brown soft soil with NL
				6.3	6.8				4	grains to brown-gray soft silty clay
1	3/8/80		7.2	6.8	7.3	7.0	7.3		6	CL at 7.2' Oxidized (soil zone)
										Varved clay (lake deposit)
				7.3	8.5			Fish tail		Clean
2		7.2		8.5	9.0	8.5	8.9		3	13 blms/ft Drive 1.5 sample 1.5.
				9.0	9.5				4	Brown-gray mottled soft clay w/ soft stringers.
3				9.5	10.0	9.3	9.7		9	Oxidized brown soil CL-CH No grain.
										Varved
				10.0	11.5			Fish tail		Clean
4				11.5	12.0	11.5	11.9		3	10 blms/ft Soft gray mottled
				12.0	12.5				4	clay CL-CH, silty stringers No grain
5				12.5	13.0	12.3	12.7		6	Varved 1/4" - 3/8" intervals

Sheet 1 of 1 Sheets

BORING LOG FIELD DATA

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. WES-1

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS	
		FROM	TO	FROM	TO	FROM	TO			
			14.0	13.0	14.5			Fish tail	Clean sand	
		14.0		14.6	15.4			Spore	8 bl/ft Drive 1.5 Sand 1.5	
				15.4	15.6				Soft silty clay w/ 5% sand gravel (CL-GH)	
6				15.6	16.4	15.4	15.8		Gray, sticky 0.1' sand layer at 14.8 to 14.9, (SW) w/ gravel, silt	
								Fish tail	Clean sand	
			17.0	16.1	17.5					
		17.0	17.0	17.5	18.0			Spore	28 bl/ft Sandy gravelly clay (CL)	
				18.0	18.5				Very sandy. Good cohesion. Med hdw/	
7				18.5	19.0	18.4	18.8		gravel to 1/2" Gray. Soft silty sand	
									at 17.6-17.8,	
									Lost circulation @ 14 ft. Ream hole and	
									about 6" PVC plastic casing to 17.5 ft.	
									Casing removed to ground.	
									Clean sand	
				19.0	20.0					

BORING LOG FIELD DATA											
Project		Site		Date		Job No.		Boring No.		WE S-1	
Location		Inspector		Operator		Surface E1					
Drill Rig											
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER			CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO				
8				20.0	20.5	20.0	20.5	Spoon	8		36 bl/ft Sand as above. Silty, green, silty clay (CL) med. kid.
9				20.5	21.0	20.0	21.2		16		Greenish silty clay (CL) med. kid.
				21.0	21.5	20.0	21.2		20		Greenish silty clay (CL) med. kid.
				21.5	23.0						Very thin silt layers at lower intervals (various?)
10	5/8			23.0	23.5	23.2	23.6	Spoon	14		55 bl/ft Drive 1.5 sample 1.1
11				23.5	24.0				22		23.0 - 24.2 - Silty fine sand, greenish.
		24.2		24.0	24.5	23.8	24.2		33		24.2 - 24.5. 11.4 gray, clay (CL) as above. 24.2 - sand / Cleanest
12		25.0		25.6	26.1	25.7	26.0	Spoon	27		67 bl/ft - SAND - well sorted, fine to med. sand
		25.0		26.1	26.6				35		272 SAND, NO GRAVEL, with numerous
13				26.6	27.1	26.6	27.1		32		INTERBEDDED CLAY LAMINAE (SP)
				27.1	28.0			Fuller			CLEANOUT

BORING LOG **FIELD DATA**

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El. _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER		CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
14			27.5	28.0	28.5	28.0	28.4		12	Drive 1.5' sample 1.5' Firm plastic
		27.5		28.5	29.0				20	gray uniform clay (CL-CH) no sand
15				29.0	29.5	28.9	29.3		28	or gravel like that at 29.2-29.5
			30.0	29.5	30.4			Fishland		
16		30.0		30.4	30.9	30.4	30.8	Spoon	42	83 1/4" Gravelly sand, graded
				30.9	31.4				56	fine to co. to gravel (SW), little coarse sand, drier.
17			31.8	31.4	31.9	31.2	31.6		27	31.8-31.9 - gray firm clay (CL)
				31.9	33.2			Fishland		Cleanout
18		31.8		33.2	33.7	33.2	33.9	Spoon	14	50 1/4" Gray firm silty clay (CL)
				33.7	34.2				24	no sand or gravel. Drive 1.5 sample
19				34.2	34.7	33.9	34.6		26	1.5
				34.7	36.4					

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. WES-1

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER		CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
20				36.8	36.6	36.1	36.5	Spoon	8	36 61/ft Very silty clay (CL), gray uniform firm fine cohesive, some plasticity. Drive 15 sample 15 Sample
21				36.6	37.1				18	remain in one complete length. No gravel
				37.1	37.6	36.9	37.3		18	Clean
								Fistful		
22		38.0		38.7	39.2	38.8	39.4	Spoon	8	28 61/ft Drive 15 near 15.
				39.2	39.7				13	Silty gray clay clay w/ trace small gravel, no sand (CL)
23	5/8			39.7	40.2	39.4	40.2		15	
				40.2	41.1			Fistful		Cleanest
24	5/9			41.1	41.6	41.1	41.7	Spoon 2" O.D.	9	41 blow/ft. Drive 15 sample 15.
25				41.6	42.1	41.7	42.3		18	Remain in one length. Soft to firm, silty clay (CL) no gravel as above.
				42.1	42.6				23	
				42.6	43.4			Fistful		Cleanest

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. WES-1

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	FEET COR.	CLASSIFICATION AND REMARKS	
		FROM	TO	FROM	TO	FROM	TO				
26	5/9		44.2	43.4	43.9	43.9	44.1	STANDARD SPIGON	12	97 blow/ft. 43.4-44.2 silty clay (cl) trace gravel 44.2 - 44.9	
27		44.2		43.9	44.4	44.4	44.7		36	silt (ML) gray #26 - CLAY	
				44.4	44.9	44.9			61		
				44.9	46.0			Clear mud		#27 - silt	
		45.5							162	Content is quartzite	
28		45.5		46.0	46.5	46.1	46.8	3" HURSLER	4/20	Push 3" tube ~ Drive 10' Clayey gravelly med-fine sand. Problem to 3/4" cohesive	
28A				46.5	46.9	46.8	46.9		6/70	sampled 0.85' broke in tube. (SC)	
				46.9	47.4						
29				47.9	47.5	47.4	47.5	3" HURSLER	6/93	Would not push more than 0.1'	
									retrial	Clayey gravelly hd sand, cohesive gravel to 1' diam.	
				0.0	48.5	Reamed hole w/	rock bit	to drive densim bbl.			

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. 4E5-1

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	1/4" pie	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
30				48.5	49.7	48.5	49.6	Denison 661	260	Rotate long bit w/ 5" tube w/ spring steel catcher in end. Rotated slowly Drive 1.2
30A						48.6	49.7		500	Groundwater at bottom. Clayey gravelly hd sand (SC). Sampled 1.2. This is some soft fill in debris at top of steel tube - (Jensen).
										Clearcut grain rounded
				49.7	50.0			Fish tail		
										Gradation change SC to CL - possibly (boiling sample)
31	quote from quality		50.5						5" steel tube	0.2' Fall in. Rotated same scheme as above.
31A	5/9/80			50.0	51.9	50.0	51.8	Denison 661	Jar	Drive 1.9 Sample 1.9 1/4" hd gravelly sandy clay, compact, dense, tight, tight. Sample in good condition. Grains rounded
						51.8	51.9			
				51.9	53.0			Fish tail		Clearcut
32				53.0	54.8	53.0	54.7	Denison 661		0.3' fall in Drive 1.8 Sample 1.8 Rotate
32A						54.7	54.8			as per above. Same method as above. 1/4"

BORING LOG **FIELD DATA**

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. WCS-1

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
				59.8	56.0			Fishtail	Clean
33				56.0	57.9	56.0	57.7	Denison bbl	Driver 1/9 sample 1.8. Same stratum as
33A						57.7	57.8		1st above (CL) abd. granules
				57.9	59.0			Fishtail	Clean
34	5/9	59.5	59.0	61.1	59.0-59.5 (approx)	59.0-59.5 (approx)	59.5-61.1	Denison bbl	Relate as above (approx as above) Drive 2.4
34A		59.5				61.1	61.2		Sample 1.6 Soft at 59.5-60.5
									Soft at 61.0-61.1. Hl gray granules
									clay to 59.5. Solid sand 59.5 to 61.4
									Probably washed over soil sand at 59.5-60.5
									1st sample in sand (SP) uniform redt poorly
									graded qtz sand (beach sand) cohesionless
				61.4	61.5			Fishtail	Clean

WES FORM 819 JAN 74 EDITION OF NOV 1971 MAY BE USED

Sheet 8 of 8 Sheets

BORING LOG FIELD DATA

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	lbs. per ft.	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
	5/10			61.5	61.7			3" Hollow	700	Pushed small hole of hard pipe. No recovery
				61.5	No drive			Denison bit		5" tube w/ catclaw and short bit, rotated. Short bit will not advance
35				61.5	63.9	61.5	61.9	Denison bit		5" tube w/ catclaw w/ long bit. 3 den samples
36						61.9	62.3			of very wet loose cohesionless well sorted
37						62.3	62.5			medium grained sand (SP) [benches]
										Drive 2.4 runs 1.0
38				63.9	64.4	63.9	65.9	3" Hollow	340	Push: 2.1 Run: 2.4 (same fall)
			2.1	64.4	64.9				460	Disregard top 1.5 feet probably disturbed
				64.9	65.4				540	(SP) cohesionless gray uniform fine grained sand
				65.4	65.9				540	
38A				65.9	66.0	65.9	66.0		720	1 in
				66.0	67.9					

BORING LOG **FIELD DATA**

Project _____		Site _____		Date _____	
Location _____		Job No. _____		Boring No. _____	
Drill Rig _____		Inspector _____		Operator _____	
		Surface El _____			

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Blow Count 60.5'	Classification and Remarks
		FROM	TO	FROM	TO	FROM	TO			
37				67.7	68.2			2" O.D. Split Spool	78	145/0.7' Drive 0.7 Sample OK
39				68.2	68.4	68.4	68.4		67	Med. sand (SP) cohesionless as above
								F. Water		Clear
				68.4	70.5					
				70.5	71.0				74	100/0.51 Med. grain SP sand as above
40				71.0	71.1	70.7	71.1		26	
								F. Water		
				71.1	73.8					
				73.5	74.0				47	112/0.75 Med. to fine (SP) sand as above
41				74.0	74.25	73.8	74.2		65	
								F. Water		
				74.3	76.5					
				76.5	77.0					
42				77.0	77.1	76.9	77.1		42	92/0.70 (SP) fine sorted sand as above
				77.1	77.1	76.9	77.1		50	

Sheet 10 of Sheets

BORING LOG **FIELD DATA**

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. WCS-1

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	blows	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				77.2	79.5					
43				79.5	80.0	79.7	80.0	2" O.D. SS	47	97/100 Sand (SP) med. fine 79.5 to 80.0
44				80.0	80.2	80.0	80.2		50	Finer v. fine 80.0 - 80.2
								Fishtail		
				80.2	80.5					
45				83.5	84.0	83.6	84.1	2" Split spn	70	100/100 Sand (SP) fine ground calc. med.
				84.0	84.1				25	[beach sand] as above
								Fist tail		
				85.0	84.1					Clear cut Head at 85' D.H.
										gravelly silty clayey sand
46				86.0	86.1	86.0	86.1		50	v. hd gravelly clayey sand, calc. med.
										(SC)
47	5/10			86.0	88.4	86.0	87.6	Denison 561		5" tube w/ catch, med. bit v. hd sandy gravel
47A						88.3	88.9			clayey clay argillaceous and rounded gravel (60% w. bit) (CL)

Sheet 11 of 11 Sheets

WES FORM 819 EDITION OF NOV 1971 MAY BE USED
 hole grnd
 88.4 - 0.0

BORING LOG FIELD DATA

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Blows	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				40.2	41.9					
				41.9	42.4			2" S.S.	5	25 blows/ft. Gray soft plastic clay
3	5/6			42.4	42.9	42.4	43.0		(11) in	(CL-CH) as above. No sand.
				42.9	43.4				14	Drive 1.5 rev. 1.5' compressed in sample
				43.4	44.5			Flight	?	Cleanout.
										Stratum grades more plastic w/ depth
				44.5	45.0			2" O.D. SS.	31	17 blows/ft. Soft gray plastic clay
4				45.0	45.5	45.0	46.0		7	as above (CH) 1 compressed in sample
				45.5	46.0				10	No sand.
				46.0	47.0					
				47.0	47.5			2" S.S.	7	31 blows/ft. Firm silty granular clay (CL)
5		47.0		47.5	48.0	47.5	48.5		14	CS. sand to pea gravel. Compressed in sample
				48.0	48.5				17	

Sheet 2 of Sheets

BORING LOG **FIELD DATA**

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
				48.5	49.3			Fishtail	Clearcut
				49.3	49.8			2" 0.0 S.S.	39 1/2 ft Drive 1.5' recover Soft to
6	5/6			49.8	50.3	49.8	50.7		firm gravelly sandy silty clay (CL)
				50.3	50.8				CS sand and fine gravel
				50.8	51.5			Fishtail	Clearcut
		51.3							Harder at 51.3 (Uniform gray silt)
			51.7	51.5	52.0			2" S.S.	102 1/2 ft Gravelly sand, gray
		51.7		52.0	52.5				(SW) med. grained, hd. but friable (some
7	5/6			52.5	53.0	52.5	53.0		cohesion) (Uniform gray silt 51.5 to 51.7)
									Sample 85 moist, not wet
			53.5	53.0	54.0			Fishtail	Clearcut
		53.5		54.0	54.5			2" S.S.	200 blow/ft U. hd. silty gravelly
8				54.5	55.0	54.8	55.3		clay (CL) 5-10% gravel (small)
				55.0	55.5				

BORING LOG **FIELD DATA**

Project _____		Site _____		Date _____	
Location _____		Job No. _____		Boring No. _____	
Drill Rig _____		Inspector _____		Operator _____	
Surface El _____					

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
				55.5	56.7			Fishtail	Claymud
				55.9	56.2			2" O.D. S.S.	208 blow/ft V. bl. gray silty
9				56.2	56.7	55.7	56.2		clay 41 above (CL) dk gray.
				56.7	57.0				
				57.0	58.0			Fishtail	Claymud
10		58.4	58.0	58.5	58.8	58.6	58.8	2" O.D. S.S.	Drive 1.0 270 blow/ft
11		58.4	58.5	59.0	59.8	58.6	58.8		58.0 - 58.6 - hd clay, silty (CL) as above
				59.0	59.8			Fishtail	58.6 - 59.0 Fine, sorted gte sand, friable, dense (SP) dk gray, some cohesion - One large cobble separates the two strata at 58.6'
12				59.5	60.0	59.5	60.1	2" O.D. S.S.	Drive 0.9 (bottom 0.4' = 250 blow/ft)
				60.0	60.4				Densigay trace (cohesionless) sand (SP) as above

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER		CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				60.9	61.5			Fishtail		
13	5/6			61.5	62.0	61.5	61.9	2" S.S.	49	75/0.3' : 250 blows/ft. Dring. 0.8.
				62.0	62.3				75	Uniform gray silt (ML) [fine texture in bank sand stratum], silt from 61.5 to 62.0
										Sand, fine (SP) 62.0 to 62.3, Sample 13
										is silt (ML). (Graduated fining.
				62.3	63.5					Clearcut
14				63.5	63.9	63.5	63.6	2" S.S.	100	Drive 0.4' (100 blows/ft. 1) : 250 blows/ft.
										Uniform gray well sorted fine gr. sand (SP)
										as above. Drive but sedimentation
				63.9	64.5			Fishtail		Clearcut
				64.5	64.9			2" O.I. SS	100 rebar	Drive 0.4' 110 sample

٧٥٠٠٠

BORING LOG
FIELD DATA

Project _____		Site _____		Date _____					
Location _____		Job No. _____		Boring No. _____					
Drill Rig _____		Inspector _____		Operator _____					
Surface El _____		Surface El _____		Surface El _____					
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE	TYPE OF SAMPLER	Blows / <u>CONT</u>	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO				
15	5/7			64.9	65.5	—	FISHTAIL	—	CLEANOUT
				65.5	65.9	65.5	STANDARD SPLITSPOON	10/	SAND - Uniform, grey, well sorted, dr fine gr. SAND, cohesionless - DRILL
				65.9	66.5	—	FISHTAIL	—	CLEANOUT
16	5/7			66.5	66.95	66.5	STANDARD SPLITSPOON	100	SAND - SEE ABOVE - DRIVE 0.45"
				66.95	68.0	—	FISHTAIL	—	CLEANOUT
17	5/7			68.0	68.5	68.0	STANDARD SPLITSPOON	47	100/0.25 - 400 blows / ft Sand w above
				68.5	68.75	—	FISHTAIL	—	CLEANOUT
				68.75	68.8	—	FISHTAIL	—	CLEANOUT
				68.8	68.8	—	FISHTAIL	—	CLEANOUT

Sheet 6 of Sheets

FORM 819 EDITION OF NOV 1971 MAY BE USED

BORING LOG **FIELD DATA**

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Blows	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
18	5/7/70			68.8	69.3				53	100/0.3' V. fine sorted glz sand (SP)
				69.3	69.6	69.2	69.5		100	
				69.6	71.0					
19				71.0	71.5	71.2	71.5	2" O.D. SS	100	100/0.5' - 200 blow/ft Fine well sorted glz sand (SP) as above
				71.5	72.5					Clearcut
20				72.5	73.0	72.8	72.9	2" O.D. SS	102	100/0.5' - 200 blow/ft Fine to v. fine sand SP as above
										Clearcut
21				73.0	74.5					
				74.5	74.9	74.7	74.8	2" O.D. SS	110	110/0.9 0.1' actual SP fine sand as above
				74.9	76.0					Clearcut

Sheet 7 of Sheets

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	B.O.W.S	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
22				76.0	76.5	76.3	76.5	2" D.D. Split Sp.	90	115 Hm/10.6' (SP) fine sand w/ll
				76.5	76.6				25	sorted as above
				76.6	78.2					Cleanest
				78.2	78.7			5.5	90	140/11.1' No sample
				78.7	78.8				50	
				78.8	79.5			Further		Cleanest
23				79.5	80.0	79.6	79.9	2" D.D. S.S.	105	105/0.5' 210 Hm/14' Fine
				80.0	81.5				75	small (SP) section
				81.5	81.85				110	110/0.35 Limestone No sample
				81.85	85.0					Cleanest

BORING LOG FIELD DATA											
Project		Site				Date					
Location		Job No.									
Drill Rig		Inspector				Operator		Surface Elevation		Boring No.	
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER			CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO				
24	5/7/80			85.4	85.6			2" ID Split Spun	44		16.0 bl./ft. v. fine sand (SP) as above
				85.6	86.1	85.5	86.1		80		and silt (ML), uniform. Grades finer
											and coarse granularly, all part of same
											stratum. Coarsely nodular texture
											silt and sand size.
				86.5	87.0			Flight			Clean out
		86.5		87.0	87.5			2" ID S.S.	75		60/0.25' fine sand w/ gravel
25				87.5	87.75	87.2	87.7		60		to 1/4" (SM) gray, dense. Med to coarse
											Butterish sand and gravel?
				88.4	88.5						Clean
		88.4		88.5	89.0				74		126/0.6 Silt, gravelly sand, compact
26				89.0	89.1	88.6	89.0		50		and cohesion (SC-SM). Probably unconsolidated
											w/ till cemented below
				90.1	90.0						

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____
 Boring No. _____

[illegible]

BORING LOG FIELD DATA

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El. 609.8 Boring No. WES-3

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
		0.0		0.0	10.1	-	-	Fish tail	Fish tailed, cleaned to 10.1' through surface debris and recent fill.
				10.1	12.5			5" Hovorker	Drive 2.4 No sample, near hole in old landfill (garbage) back casing. Drive 8' steel casing to 8.4'
				12.5	29.0				Land fill, loose, unsorted refuse.
1	4/29	28.7		29.0	29.2	29.0	29.2	5" Hovorker	Drive 0.2 to natural. Clayey, gravelly sand (SC), dk gray, soft, sticky. (10' - 12' rounded pebbles, cobbles, to 2" diam.)
				29.2	30.0			Fish tail	Cleanout. Pulled casing; rock bit to 30.04 (8'). Drive 30' steel 8" casing.
2	4/30/6			29.6	30.1	29.6	30.0	5" Hovorker	Drive 1.4, no record. (filled hole). No split stem in the entire observation.
				30.1	31.6				Sandy, gravelly clay, mud stiff. Gravel 5' to 1/16" - 1/4" diam rounded pebbles, dk gray (CL)

BORING LOG FIELD DATA		Project _____ Site _____ Date _____				
		Location _____ Job No. _____				
		Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. <u>WES-3</u>				
SAMPLE NUMBER	DATE TAKEN	STRATUM	DRIVE	SAMPLE	TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM TO	FROM TO	FROM TO		
			31.0 31.5	-	Fistail	Clean cut
<u>3</u>			31.5 32.0	31.7 31.9	5" Horseshoe	Used smooth tube (swedge connected), Drive W.P.
			32.0 32.4			Recv. 0.5 gal. or so. Gravelly clay (CL).
						med. stiff. More plastic toward bottom
			32.4 33.0		Fistail	Clean cut / Gravelly - less sandy (grit) than 30w/53
			33.0 35.4		Demon 44.5"	0.1' Stickup. Lost sample. Drive with 6" carbide bit below tube. Will retrieve w/ short bit.
<u>1</u>			33.0 35.8	33.9 33.9	Demon bbl 5" Tube	Rubb, 2.1 Drive 2.8. Gravelly, gritty clay
<u>4A</u>				33.9 34.0		dlt gray med silt (CL) to 34.6, then plastic
<u>5</u>		34.6		34.0 35.0		non-gritty clay (CU) below 34.6, dlt gray, med wd,
<u>5A</u>		34.6		35.0 35.1	JAR	very little gravel (<5%) [Note: Samples 4 and 5 were recovered and are probably disturbed!]
			35.8 36.5	-	Fistail	Clean cut

FORM 819
JAN 74
EDITION OF NOV 1971 MAY BE USED
Sheet 2 of 2 Sheets

BORING LOG **FIELD DATA**

Project _____ Date _____									
Location _____ Job No. _____									
Drill Rig _____ Inspector _____ Operator _____ Surface El. <u>509.6</u> Boring No. <u>WES-3</u>									
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
6				36.5	38.7	36.6	37.5	Denism bbl 5"	Tube Rotate carbide bit above tube Drive 2.2
6A						37.5	37.6		Jar Run 2.1 - dk gray fat clay (CH) med
7						37.6	38.6		bd. very little gravel (8.1%). Uniform color
7A						38.6	38.7		Jar another thrust. Samples in very good conditions.
				38.7	39.9	-	-	Fishtail	Clearcut.
8				40.3	39.9	39.9	40.0	Denism bbl	Rotated samess above Drive 2.3 sample 2.3
8A		40.3				40.0	40.1		JAR 39.9-40.3 CH as above. 40.3-42.2
9						40.1	42.1		(CL) silty clay. Samples in good condition
9A						42.1	42.2		JAR except 39.9-40.3, which is somewhat disturbed.
									soft. Little or no gravel. Laminar and
				42.2	43.0	-	-	Fishtail	Clearcut. Disturbed, as in turbulent sediment conditions (see section 7)
10				43.0	45.9	43.0	44.1	Denism bbl	Rotate as above. Drive 2.9, sample 2.8
10A						44.1	45.0		Sticky clay cl. ch 57% small grains, 6% gravel.
11						45.0	45.5		1 1/2" diam

Sheet 3 of _____ Sheets

BORING LOG FIELD DATA

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER			CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO				
				45.4	46.0						Clear-cut
12				46.0	48.4	46.0	47.1	Denison bbl	Tube		Drive 2.4. River. S Rotated as above
12A						47.1	47.2		Jar		46.8-47.0 Soft fine sand SP. Rest of
13						47.2	47.8		Tube		sample is med. bl. silty dk grey clay w/
13A						47.8	47.8		Jar		50% gravel to 1/2" diam. (CL-CM)
				48.4	49.4			Fishtail			Clear-cut
14		50.4	49.4	51.7	49.4	49.4	50.7	Denison bbl			Drive 2.3 Pump. Rotated as above
14A						50.7	50.8				49.4-50.4 CL-CM med. bl. silt clay.
15						50.8	51.2				50.4-51.4 Silty - clayey gravelly
15A						51.2	51.4				sand (SM-SC) w/ 15-20% gravel to 1"
											rounded pebbles of igneous rock. Very sorted - (extremely)
											Top 0.4' of #14 disturbed - #15 broke
											short to 0.5' length. CLAY - SAND
											Consolid sharp horizontal

CLAY
10.5

CLAY
10.5

CLAY
10.5

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
16				51.7	52.0				Cleaned
16.1									
16.1	16			52.0	54.1	52.0	52.9	Densim bbl	Drive 2.1 Rev. 1.3 R-1000 no. 1000
16A	16.1					52.0	53.0		gravelly clayey fine sand (SC-SH) 15-
17	17					53.2	53.7		20% gravel to 1 1/2" dia. Uniform silt (ML)
17.1	17.1								light gray, fine 52.9-53.2, sharp
									contact w/ sand above & below, stratified, w/ some clay laminae
									no gravel, no sand, H 17 is sand, H 16A
									is silt, H 16A sand w/ silt on bottom.
		54.5		54.1	55.0				Cleaned
5/18	18	54.5		55.0	57.4	55.0	55.5	Densim bbl	Rotate as above Drive 2.9 Sample 1.8
18A	18.1					55.5	56.6		54.8-56.7 discarded & Med. hd silt
19	19					55.6	56.1		clay (CL) dk gray w/ occasional thin laminae
19A	19.1					56.7	57.8		of gray silt (ML). 5-10% pebble gravel, rounded.
									Sample break w/ effort along silt laminae.
				57.4	58.2				Cleaned

BORING LOG **FIELD DATA**

Project _____		Site _____		Date _____	
Location _____		Job No. _____		Boring No. <u>6153</u>	
Drill Rig _____		Inspector _____		Operator _____	
Surface El _____					

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
20				58.2	59.8	58.2	59.0	Dennison 511	Drive 1.6 Sample 1.4
21	59.0			59.0	59.6	59.0	59.6		Fine silty dk gray dense sand w/ trace gravel. (SM) from 59.0-59.6. S.H. clayey sand (SC) from 58.2-59.0, compressed in tube. Sample also displaced to near.
				59.8	60.0	59.8	60.0	Fishtail	Cleaner
22				60.0	61.0	60.0	60.3	Dennison 511	Short bit related as above. Drive 1.0, Sample 1.0
22A						60.9	61.0		Gray hd dense silt (ML) w/ occasional gravel (<5%) and fine sand laminae, disturbed 60.4 to 61.0. From 60.0-60.9 in fine silty sand SM-SC. Contact is sharp. Sample ended badly, could not run two disturbed.
				61.0	61.5	61.0	61.5	5 1/2" Rockbit	Cleaner Much gravel

BORING LOG **FIELD DATA**

Project _____		Site _____		Date _____	
Location _____		Job No. _____		Boring No. <u>WES-3</u>	
Drill Rig _____		Inspector _____		Surface El <u>609.8</u>	
Operator _____					

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
23				61.5	63.9	61.5	62.5	Denison bbl	Long bit, 10 ft. 10 ft. 10 ft. Soft at 62.6
23A						62.5	62.6		Run. 2.0 Drive 2.4 Interbedded
24						62.6	63.4		Very fine sand, well sorted (SP) at 2.2 sand
24A						63.4	63.5		Very silt, firm to soft, dense (ML), all
									all to H. gray. Two tube samples mixed
									in very good condition. No gravel.
				63.9	64.4				Loose sand at 64.4'
				64.4	66.8			200 lb	Rotary long bit as above. Drive 2.4 sample
									Drive fast (soft soil). Lost sample in hole. Recovered
									ref split spoon to sample. Soil so loose it would
									not stay in split spoon. Probably v. loose sand
									(SP) as noted in TB boring 4 and 5. Recovered
									split spoon various strengths
				66.8	67.0			Test hole	Clear

Sheet 7 of _____ Sheets

BORING LOG FIELD DATA											
Project _____		Site _____		Date _____							
Location _____		Job No. _____		Boring No. <u>WES-3</u>							
Drill Rig _____		Inspector _____		Operator _____		Surface El _____					
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	lbs pres.	CLASSIFICATION AND REMARKS	
		FROM	TO	FROM	TO	FROM	TO				
				67.0	67.5			3" Hossley	500	Pushed 3" tube in loose sand	
				67.5	68.0				600	Chute slipped at 68.9, at 68.7. Recover only	
25				68.0	68.5				660	1" of sample v. loose noncohesive fine gr.	
				68.5	69.0				670	uniform sorted glz sand (SP). Very int.	
26				69.0	69.1				740	Went in w/ 2" split spoon to retrieve sample	
				69.1	69.5			Fail			
27				69.5	71.9	69.5	69.9	Denison bbt	200 lb	Installed 5" tube w/ spring steel retention.	
28						70.2	70.6			Rotated w/ long bit, bypassing water. Still	
29						70.7	70.9			Soft or loose. Dmr 2.9 mm. 1.9. Sample	
										recovered but in poor condition. Took 3 jar	
										samples, no mixed tubes. V. wet, cohesionless	
										well sorted glz sand (check sand) (SP), fine	
										grained. Very uniform throughout. Positive reaction	
										to dilatancy test.	
				71.9	72.0			Fin		Cleanest	

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. WES-3

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER		CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
30				72.0	72.5	72.0	73.0	3' Horseshoe	510	5" tubes will not hold material well enough.
				72.5	73.0	-			690	Running 3" Drive 1.9 sample 1.1
30A				73.0	73.5	73.0	73.1		690	Sample left in steel tube, disturbed when breaking
				73.5	73.9				794	down sampler v. loose wet sand 50 cm
										above v. fine grained. This stratum is
										getting finer w depth. No gravel.
				73.9	74.0					
31				74.0	76.1	74.4	76.0	Penison bbl		Rotating w. cathead Kept sampler vertical
31A						76.0	76.1			when breaking down, capped both ends before
										logging down. A little harder at 76.1. Drive
										2.1. Recore 1.7, left in 5" steel tube. Moved
										top, plugged bottom. Sample appears in good
										condition. 0.4' unaccounted for. Possibly washed
										away from top
				76.1	77.0			1" light		Cleaned

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	lbs per ft	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
32	5/2/80			77.0	79.4	79.0	79.4	Densison 661	240	Rotating 5" tube with lance boring bit and casing. Drive 2.4, recover 0.4'. Probably, skirted out. Replacing long bit w/ short bit on res drive. SP same as above.
				79.4	80.0			Cleanout		
				80.0	81.4			Densison 661		Drive 1.4. Rotated tube w/ catcher, for clean.
33								JAR		Recover only 0.3'. Probably, skirted out.
				81.4	82.0			Final		Cleanout
34	5/2/80			82.0	82.5	82.0	84.2	3" Hoarier	400	Pushed 3" tube. Drive 2.3, sample 2.3
				82.5	83.0				510	Fine grt sand, sorted (SP) (beach sand)
				83.0	83.5				580	as above. Not quite as fine grained as above.
				83.5	84.0				650	Loose, wet. Saturated green
34A				84.0	84.3	84.2	84.3		700	JAR
				84.3	85.0			Final		Cleanout

BORING LOG FIELD DATA

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. WES-3

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
35				85.0	86.5	85.0	86.9	3" HVBORSLV	Down 2.0 - Sample 2.0
				85.5	86.0				U. fine sorted quartz sand (SD) co above
				86.0	86.5				Loose, v. wet, cohesive
35A				86.5	87.0	86.5	87.0		
									Using small tubes because they hold sample well.
				87.2	87.5				Load under permeability of 80.0 is with 1.0
									cleaning out.
36	5/3/80	87.2		87.5	88.0	87.5	88.7	3" HVBORSLV	Pushed 3" tube. Down 1.5, recover 1.4
				88.0	88.5				Uniform gray qtz silt (ML), dense compact.
36A				88.5	89.0	88.7	88.9		but easily friable - (low cohesion). Same
									stratum co above, fine v. depth
				89.3	89.5			Fishtail	Clearer [STRATUM CHANGE]
37		89.3		89.5	90.0	89.5	89.7	3" HVBORSLV	Down 0.7 recover 0.5. Clayey gravelly
38				90.0	90.2	90.1	90.2		fine to med sand, well graded gravel 20%.
									up to 1/2" diam., rounded pebbles firm to hdy,
									w/ good cohesion. (SC)

[illegible]

FORM 819
JAN 74
EDITION OF NOV 1971 MAY BE USED

LID OF TUBE IS BOTTOM


BORING LOG FIELD DATA									
Project		DETROIT SEWER		Site		Date		Job No.	
Location		STA 112+81, 18 FT E of		LLCV 606.3		Operator		Surface El	
Drill Rig		Failing 1500		Inspector		MURPHY		Boring No. WES 4	
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
1	9/22	0.0	0.2	0.0	0.5	0.0	0.9	5" I.D. Shelly	140 S.T
1A		0.2	1.65	0.5	1.0	0.9	1.0	JAR	170
2		1.65	2.4	1.0	1.5	1.0	1.9	5" I.D. Shelly	170 S.T
2A				1.5	2.0	1.9	2.0	JAR	245
				2.0	2.35				520
				2.35	3.0			6" Fish tail	
3		2.5	5.0	3.0	3.5	3.0	4.2	Moorslow	225 Tube
3A				3.5	4.0	4.2	4.3	JAR	250
4				4.0	4.5	4.3	5.3	Moorslow	350 Tube
"				4.5	5.0				360
4A				5.0	5.35	5.3	5.35	JAR	425
								6" Fish tail	
				5.35	6.0				
5A		6.0	6.9	6.0	6.5				75
				6.5	7.0	6.6	6.7	JAR	140
5		6.9		7.0	7.5	6.9	8.3	Hoover	180 Tube

WES FORM JAN 74 819 EDITION OF NOV 1971 MAY BE USED

Sheet 1 of 1 Sheets

AD-A096 440 ARMY ENGINEER WATERWAYS EXPERIMENT STATION VICKSBURG--ETC F/G 13/2
15 MILE ROAD/EDISON CORRIDOR SEWER TUNNEL FAILURE STUDY, DETROIT--ETC((
JAN 81 D ALBERT, G C HOFF, B LORENCE NCE-IA-80-055
UNCLASSIFIED WES/TR/GL-81-2 NL

4 of 5
84-140



BORING LOG FIELD DATA

Project _____		Site _____		Date <u>4/23/80</u>	
Location _____		Job No. _____		Boring No. <u>WES-4</u>	
Drill Rig _____		Inspector _____		Operator _____	
		Surface El _____			

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
<u>6A</u>				7.5	8.0				gravelly, med. coarse stained sand (tube sample broke along two of these sand strings)
				8.0	8.4	8.3	8.4	JAR	
				8.4	9.0	—	—	Fishtail	Note G.O. to 6.9 is wk. gravelly clay that caved in hole when we came out
									No sample #16
	<u>4/23/80</u>								
									clean out to 9.0. Quick gel mud.
<u>7</u>				9.0	9.5	9.0	10.1		TOBE Dk gray clay w/ gravel < 5% (CL CH)
<u>7A</u>				9.5	10.0	10.1	10.2	UAR	Soft, 9.0-10.2, disturbed when extracted w/ wet
<u>8</u>				10.0	10.5	10.2	11.3	TOBE	Stiff, 10.2-11.9, in good condition
				10.5	11.0				
<u>8A</u>				11.0	11.4	11.3	11.4	JAR	
				11.4	12.0				
								Fishtail	— CLC AMOIT
									Push 2.4, 1' shaker, sample only 1.4
<u>9</u>				12.0	12.5	12.0	13.3	HWDR	Dk gray stiff CLCH clay, 58 gravel (note)
				12.5	13.0				Sample broke, intro at 12.6.

BORING LOG FIELD DATA

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
				13.0	13.4	13.3	13.4	HVORSLV	CLAY breaks along horizontal, rough plane
9A				13.4	14.0			FISHTAIL	1/4" thick when broken by hand (bedding). Dry sample
10		14.0	16.0	14.0	14.5	14.1	15.2	HVORSLV	very well stratified (varved), w/ much v. fine gravel (see jar)
10A				14.5	15.0	15.2	15.3	JAR	CL cement to 14.0, taper hole
11				15.0	15.5	15.3	16.2	TUBE	0.1 STICKUP CL-CH Gray sticky clay
14		16.0	20.9	16.0	16.3	16.2	16.3	JAR	w 10% gravel @ 1/8" diam.
									Gritty sandy clay (CL-CH) w/ pebble-
									sized gravel 10% or clayey sand (SC)
									Very sandy
				16.3	18.0			FISHTAIL	CL-CH UNIT
				18.0	19.5				
				18.5	19.0				Lost sample from tube. Remount Hovorslar sampler, used 2" split
				19.0	19.5				spoon to recover sample. Pushed spoon.
11B				19.5	20.0	18.5	18.8	SPLIT SPOON PUSHED	JAR Gritty sandy clay w/ gravel as above, very sandy

BORING LOG **FIELD DATA**

Project _____		Site _____		Date _____	
Location _____		Job No. _____		Boring No. _____	
Drill Rig _____		Inspector _____		Operator _____	
		Surface Elevation _____			

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
	A 123			20.0	20.4				
				20.4	20.8			FISHTAIL	CLEANOUT
12		20.9		20.9	21.5	21.0	21.9	Hudson 5"	TUBE Material hard to push. Refused at 22.3
12A				21.5	22.0	21.9	22.0	Left 0.3 in hole	JAR V. stiff dk gry clay (CL/CH) w/ occasional small gravel
				22.0	22.3				5% gravel. Breaks along hor. planes w/d difficulty
				22.3	23.2			Fish tail	Cleanout
13				23.2	26.3	25.3	26.3	Densim bowl	Rotating to drive sample (5" tube) 600 lbs
13B						25.1	25.3	"	HA stiff clay CL-V. little small gravel
13A						26.12	26.3	"	130 lbs larger gravel up to 1 1/4" round pebbles
									Ran 600 lbs pressure while rotating
				26.3	27.0			Fish tail	Clean out

[illegible]

WES FORM 819
EDITION OF NOV 1971 MAY BE USED

BORING LOG **FIELD DATA**

Project _____		Site _____		Date _____	
Location _____		Job No. _____		Boring No. WES 4	
Drill Rig _____		Inspector _____		Operator _____	
Surface El _____					

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
16	4/24			32.5	33.0				
				33.0	35.4	33.0	33.9	Denison bbl	Rotate w/ carbide bit. Hddk grey clay
						33.9	34.0		stiff (CL) w/ <5% gravel to 1"
									Lost water in this drive (33-35')
									Modified bit to place mouth of tube below hole
									of bit
									Cement
				35.4	36.0				
17				36.0	38.4	36.0	37.2	Denison bbl 6" bit	Hd stiff dk grey clay (CL) w/ 5% gravel
17A						37.2	37.3		to 3/4" diam.
				38.4	39.0	-	-	Fishtail	Cement. Bbl returned to 38.4 (0.5
									stickup. So drive 1.8)
18				39.0	40.6	39.0	39.6	Denison bbl	Drive 1.8 ft. hd. Fish tail went back in to 40.6
18A						39.6	39.7		Sample 1.3. Hd grey clay CL w/ some gravel to
19						39.7	40.2		2 diam. Sand stringers to 1/2" thick occasionally

Sheet **6** of _____ Sheets

BORING LOG **FIELD DATA**

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
19A	1/24					40.2	40.5	Denison bbl	JMR Sample broke at 39.7, so tubed two samples.
				40.8	41.5			Fishtail	
			40.2						
		40.2		41.5	43.9			5" Horseshoe	Drove 2.4 Softer, lost sample. In sand.
				41.3	43.7			" "	No resistance - No sample. (Sand)
				43.7	44.9			Fishtail	Cleaned to 44.5
20				44.9	45.0	44.7	45.8	5" Horseshoe	Drove 1.3 lost 0.1 in hole
20A				45.0	45.8	45.8	45.9		Dk grey clayey fine sand (sc), soft, uncemented.
				45.5	46.0				w/ 20% gravel 1/8-3/4" diam.
				46.0	46.5				Large gravel refilled pushed tube

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER		CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
21				46.5	48.6	46.5	47.4	Denism bbl	Tube	6" Castalloy bit Drive 2.1 Percussive
21A						47.4	47.5		Log	Dk grey firm gravelly sand 20% gravel
22						47.5	48.2		Tube	up to 24" (rounded with) from clay in
22A						48.2	48.3		Log	matrix (SP or SC)
										Drive 2.1 sample 1.8, left 3 in hole
										Sample broke into short lengths because of large gravel
				48.6	49.0			Fish tail		Clear sand
23				49.0	51.4	49.0	49.9	Denism bbl	Tube	Drive slowly Sample to 49.5, then soft clay
23A (X)						49.4	50.0		Log	23A not representative of 23 (X)
24						50.0	51.4		Tube	Dk grey hd clay w 5% gravel (CL)
24A						51.4	51.8		Log	(CONTACT clay sand in #23 @ 49.5')
				51.4	52.0			Fish tail		Clear sand
25				52.0	54.4	52.0	53.0	Denism bbl	Tube	Drive 2.1 recover 1.4 lost 1.0' @ 53.1-54.1
25A						53.0	53.1		Log	Had dk grey clay CL w 5-10% gravel

Sheet 5 of 5 Sheets

WES FORM 819 EDITION OF NOV 1971 MAY BE USED 54.1 54.3
 26 JAN 74 54.3 54.4
 26A

BORING LOG FIELD DATA


Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Lbs pres.	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				60.5	62.9	Lost sample		Denison bbl	40	Rotated slowly w/ carbide bit. Lost sample when pulled out. Will try pushing w/ 3" tube
29				62.8	63.3			3" Hydraulic		Pushed to refusal. Hld grey gritty clay CL
29A				63.3	63.35			Jar		63.0-63.3? probably sand 62.8-63.0
				63.6	64.4			Fishtail		Cleaned
30				64.0	65.9			Denison bbl	780	Rotated w/ carbide bit. Let tube strike w/ 1/2"
30A				65.0	65.1			Jar		Just keth. Fine silty light-med grey sand, occasional gravel < 5/16 (SM) Sample in good condition. Drove 1.95 sampled 1.1 foot 0.8'
				65.9	66.5			Cleanout		Fishtail
31				66.5	68.2					Drove 1.7 uniform fine grey sand (SP) soft
31A				66.5	66.9			Jar		Sample 0.4. Sample soft

BORING LOG **FIELD DATA**

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. WES 4

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	lbs pres.	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
32				69.0	69.5	69.0	70.0	3" Horseshoe	480	Pushed 3" tube in soil. Drive 1.3, sample 1.1
32A				69.5	70.0	70.0	70.1		620	Fine uniform gray gtz. sand (SP) no gravel
				70.0	70.3				800	Probably beach sand (well sorted, uniform)
				70.3	70.5			Fishtail		Cleaned
34				70.5	70.9	70.5	70.9	3" Horseshoe		Drive 0.4 refusal, Same as above
				70.9	71.8			Fishtail		(SP)
35	4/26			71.8	73.1	71.8	72.0	Denison bbl	780	1" Grabbing bit. Drive 1.3 sample 0.4
										V. soft uniform fine sand (SP) sample 0.4
										too disturbed to max in tube. Jar only.
				73.1	73.5	-	-	Fishtail		Cleaned
36				74.5	76.4	74.5	76.3	3" Horseshoe	440	Pushed 3" tube Same as above SP soft
36A						76.3	76.4		640	Drive 1.9 refusal 1.9
									700	
									740	



BORING LOG **FIELD DATA**

Project _____										Date _____	
Location _____										Job No. _____	
Drill Rig _____										Boring No. <u>WES-4</u>	
Inspector _____										Surface El _____	
Operator _____										Site _____	

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
									<u>Clearcut</u>
37	4/26			76.4	77.0	-	-		Drive 1.9 sample 1.8. Same as above
				77.0	78.9	77.0	78.7	3" Horseshoe	fine uniform grey qtz sand (SP)
				77.5	78.0				
37A				78.0	78.5	78.7	78.8		
				78.5	78.9				
				78.9	79.7	-	-	Fishtail	<u>Clearcut</u>
38				79.7	80.2	79.7	80.7	3" Horseshoe	Drive 1.2, chisel slipped, could not redrive
				80.2	80.7				Soft sand, fine (SP) becoming gradually to
38A				80.7	80.9	80.7	80.8		Very fine sand at bottom. Graduated firing of
									sand toward bottom. Recover 1.1 Drive 1.2
				80.9	81.5			Fishtail	<u>Clearcut</u>

Sheet 12 of _____ Sheets

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. WES 4

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER			CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO				
39				81.5	82.0	81.5	82.7	3" Horseshoe	470	Steel tube	Drive 1.4 Revs. 1.3 Very fine gray
				82.0	82.5				730		soft uniform fine sand (SP) [break same]
39A				82.5	82.9	82.7	82.8		790	Jar	Progressively finer w/ depth indicating off log or
									Return		refraction of 1st level w/ time.
				82.9	83.5			Fishtail			Clearcut
40				83.5	84.0	83.5	84.7	3" Horseshoe	350	Steel tube	Drive 1.3 Revs. 1.3
				84.0	84.5				680		Soft gray uniform silt (ML). Graduated
40A				84.5	84.8	84.7	84.8		800	Jar	Change from very fine sand above.
									Return		
				84.8	85.0			Fishtail			Clearcut
41				85.0	85.5	85.0	86.8	3" Horseshoe	250	Tube	Drive 1.9' - SPL 1.9
				85.5	86.0				480		Soft gray uniform silt (ML) or very fine
41A				86.0	86.5	86.8	86.9		700	Jar	sand (SP).
				86.5	86.8				810		

[illegible]

WES FORM 819
JAN 74
EDITION OF NOV 1971 MAY BE USED

BORING LOG FIELD DATA

Project <u>STURMUNG HEIGHTS SEWER</u>		Site <u>EDISON CORRIDOR</u>		Date <u>12 MAY 80</u>	
Location <u>STATION 126+87 AND 27' EAST OF SEWER CENTER LINE</u>		Job No. <u>441-621010CR21</u>			
Drill Rig <u>FALLING</u>		Inspector <u>J. DUNBAR</u>		Operator <u>B. HARRIS</u>	
		Surface El <u>608.5 (MSL)</u>		Boring No. <u>NES-5-80</u>	

SAMPLE NUMBER	LOGO DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	PREST CONT	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
	5/12	0.0		0.0	37.0			6 1/4" FISH TAIL		CLEANOUT - DUMP RUNS TO
			23.5							APPROX. 28.5' WHERE COLL
										OF DRILLING FLUID CHINNETED
										FROM BLACK TO GRAY.
	5/13				37.0			6 1/4" FISH TAIL		CLEANOUT
								DENISON BOX		OBSTRUCTION AT 9.0' - PULL OUT
					0.0	12.0		5 3/4" LUX BITE		CLEANOUT
					1.0	10.0		3" CURING		STICKUP 12' DENISON
					10.0	37.0		6 1/4" FISH TAIL		CLEANOUT
1	5/13			37.0	39.4	37.6	38.5	DENISON BOX	2.00	TUBE CLEAN - GRAY IN COLOR, MED. HARD, STIFF,
1A						38.5	35.0			WITH 5 1/2" SPINER (REMOVED ON 1/2" DIA.)

BORING LOG FIELD DATA									
Project _____		Site _____		Date _____					
Location _____		Job No. _____		Boring No. <u>WES-5-80</u>					
Drill Rig _____		Inspector _____		Operator _____		Surface El _____			
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
									2nd Low Plasticity (CL) - E _u : 1.707
									100% ² Silt & clay in 3' section
									CLEANOUT - KEEP LASING DRILLING
									FLUID TO GARBAGE DUMP AND PLUGGIN
									FISHTAIL
									SPURUP 0.8' DEPTH: 24.2
									CLEANOUT - LASING CIRCULATION
									DRILLED DOWN TO MAKE ROOM
									FOR ANOTHER SECTION - NO CLEANOUT
									PUSH.
									SPURUP 0.8' DEPTH 34.2'

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. WES - 5-80

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Press. Out.	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				—	46.0	✓		6 1/4" Fish Tail	✓	CLEANOUT
				41.0	42.4	✓		DENISON Bbl	✓	NO SAMPLE. PIECE OF CURTICE BLANKED OFF Bbl. SOME "JUNK"
										INTERIAL INDICATES CLAY.
				42.4	43.0	✓		FISH TAIL	✓	CLEANOUT
2	5/14	28.5		42.4	44.8	42.9	44.7	DENISON Bbl.	200 S.T.	
2A	5/14					44.7	44.8		JAR (SC) SINGLY CLAY - GRAY IN COLOR	
										SOFT MODERATELY STIFF, LOW PLAST., AND CONTAINS APPROX 5% F.F. WE
										GRAVEL RUN 2.4 SPL. 1.8' - DRILL
										INTERIAL INDICATES SOFT/CLAYING
										INTERIAL..
				44.8	45.0	✓		FISH TAIL	✓	CLEANOUT

BORING LOG FIELD DATA											
Project		Site				Date					
Location		Inspector				Operator		Surface El		Job No.	
Drill Rig								608.5		WES-5-80	
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Press. Cont	CLASSIFICATION AND REMARKS	
		FROM	TO	FROM	TO	FROM	TO			(G.M.)	
3A	5/14		45.0	45.0	47.4	45.5	45.6	DEWISON B61	180	JAR	GRAVELLY SILT - GREY, SOFT, STIFF.
3	5/14	45.0				46.1	47.3			ST	LOW PLAST, AND CONTAINS GRINNEL
3B	5/14					47.3	47.4			JAR	(ROUNDED - 1/8 to 1/4" diam) - Rec 18'
											SPL 1.2' - TOP 0.5' CRACK OUT -
											DURING EXAMINATION! V. TOP OF
											SAT. WAS WASHED/FALLING.
4	5/14			48.0	50.4	48.0	49.1	DEWISON B61	280	ST	SILT - SAND IS PLASTIC EXCEPT
4A	5/14					49.1	49.2		400	JAR	NO GRINNEL WAS OBSERVED.
5				49.2	51.4	51.4	51.5	DEWISON B61	100	JAR	SAND - UNIFORM, V. FINE GRNT, GREY,
		49.2							200		MODERATE/LITTLE COHESION - SOL
											WASHED - REC 0.3 FT

BORING LOG FIELD DATA

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Surface El _____ Boring No. WES-5-80

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	PRESS CONT.	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				53.8	54.0	✓		FISHTAIL	✓	CLEANOUT.
										(CL)
6	5/14	54.0	54.2	53.7	54.2	53.7	54.8	3" Hvorslev	390 ST	CLAY - DENSE, V. HARD, DENSE,
6A	5/14	54.0	54.2	54.2	54.7	54.8	54.9		520 JAR	WITH 5' FINE GRAVEL, HARD
				54.7	54.9				800	LOW PLASTICITY - GRAVEL IS ROUNDED
				54.9	55.5	✓		FISHTAIL	✓	CLEANOUT.
				55.5	57.9	---		DENISON Bhl	304 to 500	LAST SPL. - HARD MATERIAL -
										CATCHERS BUSTED! SEE ABOVE
				55.5	58.9	---		DENISON Bhl	300	ALY - SAME AS ABOVE
7	5/14					57.7	58.8		to S.T	TOR 0.5' BELIEVE IS JUNK. SOL
7A	5/14					58.8	58.9		500 JAR	Should be regarded with caution.
				58.9	59.0	✓		FISHTAIL	✓	CLEANOUT

BORING LOG FIELD DATA

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. WES-5-80

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	PASS	CUT	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO				
8A	5/15		59.0	59.0	61.3	59.0	59.1	Denison Bbl.	300±	JAR	SAND (SP) - UNIFORM, FINE GRND,
8	5/15	59.0	61.3			59.1	61.2			ST	GREY IN COLOR, WITH LITTLE COARSE.
8B	5/15	59.0	60.5			61.2	61.3			JAR	- BOTTOM OF TUBE CONTAINS CLAY
		60.5	61.3								WHICH IS DENSE, V. HARD, LOW PI
											AND INTERBEDDED SAND STRINGERS.
				61.3	62.0			FISHTAIL	✓		CLEANOUT
											(ML)
9	5/15			62.0	64.4	62.0	63.5	Denison Bbl.	300±	ST	SILT - GREY IN COLOR, DENSE.
9A						63.5	63.6			JAR	MODERATELY HARD, V. PLAST.
											REC. 1.6'
				64.4	65.0			FISHTAIL	✓		CLEANOUT.
10	5/15		63.6	65.0	67.4	65.0	66.0	Denison Bbl.	200	ST	SAND (SP) - GREY IN COLOR, V. FINE
10A	5/15	63.6				66.0	66.1		350	JAR	GRND, UNIFORM, V. LITTLE TO NO
											COHESION.


BORING LOG
FIELD DATA

[illegible]

Sheet 7 of 7 Sheets

WES-S-80
6/21 to 7/2
114+25-12 E &.

Casing to 46.5'



Filled with sand to 35.0' & Grouted

**BORING LOG
FIELD DATA**

Project <u>Detroit Sewer Failure</u>		Site <u>15 Mile & Edison Corrid.</u>		Date <u>21 June 80</u>	
Location <u>Station 114+25 and first of 12.0'</u>		Job No. <u>441-2210.10621</u>		Boring No. <u>WES-9-80</u>	
Drill Rig <u>Failing</u>		Inspector <u>Unbar</u>		Operator <u>B. HURRER</u>	
		Surface El			

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
	6/21	0.0	35.5	0.0	36.8			5" Diam Rk Bit	CLEANOUT - LAST WINTER AT 35.0' - MUDDED UP SEVERAL TIMES TO RETURN CIRCULATION.
				0.0	36.0			8 3/4" Rk Bit	CLEANOUT - 8" CASING.
	6/21			0.0	33.3			8" CASING	TOTAL: 34.5 SICKUP 1.2
	6/28			0.0	33.3			5" FISH TAIL	CLEANOUT - LAST WATER BELOW QS.
#1	6/28	36.0		0.0	45.0			7 3/4" Rk Bit	CLEANOUT - RECOVERED SAMPLE OF CUTTINGS - SAND: FINE TO MED. GRND, UNK. SHAL, IC.
									OTZ., FC Mlg, Feldspars
				33.3	40.0			8" CASING	TOTAL 41.5' SICKUP 1.5'

Sheet 1 of 5 Sheets

BORING LOG
FIELD DATA

Project _____ Site _____ Date _____

Location _____ Job No. _____

Drill Rig _____ Inspector _____ Operator _____ Surface Elevation _____ Boring No. 485-9-60

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Blows / Cnt.	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				—	440	—	—	7 3/4" R.C. Bit	—	CLEANOUT - LAST WINTER BELOW CS
				400	435	—	—	8" Casings	—	TOTAL 44.5' STRIKEUP 10'
		400		—	450	—	—	7 3/4" R.C. Bit	—	CLEANOUT - LAST WINTER BELOW CS
#2	6/28	40.0	45.0	45.0	45.5	45.0	46.5	STANDARD SPLITSPON	3	JAR Silty Sand / Sand Silt - v. Fine grad
				45.5	46.0				14	grey in color, fairly cohesive
				46.0	46.5				10	and moderately dense, Sp/ml.
										Stratum depth is assumed
				46.5	47.4	—	—	7 3/4" R.C. Bit	—	CLEANOUT
				47.4	47.4			STANDARD SPLITSPON	✓	Silty Sand / Sandy Silt - see above
				49.4	49.5				1	
				43.5	45.4	—	—	8" Casings	—	TOTAL 46.5' STRIKEUP 0.9'

FORM 819
JAN 74
EDITION OF NOV 1971 MAY BE USED

Sheet 2 of 5 Sheets

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Blows/ft	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				—	51.0	—	—	7 3/4" Rock B.t.	—	Unknown
#3	6/28	50.75	51.0	51.0	51.5	51.0	52.5	STANDARD SPLITSPRON	4	Silty Sand - Fine grad, grey
		50.75	51.5	51.5	52.0				5	brown color, moderate cohesion,
		Assumed		52.0	52.5				8	"hard", and contains approx
										5% v. fine gravel (1/4 to 1/8"
										& angular sized fragments)
				52.5	56.8	—	—	7 3/4" Rk B.t.	—	Unknown - last 1.8' is unaccounted
										Material washed away. Clean out
										went to 55.0 ft
	6/28	54.7	56.8	57.3	58.0	59.3		STANDARD SPLITSPRON	✓	
		54.7	57.3	57.8					1	Silty Sand / Sandy Silt - Same as before
		Assumed		57.8	59.3				4	

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector _____ Operator _____ Surface El _____ Boring No. _____

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER		CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				59.3	60.0			4 1/2 Fish. 1	Black Cont	Cleanout - Pumpplugged/Blew check
#4	4/28	60.0	60.5	60.0	61.5			STANDARD SPLITSPON	2 JAR	Silty Sand - Fine grain, moderate cohesion, grey in color, and approx 5% V. Fine gravel (same as before).
		60.5	61.0						3	
		61.0	61.5						11	
								4 1/2 Fish. 1		Cleanout.
				61.3	62.0					
#5	4/28	62.0	62.5	62.0	63.5			STANDARD SPLITSPON	18 JAR	Silty Sand - V. Fine grain, uniform, grey, dense, & moderately cohesive.
		62.5	63.0						30	
		63.0	63.5						51	
				63.5	64.0			4 1/2 Fish. 1		Cleanout
#6	4/28	64.0	64.5	64.0	64.7			STANDARD SPLITSPON	36 JAR	Silty Sand - Same as above
		64.5	64.7						51	


Sheet 4 of 5 Sheets

[illegible]

FORM 819
JAN 74

WES-10-80 — STATION 113+25 ± 13' WEST OF TUNNEL &
3 JULY TO 4 JULY 1980

SPLITSPOON SAMPLES



BORING LOG FIELD DATA

Project <u>Stirling Heights Sewer</u>									
Location <u>Station 113+25 and 13 ft West of Q of Tunnel</u>									
Date <u>3 July 1980</u>									
Job No. <u>441-6210.106821</u>									
Drill Rig <u>FALLING</u> Inspector <u>J. DUNBAR</u> Operator <u>B. HAREDO</u> Surface Elevation <u>WES-10-80</u>									
SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO		
		0.0		0.0				8 3/4" Rock Bit	CLEANOUT - CLAY
									LARGE BOULDERS FROM 200± TO 230±'
		35±							SAND/SILT - WATER LOST AND RETURNED AT 35±'
					45.0				
1	7/3	45±		45.0	45.5	45.0	46.5	STANDARD SPLITSPOON	JAR SANDY SILT (M1) - GREY IN COLOR, MODERATE COHESION, WITH MODERATE MOISTURE, AND S7. V. FINE GRAINEL, LOW PLASTICITY
				45.5	46.0			30	
				47.25	46.0	46.5		23	
					46.5	48.0		7 3/4" Rock Bit	CLEANOUT
2	7/3	47.25	(Assumed)	48.0	48.5	48.0	49.5	STANDARD SPLITSPOON	JAR SILTY SAND (SP) GREY TO BROWN IN COLOR, MODERATE COHESION, MOISTURE (MODERATE), FINE GRAINED, UNIFORM
				48.5	49.0			29	
				50.25	49.0	49.5		48	+ 5% V. FINE GRAINEL

WES FORM 819 EDITION OF NOV 1971 MAY BE USED

Sheet 1 of 4 Sheets

BORING LOG
FIELD DATA

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector J. DUNN Operator B. HARRIS Surface El. _____ Boring No. WES-10-80

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER		CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO			
				49.5	51.0			7 3/4" Rock Bit	Blues Cont	CLEANOUT
3	7/3	50.25 (Assumed)	51.0	51.0	51.5	51.0	52.5	STANDARD SPLIT SPOON	18 JAR	CLAY ~ BROWN IN COLOR, V. HARD, DENSE, WITH 5% V. FINE GRAVEL.
				51.5	52.0				38	
				52.0	52.5				30	LOW PLASTICITY, DRY
				52.5	54.6			7 3/4" Rock Bit		CLEANOUT
4	7/4			54.0	54.5	55.2	55.5	STANDARD SPLIT SPOON	3 JAR	CLAY ~ SAME AS ABOVE. LAST
				54.5	55.0				6	WATER & FLUSHED TOP OF
				55.0	55.5				8	SPL AWAY IN CLEANOUT.
				55.5	57.0			7 3/4" Rock Bit		CLEANOUT
5	7/4	56.25 (Assumed)	57.0	57.0	57.5	57.0	58.5	STANDARD SPLIT SPOON	7 JAR	Silty SAND ~ V. FINE, UNIFORMED,
				57.5	58.0				14	CRY SAND, MODERATE COHESION,
				58.0	58.5				12	AND MODERATE MOISTURE.

BORING LOG **FIELD DATA**

Project _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector DUNBAR Operator B. MERR Surface Elevation _____ Boring No. WES-10-80

SAMPLE NUMBER	DATE TAKEN	STRATUM		DRIVE		SAMPLE		TYPE OF SAMPLER	Blows	CONT.	CLASSIFICATION AND REMARKS
		FROM	TO	FROM	TO	FROM	TO				
				58.5	60.0			7 3/4" Rock B.	—	—	CLEANOUT
6	7/4			60.0	60.5	60.0	61.5	STANDARD SPLITSPON	8	JAR	CLAY + SAND ~ ON LAP - OFF LAP
				60.5	61.0				30		ALTERNATING LAMINA OF CL & SA
				61.0	61.5				25		GRAY BROWN IN COLOR ~ BREAKS
											ACC ALONG SANDY AREAS ~ Same as ABOVE
											MAJORITY IS SAND.
				61.5	63.0			7 3/4" Rock B.	—	—	CLEANOUT
7	7/4			63.0	63.5	63.0	64.5	STANDARD SPLITSPON	11		S. Hy SAND ~ Sand - 57. V. Fine
				63.5	64.0				25		GRAVEL
				64.0	64.5				26		
				64.5	66.0			7 3/4" Rock B.	—	—	CLEANOUT
8	7/4			66.0	66.5	66.0	67.5	STANDARD SPLITSPON	7	JAR	S. Hy SAND ~ V. Fine SAND, CLEAN
				66.5	67.0				17		UNIFORM, DENSE, SAND, MOD. CEMENTATION

Project _____ Site _____ Date _____
 Location _____ Job No. _____
 Drill Rig _____ Inspector J. DUNBAR Operator B. HARRIS Surface El _____
 Boring No. WES-10-86

[illegible]

Sheet 4 of 4 Sheets


FORM 819
JAN 74
EDITION OF NOV 1971 MAY BE USED

UNIFIED SOIL CLASSIFICATION

	Special	Notes
GRAVEL, heavy Graded gravel sand mixtures little or no fines	GM	
GRAVEL, heavy Graded gravel sand mixtures, little or no fines	GP	
Silty GRAVEL, gravel sand mixtures	GM	
CLAYEY GRAVEL, gravel sand mixtures	GC	
SAND, med. Graded gravel sands	SM	
SAND, heavy Graded, grave sands	SP	
Sandy SAND sand mixtures	SM	
CLAYEY SAND sand mixtures	SC	
Silt, clayey fine sand sily or coarse fine sand or clayey silt with slight plasticity	ML	
SAND, silty Sandey silt Silty Clay of low to medium plasticity	CL	
CLAY, silty Silty clay and argent silty clay of low plasticity	OL	
Silty clayey silt, sandy silt, silty clay with high plasticity	MM	
CLAY, silty Argent clay of high plasticity	CH	
CLAY, heavy Heavy clay of medium to high plasticity organic silt	OM	
Pt. silty and silty, highly organic to	PT	
Wd.	WD	
Silt	SI	
Sh	SH	

sigmat drozd jo tuc burzov 49 pizub sag otc 80% 6 om. jo s... 15-0-0. D. vstavat s onj f... .

DESCRIPTIVE SYMBOLS




THE UNIVERSITY OF CHICAGO


GENERAL NOTES:

[illegible]

SOILS BORING LEGEND

APPENDIX B
GRADATION CURVES







ENG FORM 2087 REPLACES WES FORM NO 1741, SEP 1962, WHICH IS OBSOLETE.


1 MAY 63


U.S. GOVERNMENT PRINTING OFFICE 1962 O-7-700-116





ENG FORM 1 MAY 83 2087



















PROJECT		DETROIT SEWER TUNNEL	
BORING NO.		WES-4	
SAMPLE NO.		25	
DEPTH/ELEV		- 52.0-53.0 DATE 01 JUL 90	
CLASSIFICATION			
SANDY CLAY (CL), GRAY			
GRADATION CURVE			













APPENDIX C
CONSOLIDATION TEST DATA



			BEFORE TEST	AFTER TEST	
OVERBURDEN PRESSURE, TSF			WATER CONTENT, %	12.4	12.3
PRECONSOL. PRESSURE, TSF			DRY DENSITY, PCF	125.0	127.5
COMPRESSION INDEX			SATURATION, %	92.5	100.0
TYPE SPECIMEN	UNDISTURBED		VOID RATIO	0.369	0.342
DIA. IN 4.44	HT. IN 1.121	BACK PRESSURE, TSF			
CLASSIFICATION CLAY (CL), BROWNISH GRAY, GRAVEL TO 1/4"					
LL 25	PL 13	PI 12	PROJECT DETROIT SLUR TUNNEL		
GS 2.74	COM	D ₁₀			
REMARKS			BORING NO WEC-3	SAMPLE NO 19	
			DEPTH/ELEV 55.1-55.5	DATE 06 JUN 90	
			CONSOLIDATION TEST REPORT		

SHEET 1 OF 13




CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL

BORING WES-3 SAMPLE NO 19

DEPTH/ELEV 55.1-55.5 DATE 08 JUN 90

SHEET 2 OF 13




PROJECT DETROIT SEWER TUNNEL

CONSOLIDATION TEST TIME CURVES

BORING WES-3 SAMPLE NO. 19

DEPTH/ELEV 55.1-55.5 DATE 08 JUN 90


SHEET 3 OF 13



CONSOLIDATION TEST
TIME CURVES

PROJECT DETROIT SEWER TUNNEL	
BORING MEC-3	SAMPLE NO 19
DEPTH/ELEV 55.1-55.5	DATE 06 JUN 90

SHEET 4 OF 13




CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL

BOPING WES-3 SAMPLE NO. 18

DEPTH/ELEV 55.1-55.5 DATE 05 JUN 90

SHEET 5 OF 13




CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL

BORING	WES-3	SAMPLE NO	19
DEPTH/ELEV	55.1-55.5	DATE	06 JUN 80

SHEET 5 OF 13




CONSOLIDATION TEST TIME CURVES

PROJECT: GATPOIT SEWER TUNNEL

RODING: W-2-B SAMPLE NO. 13


DATE: JUL 55 10:00 AM 1955

SHEET: 7 OF 13



CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL			
BORING	WES-3	SAMPLE NO.	19
DEPTH/ELEV	55.1-55.5	DATE	24 JUN 86
SHEET 9 OF 13			




CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL

BORING WES-3 SAMPLE NO 18
DEPTH/ELEV SS.1-SS.5 DATE 06 JUN 90

SHEET 9 OF 13




CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL

BORING WES-3 SAMPLE NO. 19


DEPTH/ELEV SS.1-55.5 DATE 06 JUN 80

SHEET 10 OF 13




PROJECT DETROIT SEWER TUNNEL		CONSOLIDATION TEST	
		TIME CURVES	
BORING	WES-3	SAMPLE NO.	18
DEPTH/ELEV	55.1-55.5	DATE	06 JUN 80

SHEET 11 OF 13




PROJECT DETROIT SEWER TUNNEL		CONSOLIDATION TEST	
		TIME CURVES	
BORING	WES-3	SAMPLE NO.	18
DEPTH/ELEV	55.1-55.5	DATE	06 JUN 80

SHEET 12 OF 13




PROJECT DETROIT SEWER TUNNEL		CONSOLIDATION TEST	
		TIME CURVES	
BORING	WES-3	SAMPLE NO.	18
DEPTH/ELEV	55.1-55.5	DATE	06 JUN 80

SHEET 13 OF 13




SHEET 1 OF 13




PROJECT DETROIT SEWER TUNNEL	
CONSOLIDATION TEST	
TIME CURVES	
BOBING MES-4	SAMPLE NO. 12
DEPTH/ELEV 21.5-21.9	DATE 06 JUN 90

SHEET 2 OF 13




PROJECT DETROIT SEWER TUNNEL		CONSOLIDATION TEST	
		TIME CURVES	
BORING	WES-4	SAMPLE NO.	12
DEPTH/ELEV	21-S-21-9	DATE	06 JUN 90

SHEET 3 OF 13



PROJECT DETROIT SEWER TUNNEL	
CONSOLIDATION TEST TIME CURVES	
BORING WES-4	SAMPLE NO. 12
DEPTH/ELEV 21.5-21.9	DATE 06 JUN 90
SHEET 4 OF 13	




CONSOLIDATION TEST TIME CURVES


PROJECT DETROIT SEWER TUNNEL

BORING MES-4 SAMPLE NO. 12

DEPTH/ELEV 21.5-21.9 DATE 06 JUN 80

SHEET 5 OF 13






PROJECT DETROIT SEWER TUNNEL

CONSOLIDATION TEST TIME CURVES

BORING WES-4 SAMPLE NO. 12

DEPTH/ELEV 21.5-21.9 DATE 06 JUN 80

'MEE' 7 OF 13




CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL

BORING WES-4 SAMPLE NO. 12

DEPTH/ELEV 21.5-21.9 DATE 06 JUN 80

SHEET 9 OF 13




CONSOLIDATION TEST TIME CURVES


PROJECT DETROIT SEWER TUNNEL

BORING WES-4 SAMPLE NO. 12

DEPTH/ELEV 21.5-21.9 DATE 06 JUN 80


SHEET 9 OF 13





PROJECT DETROIT SEWER TUNNEL	
CONSOLIDATION TEST	
TIME CURVES	
BORING WES-4	SAMPLE NO. 12
DEPTH/ELEV 21.5-21.9	DATE 06 JUN 90

SHEET 11 OF 13




CONSOLIDATION TEST TIME CURVES

PROJECT DETROIT SEWER TUNNEL

BORING WES-4 SAMPLE NO. 12

DEPTH/ELEV 21.5-21.9 DATE 06 JUN 80

SHEET 12 OF 13




CONSOLIDATION TEST
TIME CURVES


PROJECT DETROIT SEWER TUNNEL		
BORING MES-4	SAMPLE NO. 12	
DEPTH/ELEV 21.5-21.9	DATE	06 JUN 90

SHEET 13 OF 13

APPENDIX D
DIRECT SHEAR TEST DATA



$\phi = 26.5^\circ$
 $\tan \phi = 0.50$
 $c = 0.15 \text{ TSF}$



TEST NO.		1 Δ	2 γ	3 X
INITIAL	WATER CONTENT, %	14.5	14.0	13.3
	VOID RATIO	0.391	0.331	0.377
	SATURATION, %	100 +	93.0	100 +
	DRY DENSITY, PCF	124.7	123.9	125.1
VOID RATIO AFTER CONSOL				
FIFTY PERCENT CONSOL, MIN		< 1	< 1	< 1
FINAL	WATER CONTENT, %	14.2	14.9	13.9
	VOID RATIO			
	SATURATION, %			
NORMAL STRESS, TSF		1.0	2.0	3.0
MAXIMUM SHEAR STRESS, TSF		0.57	1.09	1.69
TIME TO FAILURE, MIN		251	757	1570
RATE OF STRAIN, IN/MIN		0.0019	0.0019	0.0019
ULTIMATE SHEAR STRESS, TSF				

TYPE SPECIMEN UNDISTURBED 3.00 IN. SQUARE 0.594 IN. THICK

CLASSIFICATION SANDY CLAY (CL), GRAY, GRAVEL TO 1/2"


LL 22 PL 11 PI 11 GS 2.76

REMARKS. PROJECT DETROIT SEWER TUNNEL


BORING NO. WES-3 SAMPLE 9

DEPTH/ELEV 41.1/42.1 DATE 05 JUN 90

DIRECT SHEAR TEST REPORT





$\phi = 24.0^\circ$
 $\tan \phi = 0.44$
 $c = 0.10 \text{ TSF}$



TEST NO.		1 Δ	2 γ	3 \times
INITIAL	WATER CONTENT, %	29.3	32.1	30.3
	VOID RATIO	0.787	0.779	0.790
	SATURATION, %	100 +	100 +	100 +
	DRY DENSITY, PCF	95.7	96.1	95.5
VOID RATIO AFTER CONSOL				
FIFTY PERCENT CONSOL. MIN		2	< 1	< 1
FINAL	WATER CONTENT, %	32.2	27.0	29.9
	VOID RATIO			
	SATURATION, %			
NORMAL STRESS, TSF		0.5	1.0	2.0
MAXIMUM SHEAR STRESS, TSF		0.32	0.59	0.94
TIME TO FAILURE, MIN		214	302	214
RATE OF STRAIN, IN/MIN		.00019	.00019	.00019
ULTIMATE SHEAR STRESS, TSF				

TYPE SPECIMEN UNDISTURBED		3.00 IN. SQUARE		0.594 IN. THICK	
CLASSIFICATION CLAY (CL), GRAY; TRACE OF SILT					
LL 32	PL 19	PI 14	GS 2.74		
REMARKS.			PROJECT, DETROIT SEWER TUNNEL		
			BORING NO. WES-4		
			SAMPLE 9		
			DEPTH/ELEV 10.2/11.3		
			DATE 24 JUN 80		
DIRECT SHEAR TEST REPORT					



$\phi = 30.5^\circ$
 $\tan \phi = 0.59$
 $c = 0.08 \text{ TSF}$

TEST NO.		1 Δ	2 Y	3 X
INITIAL	WATER CONTENT, %	15.5	14.4	14.3
	VOID RATIO	0.396	0.377	0.375
	SATURATION, %	100 +	100 +	100 +
	DRY DENSITY, PCF	122.9	124.6	124.9
VOID RATIO AFTER CONSOL				
FIFTY PERCENT CONSOL, MIN		< 1	4	3
FINAL	WATER CONTENT, %	17.4	15.2	15.9
	VOID RATIO			
	SATURATION, %			
NORMAL STRESS, TSF		0.5	1.5	2.5
MAXIMUM SHEAR STRESS, TSF		0.37	1.05	1.44
TIME TO FAILURE, MIN		396	350	536
RATE OF STRAIN, IN/MIN		.00019	.00019	.00019
ULTIMATE SHEAR STRESS, TSF				

TYPE SPECIMEN UNDISTURBED 3.00 IN. SQUARE 0.594 IN. THICK

CLASSIFICATION CLAY (CL), GRAY; MED. SAND TO FINE GRAVEL


LL 31 PL 16 PI 15 GS 2.75

REMARKS: PROJECT DETROIT SEWER TUNNEL

BORING NO. WES-4 SAMPLE 13

DEPTH/ELEV 25.3/26.2 DATE 27 JUN 90


DIRECT SHEAR TEST REPORT



$$\phi = 28.5^\circ$$

$$\tan \phi = 0.54$$

$$c = 0$$



TEST NO.		1 Δ	2 γ	3 X
INITIAL	WATER CONTENT, %	15.5	15.2	16.9
	VOID RATIO	0.349	0.344	0.341
	SATURATION, %	100 +	100 +	100 +
	DRY DENSITY, PCF	126.9	127.3	127.5
VOID RATIO AFTER CONSOL				
FIFTY PERCENT CONSOL. MIN		2	2	2
FINAL	WATER CONTENT, %	15.9	13.7	12.9
	VOID RATIO			
	SATURATION, %			
NORMAL STRESS, TSF		2.0	3.0	4.0
MAXIMUM SHEAR STRESS, TSF		0.99	1.59	2.15
TIME TO FAILURE, MIN		901	961	928
RATE OF STRAIN, IN/MIN		.00019	.00019	.00019
ULTIMATE SHEAR STRESS, TSF				

TYPE SPECIMEN UNDISTURBED 3.00 IN. SQUARE 0.594 IN. THICK
 CLASSIFICATION SANDY CLAY (CL), WITH GRAVEL



LL 29 PL 12 PI 16 GS 2.74

REMARKS. PROJECT DETROIT SEWER TUNNEL

BORING NO. WES-4 SAMPLE 24

DEPTH/ELEV 50.0/51.1 DATE 02 JUL 90

DIRECT SHEAR TEST REPORT



$\phi = 33.5^\circ$
 $\tan \phi = 0.66$
 $c = 0$

TEST NO.		1 Δ	2 γ	3 \times
INITIAL	WATER CONTENT, %	10.5	11.7	11.3
	VOID RATIO	0.294	0.319	0.311
	SATURATION, %	99.5	100 +	99.6
	DRY DENSITY, PCF	132.5	130.2	130.9
VOID RATIO AFTER CONSOL				
FIFTY PERCENT CONSOL. MIN		3	3	3
FINAL	WATER CONTENT, %	12.5	11.7	11.5
	VOID RATIO			
	SATURATION, %			
NORMAL STRESS, TSF		1.0	3.0	5.0
MAXIMUM SHEAR STRESS, TSF		0.71	2.07	3.20
TIME TO FAILURE, MIN		549	606	639
RATE OF STRAIN, IN/MIN		.00017	.00017	.00017
ULTIMATE SHEAR STRESS, TSF				

TYPE SPECIMEN UNDISTURBED			3.00 IN. SQUARE		0.594 IN. THICK	
CLASSIFICATION SANDY CLAY (CL), GRAY, WITH GRAVEL;						
CONCRETIONS TO 1/2"						
LL 24	PL 12	PI 12	GS 2.75 (EST)			
REMARKS:			PROJECT DETROIT SEWER TUNNEL			
			BORING NO WES-4		SAMPLE 25	
			DEPTH/ELEV 52.0/53.0		DATE 07 JUN 80	
			DIRECT SHEAR TEST REPORT			

APPENDIX E

$K_o \bar{R}$ TEST DATA

K _o R UNDRAINED LOADING STAGE									
LINE NO. DETROIT SEWER, WES 3-19, SILTY									
LINE NO.	DEV STRESS	OXID. STRAIN	INDUCED PWP	EFFECT S _z	"a" PERCENT	EFFECT S _{1/3}	SETTLING "a" TSF	STRESS "p" TSF	RT C/L. OLV STR TSF
3	1.155	0.	0.	0.828	0.	2.492	0.610	1.446	1.435 ← End of K _o consol.
4	1.567	0.031	0.086	0.742	0.055	3.113	0.703	1.525	1.507
5	1.789	0.124	0.144	0.684	0.080	3.616	0.895	1.579	1.789
6	2.006	0.295	0.187	0.641	0.093	4.131	1.003	1.644	2.006
7	2.438	0.775	0.194	0.634	0.080	4.848	1.219	1.853	2.438
8	2.640	1.025	0.144	0.684	0.054	4.872	1.324	2.068	2.640
9	2.862	1.287	0.086	0.742	0.030	4.857	1.431	2.172	2.862
10	2.965	1.537	-0.029	0.807	-0.010	4.460	1.182	2.339	2.965
11	3.057	1.956	-0.351	1.159	-0.108	3.639	1.529	2.689	3.057
12	3.166	2.111	-0.596	1.224	-0.125	3.586	1.583	2.807	3.166
13	3.269	2.174	-0.410	1.236	-0.126	3.636	1.632	2.871	3.265
14	3.372	2.406	-0.504	1.332	-0.149	3.531	1.686	3.018	3.372
15	3.480	2.453	-0.518	1.346	-0.149	3.584	1.740	3.096	3.480
16	3.472	2.500	-0.518	1.346	-0.149	3.579	1.736	3.083	3.472
17	3.585	2.624	-0.590	1.418	-0.165	3.527	1.792	3.211	3.585
18	3.680	2.670	-0.598	1.426	-0.162	3.582	1.840	3.266	3.680
19	3.674	2.764	-0.670	1.498	-0.182	3.453	1.937	3.334	3.674
20	3.784	2.872	-0.684	1.512	-0.181	3.502	1.992	3.404	3.784
21	3.877	2.965	-0.698	1.526	-0.180	3.540	1.938	3.465	3.877
22	3.991	3.012	-0.747	1.577	-0.188	3.531	1.996	3.572	3.991
23	4.088	3.183	-0.792	1.620	-0.194	3.523	2.044	3.664	4.088

TEST NO: DETROIT SEWER, WES 3-24, SILTY K _o R UNDRAINED LOADING STAGE									
LINE NO	DEV STRESS	AXIAL STRAIN %	INDUCED PWP	EFFECT S 3	"A" PARAM	EFFECT SI/S3	SSTRESS "Q"	NSTRESS "P"	RT CYL DEV STR
	TSF		TSF	TSF			TSF	TSF	TSF
3	1.289	0.	0.	1.037	0.	2.243	0.644	1.681	1.289
4	1.407	0.016	0.036	1.001	0.026	2.406	0.703	1.704	1.407
5	1.525	0.032	0.072	0.965	0.047	2.580	0.762	1.727	1.525
6	1.628	0.063	0.094	0.943	0.058	2.726	0.814	1.757	1.628
7	1.749	0.095	0.108	0.929	0.062	2.884	0.875	1.804	1.749
8	1.852	0.126	0.115	0.922	0.062	3.010	0.926	1.848	1.852
9	1.976	0.173	0.115	0.922	0.058	3.144	0.988	1.910	1.976
10	2.078	0.205	0.108	0.929	0.052	3.237	1.039	1.968	2.078
11	2.199	0.252	0.101	0.936	0.046	3.349	1.099	2.035	2.199
12	2.304	0.284	0.094	0.943	0.041	3.442	1.152	2.095	2.304
13	2.419	0.315	0.079	0.958	0.033	3.527	1.210	2.167	2.419
14	2.521	0.347	0.065	0.972	0.026	3.593	1.260	2.232	2.521
15	2.747	0.425	0.029	1.008	0.010	3.725	1.374	2.382	2.747
16	2.858	0.457	0.007	1.030	0.003	3.776	1.429	2.459	2.858
17	2.976	0.488	-0.007	1.044	-0.002	3.851	1.488	2.532	2.976
18	3.080	0.520	-0.029	1.066	-0.009	3.891	1.540	2.606	3.080
19	3.192	0.551	-0.050	1.087	-0.016	3.936	1.596	2.683	3.192
20	3.426	0.614	-0.101	1.138	-0.029	4.012	1.713	2.851	3.426
21	3.653	0.662	-0.151	1.188	-0.041	4.075	1.827	3.015	3.653
22	3.850	0.725	-0.194	1.231	-0.050	4.127	1.925	3.156	3.850
23	4.086	0.772	-0.245	1.282	-0.060	4.188	2.043	3.324	4.086
24	4.313	0.835	-0.302	1.339	-0.070	4.220	2.156	3.496	4.313
25	4.514	0.882	-0.346	1.382	-0.077	4.265	2.257	3.639	4.514
26	4.737	0.930	-0.396	1.433	-0.084	4.306	2.368	3.801	4.737
27	4.968	0.977	-0.446	1.483	-0.090	4.350	2.484	3.967	4.968
28	5.197	1.024	-0.504	1.541	-0.097	4.373	2.599	4.139	5.197
29	5.397	1.071	-0.547	1.584	-0.101	4.407	2.699	4.283	5.397

End of
K_o
consol.


SITE: DETROIT SEWER, WES 4-24, CLAYEY											
K ₀ R UNDRAINED LOADING STAGE											
STRESS TSF	AXIAL STRAIN %	INDUCED PWP TSF	EFFECT S 3 TSF	"A" PARAM	EFFECT SI/S3	SSTRESS "Q" TSF	NSTRESS "P" TSF	RT CYL			
								DEV STR	TSF		
3	1.811	0.	1.303	0.	2.390	0.906	2.209	1.811	←	End of	
4	1.937	0.016	1.253	0.026	2.546	0.969	2.222	1.937		K ₀	
5	2.044	0.090	1.274	0.014	2.604	1.022	2.297	2.044		consol.	
6	2.146	0.128	1.231	0.034	2.743	1.073	2.304	2.146			
7	2.261	0.304	1.238	0.029	2.826	1.130	2.369	2.261			
8	2.364	0.415	1.202	0.043	2.966	1.182	2.384	2.364			
9	2.468	0.623	1.210	0.038	3.041	1.234	2.444	2.468			
10	2.567	1.006	1.246	0.022	3.061	1.284	2.529	2.567			
11	2.671	1.214	1.231	0.027	3.169	1.335	2.567	2.671			
12	2.761	1.565	1.282	0.008	3.154	1.381	2.662	2.761			
13	2.862	1.805	1.303	0.	3.196	1.431	2.734	2.862			
14	2.975	2.029	1.332	-0.010	3.233	1.487	2.819	2.975			
15	3.050	2.668	1.411	0.035	3.161	1.525	2.936	3.050			
16	3.145	2.891	1.440	-0.043	3.184	1.573	3.013	3.145			
17	3.234	3.435	1.505	-0.062	3.149	1.617	3.122	3.234			
18	3.343	3.432	1.505	-0.060	3.222	1.672	3.176	3.343			
19	3.443	3.610	1.541	-0.069	3.234	1.721	3.262	3.443			
20	3.602	4.888	1.692	-0.108	3.129	1.801	3.493	3.602			
21	3.700	5.048	1.721	-0.113	3.150	1.850	3.571	3.700			
22	3.787	5.335	1.771	-0.124	3.138	1.893	3.664	3.787			

DETROIT SEWER, WES 4-30, SILTY $K_o \bar{R}$ UNDRAINED LOADING STAGE											
LINE NO	DEV STRESS TSF	AXIAL STRAIN %	INDUCED FWP TSF	EFFECT S 3 TSF	"A" PARAM	EFFECT SI/S3	SSTRESS		NSTRESS		RT CYL DEV STR TSF
							"Q" TSF	"P" TSF			
3	2.071	0.	0.	1.505	0.	2.377	1.036	2.540		2.071	
4	2.110	0.016	0.014	1.490	0.007	2.416	1.055	2.545		2.110	
5	2.214	0.032	0.050	1.454	0.023	2.522	1.107	2.561		2.214	
6	2.322	0.048	0.079	1.426	0.034	2.629	1.161	2.586		2.322	
7	2.429	0.064	0.108	1.397	0.044	2.739	1.215	2.611		2.429	
8	2.538	0.096	0.137	1.368	0.054	2.855	1.269	2.637		2.538	
9	2.645	0.129	0.151	1.354	0.057	2.954	1.323	2.676		2.645	
10	2.751	0.161	0.166	1.339	0.060	3.054	1.375	2.715		2.751	
11	2.862	0.193	0.173	1.332	0.060	3.149	1.431	2.763		2.862	
12	2.962	0.241	0.173	1.332	0.058	3.224	1.481	2.813		2.962	
13	3.077	0.273	0.173	1.332	0.056	3.310	1.539	2.871		3.077	
14	3.183	0.321	0.166	1.339	0.052	3.377	1.592	2.931		3.183	
15	3.282	0.353	0.158	1.346	0.048	3.438	1.641	2.987		3.282	
16	3.395	0.402	0.144	1.361	0.042	3.495	1.698	3.059		3.395	
17	3.499	0.434	0.137	1.368	0.039	3.557	1.749	3.117		3.499	
18	3.599	0.466	0.122	1.382	0.034	3.604	1.800	3.182		3.599	
19	3.718	0.514	0.108	1.397	0.029	3.662	1.859	3.256		3.718	
20	3.813	0.546	0.094	1.411	0.025	3.702	1.907	3.318		3.813	
21	3.921	0.578	0.079	1.426	0.020	3.751	1.961	3.386		3.921	
22	4.021	0.610	0.058	1.447	0.014	3.778	2.011	3.458		4.021	
23	4.134	0.643	0.043	1.462	0.010	3.829	2.067	3.529		4.134	
24	4.248	0.675	0.022	1.483	0.005	3.864	2.124	3.607		4.248	
25	4.349	0.707	0.	1.505	0.	3.890	2.175	3.679		4.349	
26	4.446	0.739	-0.022	1.526	-0.005	3.913	2.223	3.750		4.446	
27	4.563	0.771	-0.043	1.548	-0.009	3.947	2.281	3.829		4.563	
28	4.606	0.787	-0.050	1.555	-0.011	3.962	2.303	3.858		4.606	
29	4.696	0.803	-0.065	1.570	-0.014	3.992	2.348	3.918		4.696	
30	4.774	0.819	-0.079	1.584	-0.017	4.014	2.387	3.971		4.774	
31	4.873	0.851	-0.101	1.606	-0.021	4.035	2.437	4.042		4.873	
32	4.987	0.884	-0.122	1.627	-0.025	4.065	2.494	4.121		4.987	
33	5.084	0.900	-0.144	1.649	-0.028	4.083	2.542	4.191		5.084	
34	5.190	0.932	-0.173	1.678	-0.033	4.094	2.595	4.273		5.190	
35	5.290	0.964	-0.194	1.699	-0.037	4.113	2.645	4.344		5.290	
36	5.397	0.996	-0.216	1.721	-0.040	4.136	2.699	4.419		5.397	
37	5.501	1.012	-0.245	1.750	-0.045	4.144	2.750	4.500		5.501	
38	5.620	1.044	-0.266	1.771	-0.047	4.173	2.810	4.581		5.620	
39	5.719	1.076	-0.288	1.793	-0.050	4.190	2.860	4.652		5.719	

APPENDIX F
OVALLING MEASUREMENTS


PCI-7 STATION 133+50

$u/r = 0.0406$




PCI-7 STATION 132+50

$u/r = 0.8741$




PCI-7 STA 131+00

$w/r = 0.0232$




PCI-7 STA 130+00

$w/r = 0.0212$




PCI-7 STA 128+50

w/r= 0.0186




PCI-7 STA 127+50

$w/r = 0.0761$ °




PCI-7 STA 126+25

$w/r = 0.0141$




PCI-7 STA 124+00

$w/r = 0.0186$




PCI-7 STA 121+00

$w/r = 0.0206$




PCI-7 STA 118+55

$w/r = 0.0221$



PCI-7 STA 118+00

$w/r = 0.0181$



AD-A096 440 ARMY ENGINEER WATERWAYS EXPERIMENT STATION VICKSBURG--ETC F/6 13/2
15 MILE ROAD/EDISON CORRIDOR SEWER TUNNEL FAILURE STUDY, DETROIT--ETC(1
JAN 81 D ALBERT, G C HOFF, B LORENCE NCE-IA-80-055
UNCLASSIFIED WES/TR/GL-81-2 NL

5th
5

END

DATE


FILED

4 25 1

DTIC


PCI-7 STA 115+00

w/r= 0.0228




PCI-7 STA 114+75

w/r= 0.0308




PCI-7 STA 114+50

$w/r = 0.0522$




PCI-7 STM 114+25

$w/r = 0.0713$




PCI-7 STA 114+00

w/r= 0.0659




PCI-7 STA 113+75

w/r= 0.0361




PCI-7 STA 113+50

w/r= 0.0249




PCI-7 STA 113+25

w/r= 0.8344




PCI-7 STA 113+00

$w/r = 0.0238$




PCI-7 STA 112+75

w/r = 0.0180




PCI-7 STA 112+50

$w/r = 0.0143$ s.




PCI-7 STA 112+25

$w/r = 0.0297$




PCI-7 STA 112+00

w/r= 0.0400




PCI-7 STA 111+75

w/r= 0.0287...




PCI-7 STA 111+50

w/r= 0.0203.




PCI-7 STA 111+25

$w/r = 0.0157$




PCI-7 STA 111+00

w/r= 0.0217



PCI-7 STA 110+75

$w/r = 0.0237$



APPENDIX G

COMPUTER PROGRAM FOR RESISTANCE COMPUTATION

```

2000 REM DIMENSIONLESS SUBROUTINE FOR PLAIN CONCRETE MOMENT
2010 REM THRUST CURVATURE INTERACTION
2020 REM INPUTS: THRUST P      TENSILE STRENGTH T
2030 REM OUTPUT: MOMENT M      CURVATURE F
2040 REM SCRATCH: NEUTRAL AXIS DEPTH C
2050 REM          CUBIC EQN ITERATION C4,C6,P4,P5,P6
2060 IF P<2/3 THEN 2110
2070 C=1/SQR(3*(1-P))
2080 M=1/(12*C*C)
2090 F=1/C
2100 GO TO 2330
2110 IF P<(8-3*T*T)/(6*(2+T)) THEN 2160
2120 C=(3*(2-P)-SQR(9*(2-P)^2-12))/2
2130 M=(2/C-2*C+C*C)/12
2140 F=1/C
2150 GO TO 2330
2160 DEF FNP(C)=T*(-T*C*C*C-12*C*C+18*C-6)/(12*(1-C)^2)
2170 C4=0.5
2180 P4=FNP(C4)
2190 C6=2/(2+T)
2200 P6=FNP(C6)
2210 C=C4+(P-P4)*(C6-C4)/(P6-P4)
2220 P5=FNP(C)
2230 IF ABS(P5-P)<1.0E-3 THEN 2310
2240 IF P5<P THEN 2280
2250 P6=P5
2260 C6=C
2270 GO TO 2210
2280 P4=P5
2290 C4=C
2300 GO TO 2210
2310 M=T*(4-4*C-2*T*C^3+T*C^4)/(48*(1-C)^2)
2320 F=T/(2*(1-C))
2330 RETURN

```

In accordance with letter from DAEN-RDC, DAEN-ASI dated 22 July 1977, Subject: Facsimile Catalog Cards for Laboratory Technical Publications, a facsimile catalog card in Library of Congress MARC format is reproduced below.

Albert, Dick

15 Mile Road/Edison Corridor Sewer Tunnel Failure Study, Detroit Area, Michigan / by Dick Albert ... [et al.]. (Geotechnical Laboratory. U.S. Army Engineer Waterways Experiment / U.S. Army Engineer District, Detroit) ; prepared for Environmental Protection Agency, Region 5. -- Vicksburg, Miss. : U.S. Army Engineer Waterways Experiment Station; Springfield, Va. : available from NTIS, 1981.

185, [212] p. : ill. ; 27 cm. -- (Technical report / U.S. Army Engineer Waterways Experiment Station ; GL-81-2)

Cover title.

"January 1981."

1. Field control tests (Soils). 2. Laboratory tests. 3. Structural behavior. 4. Tunnel failures. I. United States. Army Engineer Waterways Experiment Station. Geotechnical Laboratory. II. United States. Army. Corps of Engineers, Detroit District. III. United States. Environmental Protection Agency, Region 5. IV. Title. V. Series: Technical report (United States. Army Engineer Waterways Experiment Station); GL-81-2.

TA7.W34 no.GL-81-2

